


SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1907, by Munn & Co.]

Vol. XCVI.—No. 19.
ESTABLISHED 1845.

NEW YORK, MAY 11, 1907.

[10 CENTS A COPY
\$3.00 A YEAR.



A THEATER AUDITORIUM WITH A ROTATABLE FLOOR PERMITTING OF ITS CONVERSION INTO A DANCING HALL.—[See page 391.]

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO. - Editors and Proprietors

Published Weekly at
No. 361 Broadway, New York

TERMS TO SUBSCRIBERS

One copy, one year, for the United States or Mexico.....\$3.00
 One copy, one year, for Canada.....3.75
 One copy, one year, to any foreign country, postage prepaid, \$0 16s. 5d. 4.00

THE SCIENTIFIC AMERICAN PUBLICATIONS

Scientific American (Established 1845).....\$3.00 a year
 Scientific American Supplement (Established 1876).....3.00
 American Homes and Gardens.....3.00
 Scientific American Export Edition (Established 1878).....3.00
 The combined subscription rates and rates to foreign countries, including Canada, will be furnished upon application.
 Remit by postal or express money order, or by bank draft or check.
 MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, MAY 11, 1907.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

THE PERIL OF THE DERELICT.

The safeguards of science and good engineering have been thrown so carefully around the transatlantic passenger, that travel by sea is decidedly safer than travel by land. One by one the perils of the deep have been removed or so far controlled that the chances of a passenger who embarks at New York, setting foot safely and unhurt, and within a few days' time, on European soil are shown by statistics to be so many millions to one. The risk of collision has been largely eliminated by the selection of separate specified lines of travel to which the ships can, and do, adhere with wonderful accuracy. Even should collision occur, the vessels are so minutely subdivided that the damage is localized and foundering is a remote possibility. Wireless telegraphy, submarine bells, improved sirens, and many ingenious and effective devices, combine to guide a transatlantic liner to port with an accuracy, which can only be impaired by negligence or carelessness, happily very rare, on the part of the navigating staff.

There is one menace of the deep, however, which, from its very nature, can never be controlled. It may lurk in the path of any unsuspecting vessel, unheralded, scarce detectable by day, quite invisible by night—a menace which may be created by any storm that blows. We refer to the derelict, or the partially submerged hull of a vessel that has been wrecked and abandoned on the high seas. Until a derelict has been sighted and reported by some passing vessel, its very existence is unknown, and even after it has been reported and ships have been warned as to its whereabouts and probable course, its place on the chart can be only approximately determined. While daylight lasts, if a sharp lookout be kept, a ship may sight the semi-submerged craft in time to avoid collision; but by night the question of hitting or missing is one of the merest chance. The only safeguard against the derelict is to find and destroy it; and from time to time the government, on being notified of the existence of dangerous floating wrecks, details a warship to search for and blow up or sink them.

Shipping men on both sides of the Atlantic have been much gratified by the announcement that the Treasury Department is asking for bids for the derelict destroyer which was authorized by the last Congress. This vessel, which is to be stationed on the North Atlantic, will embody the latest improvements in craft of her kind, and will be capable of cruising for five thousand miles without replenishing her bunkers. She will be furnished with powerful searchlights and a wireless telegraph equipment, the latter to enable her to receive and give information as to the location of derelicts. She will be provided with an ammunition room stored with high explosives for sinking and blowing to pieces floating hulls and wreckage; provision being made, as in warships, for flooding the magazines in an emergency. The derelict destroyer will also be furnished with an equipment designed to assist her in salvage and life saving work, for which her size and the fifteen hundred horse-power of her engines will render her highly efficient.

THE LIMITS OF HEAVY ELECTRIC TRACTION.

The progress of the electrification of the terminals and the suburban service of the New York Central and Pennsylvania Railroads has advanced to a point where it becomes possible to make some definite statements as to cost and practicability. Enough has been learned to make it certain, in the minds of some of the engineers associated with the carrying out of the work, that the field of electric traction on steam roads will, for the present at least, be a limited one. Such, at any rate, is the view of Mr. George Gibbs, Chief Engineer

of the Electrical Division of the Pennsylvania, New York, and Long Island Railroad, as announced at a recent meeting of the New York Railroad Club.

At present our trunk-line service is worked by heavy and comparatively infrequent train units; and unless the introduction of electric traction increases the capacity of the lines and builds up new business, and the savings in cost are such as to pay for its introduction, Mr. Gibbs believes that its use is "neither logical nor probable." In the first place, it appears that the cost of installing electric traction on steam railway lines has been almost invariably underestimated. In addition to the cost of equipping the line with its purely electrical features, it is necessary, because of that equipment, to make very serious changes in the structure and equipment of the road; so much so, that in some cases these amount to a practical rebuilding of the line. So great are these incidental expenses, that the purely electrical features involved in changing a railroad from steam to electric traction amount, under average conditions, to from one-half to two-thirds of the total cost. From the above statements and others of a like character which have appeared of late in the technical press, it would seem that the remarkable efficiency shown on the electrified elevated roads in this city caused both steam railroad men and electrical engineers to jump to somewhat hasty conclusions as to the economy that would be realized by applying electric traction to trunk lines for long-distance service. As a matter of fact, Mr. Gibbs is of the opinion that electric traction cannot at present be made to show sufficient economy over steam in trunk-line service to justify its wholesale introduction. He states that the public has little idea of the very high cost of inaugurating electric traction. To the railway engineers who have looked into the question with the idea of making the change of motive power, the figures have been "positively staggering."

The experience thus far gained indicates that the introduction of electricity on steam railroads will be confined, for the present at least, to large city terminals where, by abolishing a large amount of the switching, the daily capacity for trains will be greatly increased. It will also be applicable to those sections of the mountain divisions on which the heavy grades occur, provided always that either water power or cheap fuel is available. The electric locomotive, because of its great tractive power, is particularly suited to the handling of trains over heavy grades, and it will prove to be exceedingly valuable in increasing the weight of the ruling trainloads over any given division.

According to this authority the time is far distant when we shall be ready to discard the steam locomotive even to an appreciable extent for heavy, long-distance freight and passenger service. Moreover, he makes the rather startling announcement that when the time does come, it will be brought about through a radical change in methods from any of those heretofore advanced. All of this must not, however, be taken to indicate that any doubt is thrown upon the success of the work which is now being carried out on the New York Central and Pennsylvania Railroads. The benefits in comfort, cleanliness, speed, and safety which were aimed at, undoubtedly will be fully realized; but for the present at least it is probable that the electric zone on the respective roads will not be extended beyond the limits of the more remote suburban service.

TURBO-ELECTRIC ENGINES FOR SHIPS?

The reciprocating steam engine has apparently reached the limit of its efficiency in the propulsion of ocean-going ships. The present indications are that the marine engine of the future will be either the steam turbine or the perfected producer-gas engine; with a strong probability that the latter, because of its excellent fuel economy, will be the preferred type.

There is, however, a third system of propulsion which theoretically, at least, has so much to recommend it that we should not be surprised to see it given a trial in one of the larger ships. We refer to the use of a turbo-electric plant of the same general character as that which is giving such excellent service in stationary power houses ashore. As installed in the engine room of a large steamship the system would consist of steam turbines, direct-connected to electric generators, the current from which would operate motors directly coupled upon the propeller shafts. Although at the first blush this looks like a complication of parts, the advantages derived in the increased efficiency both of the turbines and the propellers, to say nothing of other gains, would under certain conditions render such a plant superior to the present direct turbine drive. This will be evident from the following considerations:

If the turbines on an ocean liner are run at the high speed of revolution which gives the best steam efficiency, this speed will be too great for the propellers. On the other hand, there is a certain maximum speed, beyond which propellers suitable to the propulsion of a large ship cannot be driven efficiently. From the horns of this dilemma the naval architect has

sought escape by the only road open to him—that of compromise. Consequently, in the largest turbine-propelled ships of to-day, the turbines are too large and heavy and too slow, and the propellers are too small and running too fast to give their respective best results.

The conflicting requirements of the turbine and the propeller may be harmonized by the interposition between them of the electric generator. This can be done by using small, high-speed, steam turbines direct-connected to generators, these turbo-generators being run at the speed which gives the most economical results. From the generators, current would be led to motors, whose type and speed of revolution would be accommodated to the propellers on the outboard end of the respective shafts. It is evident that by this arrangement both at the steam end and the propeller end the designer would have a perfectly free hand, and in shape, size, speed, etc., he would be able to design directly for the work to be done and, therefore, for the highest efficiency results. Of course, in a plant of this kind there would be a certain loss in the conversion from steam to electric power; but this has been reduced to such a low figure, that it would be more than offset by the increased efficiency of the turbines and propellers and by the great reduction in the sizes and weights of the turbines.

Incidentally there would be various valuable advantages secured. It would be possible, in the case of warships, to cruise at low speed economically, and it would be no longer necessary to provide separate cruising turbines. It would be possible to reverse immediately; and the go-astern turbines would, therefore, also be eliminated. Furthermore, the steam turbines could be located quite independently of the position of the propeller shafts, and might be carried on an upper deck immediately above the propeller-shaft motors. We understand that the problem, as we have outlined it above, has been receiving careful consideration from some of the manufacturers of turbine and electric plants. The only discouraging feature, in any proposed experimental work that might be done, is that a comparative test, to be of any value, must necessarily be carried on in an ocean-going ship of the larger size, since it is only in the larger ships that the reduction of turbine speed becomes a serious drawback.

THE SPRING MEETING OF THE AMERICAN SOCIETY OF MECHANICAL ENGINEERS.

The spring meeting of the American Society of Mechanical Engineers will be held in Indianapolis, Indiana, from May 28 to May 31. The headquarters room will be on the parlor floor of the Claypool Hotel, and the professional sessions on the top floor on the south side of the building.

The official headquarters will be opened in the Claypool Hotel at noon on Tuesday, May 28, and maintained throughout the meeting.

The opening session will take place on Tuesday evening, May 28, at 9 o'clock, in the auditorium of the Claypool Hotel. An address of welcome will be delivered, with response by Frederick Remson Hutton, president of the society. The second session will be called to order on Wednesday morning, May 29, at 9:30 o'clock. This will be a business session, devoted to the reading of reports of the tellers of election of members and vote on amendments and reports of standing and special committees. The more important reports to be considered will be those of the committee on Standard Proportions for Machine Screws; preliminary report of the committee on Refrigerating Machines; Collapsing Pressures of Lap-Welded Steel Tubes (Reid T. Stewart); The Balancing of Pumping Engines (A. F. Nagle); A Comparison of Long and Short Rotary Kilns (E. C. Soper).

An automobile symposium will be held with papers on "Bearings and Moving Mechanism," by Henry Hess; "Air Cooling of Automobile Engines," by John Wilkinson; "Materials for Automobiles," by Elwood Haynes; "Special Auto Steel," by T. J. Fay; "Railway Motor Car," by B. D. Gray.

The fourth session will be held on Thursday morning, May 30, at 9 o'clock, and the subject of Superheated Steam will be discussed. Papers on "The Specific Heat of Superheated Steam" will be read by A. R. Dodge; "Determination of Entropy Lines for Superheated Steam," by A. M. Greene; "The Flow of Superheated Steam in Pipes," by E. H. Foster; "Correlation of Furnace and Superheated Conditions," by R. P. Bolton; "The Heating of Storehouses," by H. O. Lacount.

On Friday morning, May 31, a professional session will be held at 10 o'clock in one of the Purdue University buildings. The following papers will be read: "Performance of Cole Superheaters," by W. F. M. Goss; "Experience with Superheated Steam," by G. H. Barrus; "Use of Superheated Steam in Locomotives in America," by H. H. Vaughan; "Superheated Steam in an Injector," by S. L. Kneass; "A Hirn's Analysis of Locomotive Test," by S. A. Reeve. Other papers are expected.

DEFLOCCULATED GRAPHITE AND THE "ACHESON EFFECT."

BY ORRIN E. DUNLAP.

Deflocculated graphite is the latest invention of E. G. Acheson, the discoverer of the processes for making carborundum and artificial or manufactured graphite. In the deflocculated condition produced by Mr. Acheson, graphite has a condition of fineness far beyond that attainable by mechanical means. In fact, its condition resembles, if not wholly approaches, the molecular state. The "effect," for such it must be termed, is produced with water and a comparatively small quantity of gallotannic acid, and when thus treated the unctuous graphite remains suspended in the water, showing not the slightest disposition to settle. The black liquid passes with ease through the finest filter paper. Severe tests have demonstrated that it is an admirable lubricant. There is every reason to believe that deflocculated graphite with or without oil will become a popular agent for all classes of lubrication, for, strange as it may seem, deflocculated graphite possesses the remarkable power of preventing rust or corrosion of iron or steel.

It was in March, 1891, while Mr. Acheson was experimenting in Monongahela City, Pa., that he discovered carborundum. Sixteen years ago he carried about in a small vial in his vest pocket all the carborundum he had been able to produce in two months. With this vial in his pocket, he hurried off to New York city to interest diamond cutters in his new product. To them he sold the contents of that vial at seventy cents a carat, receiving \$60 for all there was in the world. With this money he bought a microscope with which to study the structure of the carborundum crystals. Looking from his office window to-day, Mr. Acheson has a splendid view of the carborundum plant, and in the evening he notes that between 400 and 500 men leave it for their homes after passing the day in making carborundum and putting it in shape for sale throughout the world. It was in 1895 that commercial operations were begun in Niagara Falls, using 1,000 electrical horse-power, while to-day the works are equipped for 5,000 horse-power.

Mr. Acheson's vest pocket carries another little vial to-day, and in it is deflocculated graphite. Having given the world the hardest known abrasive, and thus advanced the art of abrasion, he has solved the problem of how to reduce the cost of lubrication.

Before the latter part of the sixties, petroleum oils were unknown, commercially, animal oils having been used for lubrication entirely. In the forty years that have passed, the world has seen a change from animal oils to mineral oils, and witnessed the growth and development of the wealthiest corporation in the world. To-day it is stated that the major part of the business of the Standard Oil Company is the manufacture not of illuminating oils, but of lubricating oils. The commerce and manufacturing of the world is guided by wheels operating in bearings, the important problem being to keep things running smoothly. No wars, no business depressions cause a cessation of the demand for lubricants.

It has been known for years that graphite is an excellent lubricating body, both in a dry state, and particularly when associated with oil, fats, or water. Strenuous efforts, extending over a long time, have been made to suspend graphite in a liquid to be used as a lubricant, but all these efforts were unsuccessful. It is a well-recognized fact among scientific men that plain water has many advantages as a lubricant if it had sufficient body to withstand the pressures brought to bear and to which lubricants are subjected. Its very high specific heat would be of great advantage to keep down the temperatures of bearings, while its low viscosity would reduce friction, but unfortunately it has not sufficient body to withstand the pressure of an ordinary bearing. It also has the fatal quality of rusting and corroding metals, thus making it absolutely worthless as a lubricant.

The "effect" which Mr. Acheson has discovered makes it possible not only to reduce graphite practically to the molecular state, and to cause it to remain suspended in water for an indefinite period of time, but also to prevent iron and steel from rusting or corroding while associated with water, thus rendering of advantage the high specific heat and low viscosity of water.

In 1901 Mr. Acheson engaged in a series of experiments having as their object the production of crucibles from artificial graphite. This led him to a study of clays, and he learned that American manufacturers of graphite crucibles import from Germany the clay used by them as a binder of the graphite entering into the crucibles; also that the German clays are more plastic and have a greater tensile strength than American clays of very similar chemical constitution, while residual clays—those found at or near the point at which the parent feldspathic rock was decomposed—are not in any sense as plastic or as strong as the same clays are when found as sedimentary clays at a distance from their place of origin. Chemical analysis failed to account for these decided differences.

Under these conditions Mr. Acheson reasoned that

the greater plasticity and tensile strength were developed during the period of transportation from the place of their formation to their final bed, thinking possibly it might be due to the presence of vegetable extractions in the waters which carried them. He made several experiments on clay with vegetable extracts, tannin being one of them, and found a moderately plastic, weak clay, when treated with a dilute solution of gallotannic acid or extract of straw, was increased in plasticity. Familiar with the record of how the Egyptians made the Children of Israel use straw in the making of bricks, and believing it was used not for any benefits derivable from the weak fibers, but for the extract, he calls clay so treated Egyptianized clay.

In 1906 Mr. Acheson discovered a process of producing a fine, pure, unctuous graphite. He undertook to work out the details of its application as a lubricant. In the dry form, or mixed with grease or oil, it was easy to handle, but he wished it to enter the entire field of lubrication as occupied by oil. In his efforts to suspend it in oil, he met the same troubles encountered by his predecessors in this line of work. It would quickly settle out of the oil. His unctuous graphite was just plain, simple graphite, and obeyed the same laws covering the natural product.

This was the condition of things in the latter part of 1906, when the thought occurred to him that tannin might have the same effect on graphite as it did on clay. He tried it with satisfactory results. The writer has seen most interesting experiments made with unctuous graphite of Mr. Acheson's manufacture, a graphite which may be termed disintegrated unctuous graphite.

To one sample of this graphite plain water was added, and after rubbing it in a mortar it was poured into a test tube.

To another sample of the graphite and water and a little gallotannic acid were added also a few drops of ammonia, this last being not absolutely necessary, but having been found to improve the result with some waters. This second mixture was rubbed in the mortar as in the first case, and then was poured into a second test tube. Both tubes and their contents were thoroughly shaken, and simultaneously placed in a rack to settle.

When about two minutes had elapsed after the shaking, it was found that the graphite in the plain water had very completely separated from the water, not being miscible therewith, while the mixture of water, graphite, tannin, and ammonia remained as black as when originally shaken up. The graphite was thoroughly suspended, and showed no disposition to settle or separate.

Next from a bottle containing a quantity of graphite, water, tannin, and ammonia, which had been mixed some weeks, as stated, a quantity was poured into a glass funnel containing one of the finest filter papers made in America. The deflocculated graphite ran through the fine filter paper and collected as black as ever in the tube below, apparently unchanged. Its passage through the paper was remarkably rapid, leaving no doubt but that it was thoroughly mixed; and in order to demonstrate that the black liquid was a mixture of water and a solid body—graphite—a few drops of hydrochloric acid were introduced into the test tube containing the mixture. This was slightly warmed over a spirit flame, causing the suspended graphite to flocculate, so that when the liquid was again poured into a filter paper, the water ran through clear, the graphite remaining on the paper. A small quantity of this graphite was removed from the filter paper and rubbed on another paper, where it was dried. Then a brisk rubbing with the finger brought out the full luster of the graphite. Mr. Acheson has obtained this effect with amorphous bodies generally, alumina, lamp-black, clay, graphite, and siloxicon, the only exception being magnesia, which needs further tests.

These were the conditions surrounding Mr. Acheson's experiments until the latter part of April. His success in deflocculating graphite and causing it to remain suspended in water was most gratifying, not only to himself, but to others who appreciated the wonderful possibilities of this magnificent new lubricant. However, Mr. Acheson realized that the world at large has been educated to the use of oil as a lubricant, and that it might be difficult to re-educate them to the use of water and graphite for a similar purpose until they better understood what he had accomplished. It was with this conviction that he undertook to solve the problem of replacing the water used as a conveyor of the deflocculated graphite with petroleum.

His first experiment, and probably the simplest and most rational, was to diminish the quantity of water by evaporation, leaving the graphite in a dry state, to be rubbed up later in oil. While this method produced what seemed to be an ideal result, it was soon discovered that in a comparatively short time the graphite had settled out of the oil, having lost its deflocculated condition and returned to its original flocculated state. Consequently, it was not in condition to remain suspended in oil, nor indeed was it

possible again to suspend it in water, a fact strange to record.

Notwithstanding this decided failure, and the apparently insurmountable difficulty associated with the problem, the desired result was eventually accomplished. The writer has witnessed the suspension of deflocculated graphite in water, has seen the water removed, and the deflocculated graphite suspended in oil and passed through the finest filter paper, remaining suspended thereafter in a most remarkable manner. In these circumstances, Mr. Acheson now feels assured that with his disintegrated unctuous graphite, which is guaranteed to contain less than one per cent impurity, and which can be mixed with oils or grease as may be desired for all specific uses; with his deflocculated graphite in water for the lubrication of steam-engine cylinders and other places and parts where the introduction of oils is objectionable; and with his deflocculated graphite in oil, the quantity carried by the oil to be varied to suit requirements of the most difficult lubrication, he can meet any demand for a lubricant where oil is preferable and evaporation of his water lubricant might be objectionable. It should be understood in this connection that the very lightest and thinnest of oils, when used in conjunction with deflocculated graphite, can be used in the place of the heavy and expensive lubricating oils of the present day, while the lasting qualities of these graphite lubricants will be greater by far than the oil lubricants heretofore used.

Automobile Notes.

The first of the great automobile races of the year—the Targa Florio—was run off on the 20th ultimo over a mountainous and rather rough course 450 kilometers (279.45 miles) in length on the island of Sicily. The race was for touring cars with racing bodies. It was won by Nazzaro on a 35-horse-power Fiat, with Lancia, on a car of the same make, second; Fabry, on an Itala, third, and Duray, on a De Dietrich, fourth. Nazzaro beat Lancia by 12 minutes, and won not only the cup but a cash prize of \$3,000 as well. His time was 8 hours and 17 minutes, corresponding to an average speed of 34 miles an hour. This was an excellent performance considering the roughness of the course.

The great English race for touring cars—the Tourist Trophy race—will be held for the third time on the Isle of Man on May 28. In this race, as heretofore, each car will be allowed a certain quantity of fuel with which to cover the course, the winner being the car that covers it the quickest on this allowance. Twenty-five miles on a British gallon is the distance which is required to be covered. Nearly all the great road races held abroad this year will be based on a limited fuel consumption or cylinder capacity.

In this connection it should be mentioned that plans are being made for a similar touring car race to be held on the new motor parkway on Long Island after the Vanderbilt cup race. It is proposed to limit the cars to a certain cylinder capacity. In addition to this, it would make the race much more interesting if they were also allowed a limited supply of fuel.

The chief touring event in America this year is to be conducted by the American Automobile Association in July. This will be the third annual contest for the Glidden trophy and will start from Cleveland on July 10. The route will be through Detroit and Lansing, Mich., to Chicago; thence south and east to Indianapolis, Columbus, Cincinnati, Pittsburg, Harrisburg, Philadelphia, and New York. It is proposed to have only noon and night controls, with two minutes leeway; also to require the cars to make a good average speed behind a pacemaker and not to allow them to use any spare parts except those they carry with them. Besides the Glidden trophy for touring cars (which will this year be awarded to the club which makes the best showing) a trophy has been offered for runabouts and will be awarded to the owner who makes the best performance with this style of car.

Oxford Honors for Prof. A. G. Bell.

Prof. Alexander Graham Bell has received the honorary degree of Doctor of Science from Oxford University, in recognition of his efforts to teach the deaf and dumb to speak, as well as for his invention of the telephone. The presentation was made on May 2 last by the dean of the faculty of science, Prof. A. E. H. Love.

The first American gas engine patent, No. 3,597, issued May 25, 1844, was granted to Stuart Perry, Newport, N. Y., for his two-cycle, double-acting, air-cooled gas engine. Perry proposed to inclose the cylinder and its immediate appendages in a case, through which cold air could be blown by means of a rotary fan or other blowing apparatus. Mr. Hugh Dolnar, in an article in the American Machinist, claims that Perry not only was the original inventor of both air and water cooling of gas-engine cylinders, but also was the first to devise a hot-tube ignition system, which was reinvented and patented many years later by Gottlieb Daimler.

AN AUTOMOBILE HEARSE.

A lugubrious automobile novelty in the form of a motor-driven hearse has recently made its appearance in the streets of Paris. A nation that rejoices in the grim delights of trolley-car funerals is hardly justified in shaking its head at this latest application of the electric auto. After all is said and done, no very good reason can be advanced why a man should not be buried in a ceremonious and somber motor hearse, particularly in these piping motor times, when touring cars filled with tearful mourners are not infrequently seen in funeral processions.

THE BLERIOT AEROPLANE.

BY THE PARIS CORRESPONDENT OF THE SCIENTIFIC AMERICAN.

M. Bleriot, a well-known Paris engineer, has lately re-entered the aeronautical field with an aeroplane of a new design. In its general lines it closely resembles a bird, with a central body, long tail and two large outspread wings, and it differs in many respects from the other flyers which have been brought out at Paris. Here there is but a single plane formed of the two flat wing surfaces. The skeleton frame of the apparatus is entirely covered in the present design, this frame being rigid as well as elastic. The general lines of the flyer are designed so as to give it as small a resistance in the air as possible, and to this end the covering is formed of a kind of parchment paper which is very efficient in reducing the air friction, owing to its polished surface. Some of the other arrangements of the flyer are quite ingenious. As will be noticed in the accompanying views, the body of the bird consists of a central portion which contains the motor and the aeronaut's seat in the front part, followed by a tail-like appendix which, like the rest, consists of a covered skeletal frame. The tail has the form of a quadrangular pyramid, tapering to a rather sharp point. At the rear end of the tail M. Bleriot has mounted the two rudders which control the flight, with the horizontal rudder consisting of a canvas-covered frame placed at the extreme end, while next it is the vertical rudder. Both the rudders are operated from the aeronaut's seat by means of universally-jointed rods connected to a single lever for both rudders. By working this lever, the rudders can be used together or separately as the pilot desires. Means are provided for changing the angle of the wings, and this is carried out by a lever which the pilot has placed between his knees. Thus either one of the wings can be raised or lowered at the desired angle, within certain limits. This will no doubt be a considerable aid in handling the flyer. One of the views shows the two wings folded up when the aeroplane is not in use, thus making it possible to occupy relatively small space when stored away. The form of the wings is also noticeable. They are somewhat

enlarged at the ends and are curved upward at the tip. At the base, the width of the wing is 2 meters (6 feet 7 inches), and the total spread of the wings is 7.50 meters (24 feet 8 inches). The surface of the aeroplane is 13 square meters (139.8 square feet) and the weight is 260 kgs. (573 lbs.). As to the motor, it is located in the front end of the middle frame, and is of the 24 horse-power Antoinette pattern, which we have already had occasion to describe. The propeller



AN ELECTRIC AUTOMOBILE HEARSE NOW IN USE IN PARIS.

is mounted in front on a short shaft, direct connected to the crank shaft. It is 1.6 meters (5¼ feet) in diameter. Two bicycle wheels are used to support the flyer on the ground. They are mounted on a common axle which is fixed to the middle part of the body.

The new flyer was recently put through its first experimental trials at the Bagatelle grounds in the suburbs of Paris, and these trials were quite remarkable in several respects. In the trial of April 5th the aeroplane was set in motion against a somewhat stiff breeze, with M. Bleriot piloting. After running for a few hundred feet on the ground, it rose to a height of two feet above the ground and was able to fly for a short distance, about twenty feet. But the aeronaut feared that it would be driven to one side by the wind, and so was obliged to bring it to the ground. What is brought out in this short flight is the general good performance of the apparatus and the small amount of power which is needed for flying, seeing that it has a motor of only twenty-four horse-power. In another

experiment it was found that the aeroplane could be made to leave the ground with its small carrying surface of 140 square feet, without even using the whole power of the motor, the actual amount being estimated at sixteen horse-power.


After the trial on April 5, during which the axle connecting the wheels was bent upon landing, M. Bleriot strengthened his machine somewhat and added a third small wheel at the end of the tail in case the latter should drag when the machine is leaving the ground. He also increased the size of the forward horizontal rudder and doubled the surface of the vertical rudder at the rear. In another trial on April 8 the machine rose off the ground slightly when the horizontal rudder was directed upward, but a gust of wind upset it.

Failure of Santos Dumont's Aeroplane.

After previously demolishing his new aeroplane in the first trial he made with it, Santos-Dumont, during the first week in April, refitted his 50-horse-power 8-cylinder motor to his old machine—"14bis"—with which he won the Arch-deacon cup for a flight of 220 meters last November. After waiting several days for good weather, he at length attempted to make a flight in a light wind of but 5 or 6 miles an hour velocity. He succeeded in getting the machine up in the air after a run of about 100 feet along the ground, but it showed great lack of stability and lurched from side to side. After flying less than 200 feet, the machine made a sharp turn and the left wing touched the ground. Santos-Dumont attempted to counteract the sudden turning of the machine by a quick movement of the rudder, with the result that the rudder struck the ground and the machine collapsed. Its intrepid pilot escaped unharmed by ducking down in the basket. This trial has demonstrated anew the instability of a machine of this type.

The Delagrangé aeroplane, on the other hand, in a trial on April 8, although it showed very good stability while in the air, was damaged when it struck *terra firma*. In this case, too, the slight wind that was blowing was said to have driven the machine forcibly to earth when the motor was stopped. The wheels and some of the tubes of the framework were broken. The flight was only 50 meters (164 feet) in length at a height of from 15 to 20 feet. A previous flight, on March 30, was 60 meters (196 feet) in length. In both instances the pilot, M. Voisin, cut off the ignition current and stopped the motor, fearing injury to the spectators.

While these experiments show that there are several machines in France capable of getting off the ground, and that this capability is confined to no one type,



Attaching the Wings to the Aeroplane Upon Its Arrival at the Testing Place.

The wings of this aeroplane are formed of parchment paper applied to a suitable framework.

THE BLERIOT AEROPLANE.



The Bleriot Aeroplane With Its Wings Outspread.

still they prove that the conquest of the air is not yet so near completion as some would suppose, and that there is much yet to be done before a successful flying machine will be evolved.

Razor Straps.

These are prepared from strips of linoleum of the usual length and width, left for 24 hours in a ¼ to ½ per cent. solution of hartshorn salt, to which 1½ per cent. of alum has previously been added, at the ordinary temperature; the strips are then dried at the normal temperature, rubbed with soap and polished with pumice stone. They are finally fastened in the usual manner to wooden handles. Straps made in this way will give a smooth sharp edge to the razor.

THE TALKING SIREN OF DR. MARAGE.

BY DR. ALFRED GRADENWITZ.

While many early inventors attempted to produce an apparatus which synthesized the elemental sounds used in talking and which imitated the human voice, the invention of the phonograph gave such experiments their quietus.

Despite the success of the phonograph, a French scientist, Dr. Marage, has constructed what may be described as a talking siren, that is, a siren which produces sounds that accurately imitate those of the various vowels both when sung and spoken.

In constructing this device, Dr. Marage intended primarily to design an apparatus for gaging the sharpness of the sense of hearing in different individuals. The "acoumeters" previously constructed for the purpose may be divided into three classes, producing respectively noises, musical vibrations, or the vibrations of spoken words. The first two classes will obviously give only a faint idea of the way in which a given individual may be able to perceive spoken words. In fact, many persons have a rather limited capacity of hearing ordinary speech but are able to hear distinctly either musical vibrations or noises. The reason is to be found in the more complex character of spoken words.

A graphical record of vowels (such as the flames of König) is composed of a certain group of vibrations. French "i" (English "e") and French "ou" (English "oo") are composed, for example, of isolated vibrations, "é" (English "ay") and "o" by groups of two, and French "a" ("ä" as in "father") by groups of three vibrations. In order to reconstitute these vowels, the groups referred to should thus be artificially reproduced. To this effect slots arranged in groups of one, two, and three respectively are cut in a rotatable circular disk. When air is blown through these slots the vowels mentioned will be distinctly heard. In fact, they are not only recognized by the ear but give the same graphical records as natural vowels or the vowels produced by a phonograph. However, they correspond with sung vowels only. In order to obtain spoken vowels the air current is made to pass through




Fig. 5.—An Apparatus for Teaching the Deaf How to Hear and for Massaging the Ear.




Fig. 6.—Two Sirens, One with a Complete Set of Mouthpieces.

are absolutely identical with those of natural spoken vowels. An artificial talker is thus obtained and

that the intensity of the sounds given out by it is accurately proportional to the pressure of the air cur-




Fig. 1.—Artificial Mouth for Producing the Sound of French "é." (English "a" as in "Make.")




Fig. 2.—Artificial Mouth for Producing the Sound of French "i." (English "e.")




Fig. 3.—Artificial Mouth for Producing the Vowel Sound "o."




Fig. 4.—Artificial Mouth for Producing the Sound French "ou." (English "oo," as in "Moon.")

special molds (Figs. 1, 2, 3, 4), which accurately imitate the form of the human mouth in pronouncing a given vowel. The graphical records of these sounds

the apparatus in question may be fitly termed "vowel siren" or "talking siren."

The most valuable property of this apparatus is

rent. It thus affords a means of gaging the intensity of a given sound and producing a sound of any desired strength. This is made use of in determining keenness of hearing.

The ear to be tested should be placed at a constant distance from the instrument, the sound intensity of which is gradually increased by augmenting the pressure of the air, this pressure being gaged by means of a highly sensitive metallic manometer.

The sound produced by a pressure of 1 millimeter is perfectly well perceived by a normal ear. If the pressure for an ear must be raised to 40 millimeters before the sound can be heard, the acoustic sense of the patient may be said to be 1/40, if to sixty, 1/60, if to two hundred, 1/200, and so on—a simple and efficient scale. The apparatus thus affords an extremely simple measuring instrument, which always remains constant. Its readings may be accurately checked and reproduced whenever desired.

The condition of a given ear is gaged and represented by the following graphical method:

The French vowels "ou," "o," "a," "é," "i" (or their English equivalents) are inscribed on a horizontal line, and below each of them, as shown in the accompanying table, a vertical scale is drawn with graduations corresponding with the pressure read on the manometer at the moment the vowel in question is perceived. If for instance the French vowels "ou," "o," "a," are perceived under a pressure of 8 millimeters, the point 8 on the scales corresponding with each of these vowels is marked; if "é" is heard under a pressure of 21 millimeters, the point 21 is marked on the "é" scale. Finally the point 162 is marked on the scale of the French vowel "i," if the latter is heard under a pressure of 162 millimeters; these five points are then connected by a line and a curve will




Fig. 7.—Dr. Marage in His Laboratory. On the Table Are a Manometer and Mouthpieces for Uttering Vowel Sounds.

THE TALKING SIREN OF DR. MARAGE.

be obtained. From these curves, varying markedly in shape, the following conclusions can be drawn:

1. If the ticking of a watch, which is normally heard at a distance of 1.5 meters, is heard only when applied to the ear, the acoustic intensity, according to the talking siren, will have become 1/3.

2. If auditive acuteness further decreases, being finally comprised between 1/3 and 1/13, the patient, although he may be able to hear a particular conversation, will lose many words in a general conversation.

3. In the case of an auditive acuteness of less than 1/13, the patient will unconsciously train himself to listen only with the other ear, if this be normal. The deaf ear will perceive only those sounds which are pronounced very distinctly at a short distance.

4. Between 1/30 and 1/200 only those words which are spoken in a very loud tone close to the patient will be heard.

5. Beginning from 1/200, spoken words will be heard only by means of a hearing tube.

These five zones of deafness are separated in the table by heavy horizontal lines. As long as the hearing remains within a given zone, the patient will not feel any appreciable change and only those talking with the patient may appreciate some variation in the loudness of their words. The siren thus allows the perception of degrees in acoustic intensity which the patient himself or direct observation could not ascertain. After measuring the acoustic intensity and drawing the curve of a patient, the shape of the curve will locate the seat of the trouble. If for instance the curve has the approximate shape of an inverted U, only the middle ear will be affected. Thus each peculiar affliction will have its special characteristic curve.

While the siren can thus be used for diagnostical purposes it will be found useful also in curing the trouble. In fact, a systematic treatment consisting in the repeated production of given sounds before the tympanum of the ear has been found to be a most efficient "massage," which in some cases restores the ear to normal hearing capacity, while nearly always effecting some improvement (Fig. 5). This process has also been used with much success in the treatment of deaf-mutes, many of whom have been taught to hear by its means. In this case the ear is taught according to a method which from the most simple elements of speech, that is the vowels, proceeds to the more complicated, the deaf-mute learning how to hear in exactly the same way as a child is taught how to read by beginning with the alphabet.

In a memoir recently presented to the French Academy of Sciences, Dr. Marage records some interesting experiments made by himself as to the acoustic qualities of some large halls of the city of Paris. He confirms the result found some years ago by Mr. Wallace Sabine, viz., that the sound of resonance is the principal factor in question. The duration of this sound, as stated by Marage, will vary according to the intensity, pitch, and timbre of the primitive sound, which possibly accounts for the fact that a given hall may be bad for an orchestra and satisfactory for an orator.

Official Meteorological Summary, New York, N. Y. April, 1907.

Atmospheric pressure: Highest, 30.38; lowest, 29.16; mean, 29.89. Temperature: Highest, 73; date, 25th; lowest, 26; date, 2nd; mean of warmest day, 61; date, 26th; coolest day, 35; date, 1st; mean of maximum for the month, 52.2; mean of minimum, 37.7; absolute mean, 45; normal, 48.6; deficiency compared with mean of 37 years, -3.6. Warmest mean temperature of April, 54, in 1871. Coldest mean, 41, in 1874. Absolute maximum and minimum of this month for 37 years, 90 and 20. Average daily deficiency since January 1, -1.1. Precipitation, 3.89; greatest in 24 hours, 0.97; date, 9th; average of this month for 37 years, 3.37. Excess, +0.52. Accumulated deficiency since January 1, -1.48. Greatest precipitation, 7.02, in 1874; least, 1.00, in 1881. Snowfall, 6.1. Wind: Prevailing direction, N.W.; total movement, 9,924 miles; average hourly velocity, 13.8; maximum velocity, 52 miles per hour. Weather: Clear days, 8; cloudy, 8; partly cloudy, 14. Fog, 29th, 30th. Thunderstorms, 23rd, 26th. Remarks: Coldest April in 32 years.

Alcohol Engines to Replace Gasoline Engines.

BY JOHN PRESTON.

Although the general use of gasoline engines has developed entirely within the past ten or twenty years, the number of such engines in this country is now high up in the hundreds of thousands, being used as they are for automobiles and as stationary engines for pumping water, running small factories, and for furnishing power for various uses in country residences and on farms.

The law which recently took effect, releasing from the internal revenue tax alcohol so denatured as to render it unfit for drinking, permits, through decrease in price, alcohol to become a possible substitute for gasoline and kerosene as a fuel.

The price at which a gallon of 95 per cent grain alcohol can be manufactured and marketed is now about 40 cents. The government tax raised the market price to about \$2.50 per gallon; it is now 37 cents per gallon for the denatured alcohol. In order to avoid paying the revenue tax, the government regulations prescribe that the alcohol must be denatured according to the following rule: To 100 parts of grain alcohol of not less than 90 per cent strength must be added 10 parts of wood alcohol and one-half of one part of benzine. Consequently, the mixture will not only be very poisonous, but will have a strong, disagreeable odor, which will obviate any danger of its being confused with pure alcohol.

cylinder, horizontal and vertical, four cycle and two-cycle, gasoline and kerosene. Since alcohol is much less volatile than gasoline, it was to be expected that difficulties would arise in its use in a gasoline engine. These difficulties were often very curious, and in some cases seemed for a time quite baffling, but they all yielded to patient study. The proper vaporization of alcohol before its introduction into the engine cylinder is a question which requires for its solution a comprehensive knowledge of the vapor pressure and of the other properties of alcohol as compared with gasoline.

With all the engines it was found that the valve adjustments must be quite different for alcohol from those used for gasoline. Gasoline is so volatile, that it might be almost said to vaporize itself. On the contrary, the vaporization of the alcohol must be carefully attended to. When gasoline is used as a fuel, it is sometimes difficult to start an engine out of doors in the coldest weather. Under like conditions it would be impossible to start an engine using alcohol without the aid of a little gasoline or without first heating the engine in some manner.

There are several important differences between the behavior of an engine when running on gasoline and its action with alcohol. With alcohol fuel there is never any hammering due to pre-ignition. The explosions are slower and consequently less noisy, and there seems to be correspondingly less wear and tear

on the machine. The exhaust is never strongly disagreeable in odor, as may be the case with gasoline. With alcohol fuel an engine may be overloaded to an amount considerably in excess of its maximum possible power on gasoline. In other words, an engine rated at 10 horsepower on gasoline might be called a 12 horsepower engine when running on alcohol.

A gasoline engine requires about twice as much alcohol measured in gallons as it does gasoline to develop the same power. This excess in consumption of alcohol would doubtless be reduced in engines specially designed for alcohol.

This increased consumption of alcohol is to some extent offset by its much greater cleanliness when handled and used, the absence of disagreeable noise and odor, and the very great diminution of danger from fire.

On account of the low degree of volatility of alcohol, it is possible to run into the engine an amount greatly in excess of its requirements. This excess will pass through the engine without doing any good. Hence to secure the most economical use of this fuel, perhaps greater care in the valve setting of the engine is required than is the case when gasoline is used.


It has been completely proved that alcohol is perfectly adapted for use as an engine fuel; and, except for its present cost, the advantages of alcohol as a fuel far outweigh those of gasoline. As the use of alcohol engines increases, large quantities of alcohol will be made,

and the denatured product will be as easily obtainable anywhere as is kerosene at the present time. The price will doubtless become materially lower than it now is.

If, under the stimulus of demand, inventors and manufacturers will combine to devise, and put on the market, special alcohol engines fitted to secure the highest economy in the consumption of the fuel, we may expect to see, within a few years, alcohol engines as numerous as gasoline engines are to-day.

The best efficiencies of centrifugal pumps are supposed to have been obtained at discharge velocities equaling about 12 feet per second through the discharge aperture of the pump. Recent experiments have shown that from pumps as large as 32 inches 80 per cent efficiency was obtained at 38.68 feet lift, under a discharge velocity of 21.2 feet per second, while some recent tests on very small pumps show gradually increasing efficiencies under heads up to 89 feet and discharge velocities of 40 feet per second.

The pipe line, conveying petroleum from Baku to the Black Sea, has been completed. It is 550 miles long, and is capable of passing 400,000,000 gallons of oil yearly. Another important oil pipe line has been built for transporting Texas and California petroleum across the Isthmus of Panama. It is 8 inches in diameter and 51 miles long.



Analytic Curve Obtained With
Dr. Marage's Apparatus.

AVERAGE										PATIENT HEARS WATCH AT A DISTANCE OF ONLY A FEW CENTIMETERS.
R	L	OU	O	A	E	I				
5	5	5	5	5	5	5	5	5	5	PATIENT CAN HEAR NO GENERAL CONVERSATION; ONLY PARTICULAR CONVERSATION.
10	10	10	10	10	10	10	10	10	10	
20	20	20	20	20	20	20	20	20	20	
30	30	30	30	30	30	30	30	30	30	
40	40	40	40	40	40	40	40	40	40	
50	50	50	50	50	50	50	50	50	50	PATIENT HEARS SINGLE PERSON TALKING DISTINCTLY, AT NORMAL DISTANCE.
60	60	60	60	60	60	60	60	60	60	
70	70	70	70	70	70	70	70	70	70	
80	80	80	80	80	80	80	80	80	80	
90	90	90	90	90	90	90	90	90	90	
100	100	100	100	100	100	100	100	100	100	PATIENT HEARS ONLY WHEN TALKED TO CLOSE TO THE EAR, AND MORE AND MORE LOUDLY.
110	110	110	110	110	110	110	110	110	110	
120	120	120	120	120	120	120	120	120	120	
130	130	130	130	130	130	130	130	130	130	
140	140	140	140	140	140	140	140	140	140	
150	150	150	150	150	150	150	150	150	150	PATIENT HEARS ONLY WITH AID OF A HEARING TUBE.
160	160	160	160	160	160	160	160	160	160	
170	170	170	170	170	170	170	170	170	170	
180	180	180	180	180	180	180	180	180	180	
190	190	190	190	190	190	190	190	190	190	
200	200	200	200	200	200	200	200	200	200	
210	210	210	210	210	210	210	210	210	210	
220	220	220	220	220	220	220	220	220	220	
230	230	230	230	230	230	230	230	230	230	
240	240	240	240	240	240	240	240	240	240	
250	250	250	250	250	250	250	250	250	250	
260	260	260	260	260	260	260	260	260	260	
270	270	270	270	270	270	270	270	270	270	
280	280	280	280	280	280	280	280	280	280	
290	290	290	290	290	290	290	290	290	290	
300	300	300	300	300	300	300	300	300	300	
310	310	310	310	310	310	310	310	310	310	
320	320	320	320	320	320	320	320	320	320	
330	330	330	330	330	330	330	330	330	330	
340	340	340	340	340	340	340	340	340	340	
350	350	350	350	350	350	350	350	350	350	
360	360	360	360	360	360	360	360	360	360	
370	370	370	370	370	370	370	370	370	370	
380	380	380	380	380	380	380	380	380	380	
390	390	390	390	390	390	390	390	390	390	
400	400	400	400	400	400	400	400	400	400	

Dr. Marage's Table of Auditive Acuteness.

THE TALKING SIREN OF DR. MARAGE.

Alcohol is an inflammable liquid, and its vapor, when combined with the right proportion of air, forms an explosive mixture suitable for use in engines. Alcohol differs materially in its properties from gasoline. It is less volatile, it gives out less heat per gallon when burned, and its latent heat of vaporization is much greater than that of gasoline.

Although for ten years alcohol has been used to a considerable extent in special alcohol engines on the continent of Europe, such use has been untried in this country.

In Europe alcohol engines have differed from gasoline engines chiefly in the use of a higher compression than is permissible when gasoline is used as a fuel, and in the use of a more or less intricate form of heated carbureter.

Since no alcohol engines are on the American market, all the tests by the United States Department of Agriculture have been made on American engines designed for gasoline or kerosene as fuel.

Every engine tried—ten different kinds in all—was found to work as perfectly on alcohol fuel as on the gasoline or kerosene fuel for which it was made, after sufficient preliminary trial to determine the peculiarities of setting and adjustment necessary for the alcohol. The engines tried included stationary engines up to 20 horse-power, automobile engines up to 40 horse-power, and one marine engine. The engines were of nearly every type—one to four

Correspondence.

Broken Rails.

To the Editor of the SCIENTIFIC AMERICAN:

In your issue of the 20th ultimo you brought out an article on "Broken Rails." Since then the New York press has taken this matter up, as well, and it has thereby received some publicity. I have not noticed any further article in your paper, and would therefore suggest that you give your readers all the information on this score which it is possible for you to do. There is nothing that will cure so stupendous a fraud as this, perpetrated on the public, who are really the owners of the railways, and therefore the purchasers of rails, as the truthful and persistent exposure of the methods by which this fraud is enacted. Among an intelligent public, you have an excellent opportunity for exposing these facts.

RUDOLPH R. HOFFMANN.

Brooklyn, N. Y., May 1, 1907.

Railroad Accidents.

To the Editor of the SCIENTIFIC AMERICAN:

The illustrated article on page 232 of the March 16 issue of the SCIENTIFIC AMERICAN, in regard to railroad accidents occasioned through neglect, carelessness, forgetfulness, or whatever may have been the fault, is remindful of quite too many similar accidents—similar in the fact of the same cause—within the recollection of all who have had much to do with the operation of railroad trains.

The article, aside from the meritorious criticism of the common practice of placing lightly constructed equipment between two that are much stronger and heavier, and the deplorable necessity that exists for maintaining "facing switches," further illustrates the lack in advancement and the weakness in conditions that will permit frequent repetitions year after year, and continue placing extremely hazardous responsibility and dependence on the fallibility of the human mind.

Quoting from the article: "It is certain, however, that greater precautions could be taken to safeguard such switches." It is remarkable that, with the many improvements in rolling stock and appliances tending to betterment of the commercial interests of railroads, there has been so little advancement in the facilities and appliances that constantly and fearfully menace public safety in travel. True, the automatic block signal system is a great advance over the primitive methods of "by rule and by guess," yet it is the one pronounced improvement toward safety in travel, that is not more a change of "rules" than appliances. The improvement in construction is splendid, so far as it goes, but when improved construction is placed next to the inferior, the benefit is mostly lost in the test, while the danger is greatly intensified.

The only improvement in switches that has been effected in the past forty or fifty years, was the substitution of the "stub" by the "split" switch; and practically no change whatever in the switch stand, except as to pattern and the revolving staff instead of the "throw lever"—simply change as to ease of operation, not adding a particle to the safety of passing trains. The signals are the same, as to effectiveness, and just as impossible of discernment—even more so, with the greatly increased speed and fewer stops.

With the many, constantly increasing duties required of the engineer, and the frightful speed exacted of him, the unceasing wonder is that he distinguishes the multitude of signals he encounters. The fact is, that he proceeds on faith that every man is faithful in his duty, as it is impossible that he can see every insignificant switch target at sufficient distance to enable him making the stop if it is set wrong. The contention is well taken: "Not only should the switch signals be mounted on a lofty post, but a lofty distant signal should be provided." Better than the last, would be a distant alarm signal that would operate a loud-sounding gong in the locomotive, through wheel contact.

While "facing" switches are necessary with single, and not with double tracking, the liability of "wrong switch" is still to be considered. Local and slow trains are required to clear the faster, in passing. The difference would be, in a forgotten switch, that the collision would be rear instead of head on. The fatality could be as great, or greater.

The remedy is not in more stringent rules, nor altogether in certain signaling, but in more assured switch closing. How is that to be done? Certainly through automatic mechanical action. Allow me to suggest that the proper and normal position for a switch should be *closed*, and under no circumstance should it be possible to *leave* it in an open position. Were this adopted, it would not be necessary to protect against open switches, as there would be none. It would be necessary, however, to make it a penal offense to, at any time or for any purpose, use means of fastening open; and it would be necessary that the person operating the switch should hold it open during the passage of wheels through.

This may be accomplished by a gravity mechanism, that, as soon as released from the hand, would fall to the normal or closed position. This operation of opening during necessity could be made secure, just while being held open, by means of a secondary gravity clip that would effectually lock the switch open only so long as the switchman retained it in his hold.

A remiss duty would seldom cause more than simple derailment of a few trucks or cars, under the customary use of switches.

E. S. CRULL.

Sedalia, Mo.

A THEATER AUDITORIUM TURNED INTO A BALLROOM AT A MOMENT'S NOTICE.

The problem of a ballroom sufficiently large to house a considerable number of dancers, or to provide space for banquet tables, has been solved in a more or less satisfactory manner by boarding over the orchestra and parterre of the theater or opera house. Such makeshift is necessarily clumsy and unsatisfactory. Horses, framing, and boarding must be stored at all times, affording excellent food for fire. Much time and expense is entailed in erecting the flimsy temporary structure each time it is used. A French inventor, Dr. Eugène Gravelotte, conceived the rather brilliant idea of applying the principle of the waffle iron to the floors of theaters, and a new Paris music hall in the Rue de Clichy has been provided with this somersaulting orchestra floor, which can be changed in seven minutes from the usual conventional inclined floor with comfortable chairs to a horizontal, highly-polished dance floor. The carcass which holds the twin floors in a parallel position revolves about a horizontal axis in a pit permitting of a complete revolution.

Our front-page engraving gives some idea of this audacious transformation. The dimensions of the revolvable sections of the floor are as follows: Length, 53 feet; width, 50 feet; and the depth of the pit is 30 feet. Metallic trunnions or pivots are secured to the carcass. On one of the two twin floors are nineteen rows of orchestra chairs. There is a difference in level of some 7 feet when the dance floor is in use. Steps lead down from the foyer. The mechanism for making the transformation is very simple. Up over the proscenium are motors which actuate drums around which are roved steel cables, which are in turn roved around the trunnions. The principle is the same as winding a string upon a lead pencil. When the string is pulled the pencil revolves. The total weight of the construction is 90 tons, yet so well is the floor balanced that a 2-horse-power motor is all that is required, and the cost of operation is only eight cents for each transformation. The installation cost the moderate sum of \$14,000, of which \$9,000 was used for building the carcass, the floors, and the operating mechanism, and the balance was taken up in excavating the pit and in the masonry. The greatest difficulty connected with the installation was to find an engineer with enough courage to make the necessary calculations for the realization of the idea.

The Current Supplement.

For the fourth time there were held at Monaco, from the 2d to the 14th of last month, the Motor Boat Show and Races that have come to be the great annual spring event in Europe. The races this year were noted for the record of the Panhard boat, which kept up a speed of 30 knots for three hours, the best performance ever made by any motor boat. In the current SUPPLEMENT, No. 1636, the Paris correspondent of the SCIENTIFIC AMERICAN thoroughly describes these races and gives details of the feats of the individual boats. Illustrations of the more prominent types accompany the text. Of technological interest are articles on the "Slaking of Plaster and Means of Retarding Its Hardening," "Waste Products from the Manufacture of Glue," "Process of Producing Plaster Free from Bubbles," "The Manufacture, Denaturing, and the Technical and Chemical Utilization of Alcohol" (the first of two splendid installments on this subject by M. Klar, a well-known German alcohol chemist), and "The Powell Process of Preserving Wood with Saccharine." A new telephone dictating apparatus, invented by Turner and Germer, is described. "What is a Watt?" is the title of an article by George S. Hodgins, which explains clearly the meaning of this electrical term. Among flying-machine experimenters there is about as great a diversity of opinion on air-propeller shapes as there is a dearth of actual knowledge of their efficiencies. For that reason Mr. A. M. Herring's article on an air-propeller testing device should be particularly welcome, inasmuch as Mr. Herring is himself a well-known aeronautical expert. "A Quarter Century's Progress in the Applications of Electricity," is the title of a splendid review of modern electrical achievements. Dr. Alfred Gradenwitz writes on a German system of compressed-air cleaning. The intensity of the tropical sun and its effect on the human body is discussed by Surgeon-General Stendel. Joel A. Allen writes on the influence of physical conditions in the genesis of species.

The Wellman Expedition to the North Pole.

BY THE PARIS CORRESPONDENT OF THE SCIENTIFIC AMERICAN.

Mr. Walter Wellman has already made his plans for the expedition to the North Pole which he expects to make during the coming season. He states that the steamer which is to take the expedition to its starting point in the Danish islands has already arrived at Trondhjem, Norway, where it is now lying in dry dock, and it will be ready to leave for Spitzbergen about the first of June. The party which is to proceed to the islands is made up of some thirty-five persons. The sleds are to be drawn by dogs coming from the north of Siberia from the Samoides tribes dwelling on the banks of the Obi River. As to the airship, of which we already gave an illustrated account some time since, it has been entirely rebuilt in the Mallet aeronautic establishment at Paris. According to the present design, it measures 55.8 meters (183.7 feet) in length, with a middle diameter of 16 meters (52.8 feet). The volume of the balloon is 7,500 cubic meters (9,825 cubic yards), and it will have an ascensional force of 8,870 kilogrammes (19,515 pounds). Near Paris is being constructed a new nacelle which is built entirely of steel, with a motor and improved mechanical parts for the helices, these having been designed by Mr. Wellman. The mechanical design has some original features which differ to a great extent from what has been hitherto constructed for airships. Built of steel tubes which give it lightness as well as stiffness, the nacelle has a total length of 115 feet. Together with the steel part is built a large reservoir which is expected to contain all the gasoline needed for the trip to the pole and return, this being 6,800 liters. As regards the principal motor mounted on the nacelle, it is rated at 60 to 70 horse-power. Directly mounted upon the motor shafting are two helices of steel having 11.5 feet diameter, and there is one such helice at either end of the nacelle, resembling in this respect the design which is adopted by the Lebaudy brothers in the airship "Patrie." A good speed is expected to be made by the new airship, this being calculated at fifteen to eighteen miles an hour, and there will be enough fuel in the reservoir to give a continuous flight of 150 hours at full speed. This is expected to allow the airship to cover a radius of 2,000 miles, and is nearly double the distance from Spitzbergen to the pole and return, so that there is a good margin allowed. All the mechanical parts have been put through a good series of practical tests for some time past. When the airship is entirely set up at Spitzbergen during the month of July next, a series of trial tests will be made of the whole before setting out upon the trip. Mr. Wellman does not think it advisable to make the trial tests of the balloon at Paris before taking it to the Arctic regions. At first he intended to do so, but was brought to a different conclusion after considering the matter. Should this be done he could not make the expedition this year, as a balloon shed would have to be built and other arrangements made which would take a great deal of time, and again these tests would not be decisive at any rate, seeing that the airship must be taken apart for transportation for several thousand miles and then set up again. To be sure that all was right, a new set of trials would need to be made on the spot after assembling it. As the airship is designed for use in the Arctic regions and above the ice, the conditions are special, and it would need to be tested on the spot. The new airship "America" will carry quite an amount of load, seeing that besides the machinery and 3½ tons of gasoline there will be four or five men for the crew, about a dozen dogs for the sleds and all that will be needed should they be required to make the return trip on the ice; added to this there are 1½ tons of provisions, so that the crew could pass all the winter in the Arctic regions. The material which is used for the balloon seems to be of first-class quality and according to recent tests made upon it, not more than one per cent of hydrogen would be lost during twenty-four hours. Even should this amount rise as high as two per cent per day, Mr. Wellman estimates that he could continue in the air for about twenty-five or thirty days without difficulty, keeping the balloon swelled out by the interior ballonet. His present plan is to arrive at Spitzbergen during the first week of June and thus to make a series of trial flights during the month of July, leaving for the pole about the first half of August.

Hydrofluoric acid as a cleaning agent for castings has been in general use but a short time, being treated a few years ago as a secret process. Formulae for the acid containing superfluous and innocuous ingredients to mystify the purchaser have been sold for considerable sums. Anything used in connection with this "pickle," aside from the hydrofluoric acid and water, is wholly unnecessary, the usual formula being one part of acid to ten of water. In adding water, however, care should be taken to know the strength of the acid. The idea is to get a dip that will remove the sand perfectly and quickly, the operation requiring ten to fifteen minutes.

THE MANUFACTURE OF MATCHES IN FRANCE.

BY JACQUES BOYER.

Since 1890 the manufacture of matches in France has been a government monopoly. There are seven national match factories, situated at Pantin, Aubervilliers, Saintines, Bègles, Trélaze, Aix, and Marseilles, each of which has a specialty of its own. The logs are sawed and cut into splints in the little village of Saintines on the edge of the forest of Compiègne; parlor matches come from Pantin and the wicks of wax matches are made exclusively at Marseilles. Two of the most interesting factories are described in this article — Pantin, with its old equipment which will soon be abandoned, and Aubervilliers, recently reconstructed and provided with machinery of the highest perfection. First we will visit the venerable factory at Pantin. The splints come in great boxes from Saintines. The best are made

of Russian willow, which is stronger than the French variety. Poplar and birch are also used. The splints are unpacked and laid in a row in a square form called a boat, and this is placed on an apparatus designed to arrange the splints in regular order, separate them from each other and bind them together in a "press" or iron frame. The operator, by pressing a lever with his foot, feeds into the press a row of 100 matches, which he covers with a thin strip of wood to separate it from the following row, formed by the next movement of the treadle. The "press" or frame, balanced by a counterpoise, gradually descends during this operation. When full it is locked by fastening on a headpiece, taken from the machine and carried to the sulphuring room.


In framing safety matches the empty frame is laid horizontally under a battery of vertical tubes surmounted by a perforated plate on which the splints are stacked in a vertical position. Each movement

of the pedal causes a splint to descend through each tube to its place in the frame, which is thus filled at one effort. The upper part of the apparatus is then raised and the filled frame is locked and replaced by an empty one.


In the sulphuring room the frames containing the splints, regularly spaced, are first pressed upon hot iron plates which heat the ends of the splints in order to facilitate adhesion of the melted sulphur into

except that they are pressed on a metal plate covered with a uniform layer of the chlorate mixture instead of being dipped into a tank. The operation requires much care and skill, for the heads are large and all must be of the same size. In wax matches and all others in which the sulphur is replaced by stearine, paraffine, or some other combustible, a little potassium chlorate is added to the paste to increase the temperature of the flame. The heads of safety matches, which

contain neither uncombined sulphur nor phosphorus are made of a paste composed of 100 parts of potassium chlorate, 40 parts of antimony sulphide, 20 parts of gelatine and sufficient water to produce the desired consistence. These matches take fire only when rubbed on the box, which is coated with a mixture of 100 parts of red phosphorus, 80 parts of antimony sulphide, and 50 parts of gelatine. All these pastes, whether they contain phos-



Charging the Frames with Splints.



Applying Phosphorus Paste to the Sulphured Matches.

phorus or not, are prepared in a special laboratory where the ingredients are carefully weighed out and mixed by machines.


The common sulphur matches after receiving their two coatings, of sulphur and phosphorus, are conveyed, still clamped in the frames, on iron cars to the drying rooms. These tunnel-shaped rooms have airtight doors at each end, and the drying is effected by the combined agencies of steam pipes and energetic ventilation. If fire breaks out it simply consumes the contents of the fireproof room, producing volumes of offensive smoke but doing little damage.

From the drying rooms the cars laden with matches are rolled to the discharging rooms where women open the frames and put the matches into open boxes called "boats," which are divided into small compartments. This operation is performed almost mechanically. The operator places the frame on the apparatus, unloads the frame and removes, one by one, the strips of wood

which they are next dipped. The depth of the immersion is limited by the contact of the iron frame with the rim of the steam-heated vessel, in which the level of the melted sulphur is maintained constant. Expert workmen are needed for this operation, as too brief or too prolonged immersion may seriously injure or even destroy the value of the product.

The heads of common matches next receive a coating of phosphorus. The apparatus employed for this purpose consists essentially of a horizontal cylinder which dips into the phosphorus paste to a depth equal to one-third of its diameter and carries a layer of the paste with it as it revolves. The frames filled with sulphured matches are passed between this cylinder and another, at such a distance above it that the sulphured ends are pressed firmly against the paste-covered lower cylinder.

Parlor matches are headed by a single operation which resembles the sulphuring of common matches,



A Machine Which Automatically Converts Splints Into Finished and Boxed Matches.

THE MANUFACTURE OF MATCHES IN FRANCE.

between the rows of matches, at the same time pressing a pedal which causes the row of matches just released to fall into the boat below. Another woman turns, with pincers, all matches that have become inverted. The loaded boats are then taken to the boxing room. The boxes for common sulphur matches are made by machine in a neighboring apartment and are brought, piled pell-mell in great crates, to the women in the boxing room, who fill them very rapidly. Boxing is also done by machine.

In this case the boat is placed behind a glass screen, through which the attendant watches the operation, and is subjected to constant shaking in consequence of which the matches glide, by their own weight, into a tube which holds the number of matches required to fill a box. The attendant empties the filled tube into a box by pressing a pedal and two assistants cover the filled boxes. One machine with its crew of three women can put up, on an average, 20,000 boxes in a day. The packing and labeling of the boxes offer nothing of particular interest except the dexterity of the women who do the work. The boxing of parlor matches is performed in a different manner, as shown in one of the illustrations. Women sit at a table on which the frames of matches are placed vertically. After unlocking the frame the operator takes out with her forefinger and thumb the matches of one row, arranges them on the table and puts them into a box, then proceeds to the next row, and so on. The great inflammability of the matches makes the operation rather dangerous and also makes boxing by machine impossible. Occasionally a match ignites and sets fire to others. The woman must then promptly spring back from the table and sweep to the floor the burning boxes and

frame. These little fires are usually extinguished without difficulty, as are those which are caused, now and then, by the parlor matches or other matches which always litter the floor, for dropped matches are of too little value to be picked up as they fall, so they are simply swept up once a day and burned in a furnace provided for the purpose.


The boxes for parlor matches and safety matches are coated on their sides with frictional or chemical

ber, to the packing tables where girls put them up in packages.

Now, having reviewed the successive operations which are required in the manufacture of matches by the old methods, let us examine the remarkable machine invented by MM. Cahen and Sevéne which takes the place of many hands, automatically transforming the bare wooden splints into perfect matches and even putting them into boxes. Twenty of these mas-


terpieces of mechanism are employed in the new factory at Aubervilliers, near Paris. A woman feeds the machine with splints while a man sees to the replenishment of the tanks of sulphur and phosphorus composition. At one end of the machine is a funnel into which a girl feeds empty boxes which are quickly filled and dropped before another girl who puts them in a large open crate for transportation to the crating room. The essential part of the match-making machine is the carrier, which in the French industry bears the same name, "presse," that is given to the small frame used in the hand manufacture. This carrier consists of a long endless band composed of a great number of steel plates connected by chains and driven forward by toothed wheels and pawls. Each plate is

2½ inches long (in the direction of motion) and 48 inches broad and is pierced with 550 round holes, the diameter of which (1/12 inch) is sensibly equal to the width of a match splint. Hence when the ends of the square splints are forced into the round holes they become fastened very securely to the plates. The holes are arranged in five rows, each containing 110 holes and holding the matches required to fill one box of 100 or two boxes of 50—the excess of 10 per cent having been found necessary to allow for broken




Making Packages of Filled and Coated Boxes of Safety Matches.

compositions on which the matches are to be scratched. These coatings are applied either by hand or by machine. In the former case the box is simply dipped lightly in the phosphorus or other composition; in the latter, the curious machine shown in one of the illustrations is employed. The filled boxes, arranged in rows on three long rails, are pushed by a woman under rollers which drive them forward to rotating brushes which apply the coatings. The boxes then travel onward, automatically, through a drying cham-




Filling Small Boxes with Safety Matches.



Coating Safety-Match Boxes With Red Phosphorus Composition.



Discharging the Frames.



Mixing the Inflammable Coating.


or otherwise spoiled matches. The carrier being set in motion is charged with splints in the following manner: The splints fall from an oscillating hopper upon a horizontal iron table bearing 110 parallel grooves. The splints lodge in these grooves from which they are driven by plungers, at each stroke of the machine, into the 110 grooves of a traveling table or charger, which moves to and fro between the fixed table and a vertical portion of the endless carrier. As the charger approaches the carrier a blade rises behind it and prevents the splints from being driven backward. The splints, being a little longer than the charger, project in front of it and are forced into the 110 holes of one row of the carrier plate, where they remain firmly attached when the charger retreats. The force required for this operation is so great that an iron plate is pressed automatically on the splints from above to prevent bending and breaking.

As the carrier travels onward the free ends of the splints with which each plate bristles are dipped successively into a paraffine and a sulphur bath after which they receive their coat of phosphorus from a rotating cylinder which dips in a vessel of the composition. Then they travel a long distance, for the purpose of drying, and finally reach the discharging and boxing station. Here they are expelled from the holes in the carrier plate by minute plungers so controlled by springs that they follow the plate in its motion as nicely as a human hand could do and perform their functions without shock or jar. The matches fall, in groups of five, into little receptacles whence they are pushed by pistons into the boxes, which are mechanically opened to receive them and similarly closed when full. The machine, therefore, does everything, even boxing, human hands merely feeding it with the raw material and removing the finished product. One such machine attended by three girls, turns out about 50,000 boxes, each containing 50 matches, in ten hours—an output which would require the labor of twenty persons in the old method of manufacture.

RECONSTRUCTING A GREAT CITY RAILROAD TERMINAL.

In a comparison of the problem presented by the construction of the two great railroad terminals which

any delay or confusion of its schedule, right upon the very ground where the new station and the complicated yard is being built. The problem would be perplexing enough, in all conscience, did it consist merely in the pulling down of the old and the erection of the new buildings in the presence of the traffic; but as a matter of fact, the difficulties are enormously increased by the fact that the whole surface, both of the station yard and train shed, has to be excavated to a least depth of 15 feet to accommodate the express traffic of the road, and that 25 feet below this level as thus depressed, yet another yard and station



The new station and yard as they will appear from Fiftieth Street. The broad central roadway is Park Avenue, which will extend to the office and station building. To the left is the new Post Office. The open spaces will eventually be covered by buildings.

THE NEW GRAND CENTRAL TERMINAL, NEW YORK.

must be excavated for the accommodation of the local service. At the present writing the westerly third of this excavation is completed, and the suburban service of the New York Central Railroad is being operated from a temporary terminal station built in this completed portion.

Nor are the difficulties of reconstruction at all assisted by the fact that simultaneously with all this excavation and tearing down and building up, a radical change is being carried out in the methods of traction employed, the steam trains being abolished and an elaborate and costly system of electric traction installed. Moreover, as though this were not sufficient, the company have put upon their engineers the burden also of instituting an entirely new system of signaling suitable to the electrified road.

Apart from the fact that there may be in the long run some slight financial gain from the change of motive power, and that there will be an immediate

the intersection of Fiftieth Street and Park Avenue. One of them portrays a scene which may be witnessed at any time in the present yard when the condition of the atmosphere is favorable to a slow dissipation of the steam and smoke. The other view represents the conditions as they will appear in the year 1909, when the new yard and station shall have been built, and Park Avenue with the intersecting streets from Fiftieth to Forty-fifth Street have been built above the yard and restored to the use of the city. When this work has been completed there will be a complete absence of steam and smoke, and the loud exhaust of the


steam locomotives will give place to the quiet hum of the big electric motors and the multiple-unit trains.

The southerly end of the depressed yard will be covered by the new Grand Central Station proper, whose southerly façade will stretch for 300 feet on 42d Street, and its westerly façade for 680 feet on Vanderbilt Avenue on the west. The building will also extend 625 feet on Forty-fifth Street, 400 feet on Lexington Avenue, 275 feet on Forty-fourth Street, and 260 feet on Depew Place. Of this great block of buildings, the southerly portion will include the station proper, and the northerly and larger half will be taken up by the offices of the company. In the view herewith given, the northerly façade of the office buildings lies to the right.

The large building, of similar architectural treatment, to the left, is the new Post Office building, beneath which will extend a portion of the tracks of the upper express level.

The station building proper will include a ticket lobby 90 feet wide by 300 feet long, from which access will be had to a grand concourse 160 feet in width by 470 feet in length, the latter being covered by a vast domed roof, rising at its crown to a height of 150 feet above the floor. Beyond the concourse will be thirty-four stub tracks for passenger trains, with broad platforms, of an average width of 16 feet, between them. On the lower deck will be a separate station for suburban travel, which will be served by fifteen parallel tracks and a two-track loop.

Referring again to the view illustrating the completed station, it will be observed that between Fiftieth and Forty-fifth Streets, the squares which would normally be occupied by blocks of buildings are, for the




The yard here shown will be lowered fifteen feet; below this will be the suburban tracks. The steam and smoke will disappear with the introduction of electric traction.

VIEW OF THE PRESENT GRAND CENTRAL STATION FROM THE NORTH.

are now being built in this city, one for the Pennsylvania Company and the other for the New York Central, it must be admitted that the New York Central terminal presents the greater difficulties, for whereas the Pennsylvania Railroad station is being built *de novo*, and on a stretch of ground bought for the purpose, and free from any complications save those directly incidental to the construction of the station itself, the New York Central terminal problem is greatly complicated by the fact that the whole of the traffic of two large trunk railroads has to be provided for, and kept in movement, as far as possible without


gain in convenience of operation, the immediate motive for this costly work was the desire to render safe and comfortable the operation of trains through the Park Avenue tunnel, and to abolish the smoke and steam, the noise and odors, incidental to the use of steam locomotives in the terminal yard. There is no doubt whatever that all of these objects will be secured; and by way of illustrating how completely the smoke and steam nuisance will be abated, we present two illustrations which show in a very dramatic way how great will be the improvement. Both illustrations are taken from a point of view near

present, being left vacant. There is no doubt, however, but that ultimately these enormously valuable areas will be covered by office or apartment structures; indeed, the railroad company, in laying out the tracks in the yard below, have been careful to make provision for suitable footings for the bases of the columns of the buildings which will ultimately be put in place when the increased value of this property warrants their erection. When that is done, the entire yard with its hundreds of entering and leaving trains, will be entirely shut out from view, and the noise of the traffic will be entirely eliminated.



AN IMPROVED VEHICLE JACK.

An improved vehicle jack has recently been invented, which is of a type adapted to be fastened to and form a permanent attachment for a vehicle. The jack is so mounted that it can easily be brought into operative




AN IMPROVED VEHICLE JACK.

position, and carried to inoperative position with little work on the part of the operator. In the accompanying engraving the jack is shown at A. It will be observed that it comprises two legs hinged to the axle of the vehicle. The method of hinging these legs to the axle is shown in Fig. 3. A collar B is secured to the axle, and this is provided with an undercut slot. Each leg A is journaled on a transverse bolt in a yoke C. The latter is formed with a pin D adapted to enter the slot in the collar B. The head of this pin D engages the undercut portion of the slot. When the jack is not in use the legs are folded up against the axle, to which they are secured by means of hooks, as shown in Fig. 2. In the operation of the jack the legs are detached from the hooks and swung laterally on the pins D as a pivot, after which they are dropped downward, turning on the bolts in the yokes C. To lift the vehicle wheels it is only necessary to back the vehicle, when the wheels will be raised by the legs. A patent on this improved vehicle jack has recently been secured by Mr. Anthony Gordon, of Sourisford, Arthur Municipality, Manitoba, Canada.

COUPLING FOR LARGE PIPES.

Pipe lines lying on the bed of a river frequently become broken from various causes, such as the dragging of an anchor along the bottom of the river, and when the connecting ends of the pipe sections become broken, it is necessary to cut away a portion of the ends of the pipe and connect the sections together by means of a sleeve, which will make up in length for the portions that have been cut away. This sleeve must be applied when the pipe sections are in their places under water, and the couplings should be so constructed as to enable the pipe sections to lie evenly on the bed of the river, otherwise a continuous strain is exerted on the joint, which is liable to break the joint. The accompanying drawing shows a simple method of making such a connection under water between pipes of large diameter. The coupling consists of two similar cylindrical sleeves A, formed with flanges on their adjacent ends, extending in a plane inclined to the axial line of the sleeves. These flanges




COUPLING FOR LARGE PIPES.

are provided with bolt holes equally spaced thereon, so that the sections may be rotatably adjusted on each other before being bolted together, so as to extend in any line between a straight line and a right angle. In the illustration Fig. 1 shows a straight line coupling, while Fig. 2 shows the method of coupling the sleeves at an angle with each other. This adjustment permits of coupling the sections so that they will conform to the contour of the ground upon which they lie. A series of lugs B are formed on the outer ends of the sections. Bolts which pass through these lugs are adapted to engage apertures in similar lugs formed on the sections C. The outer ends of each sleeve section and the inner edge of each set ring are beveled. In use a soft metallic packing is placed between the set ring and the sleeve, and is compressed firmly against the end of the pipe section by tightening the bolts which pass through the lugs B. A patent on this improved type of coupling has recently been granted to Messrs. Erick T. Christensen and David M. Tulloch, Hanover Square Building, New York city.

QUICK-ACTING WRENCH.

Pictured in the accompanying engraving is an improved wrench of such design that the jaws can be quickly adjusted to the work, after which they may be moved to clamp the work as tightly as may be desired. The wrench consists of a shank A with a fixed jaw formed thereon. Fitted to slide on the shank is a sleeve B, which is formed with inwardly-projecting flanges adapted to engage a pair of grooves in the shank A. At the end of the shank a collar is secured, which serves to prevent the sleeve B from being dis-




QUICK-ACTING WRENCH.

engaged from the shank A. The sleeve B carries the movable jaw of the wrench. Pivoted to this movable jaw is an auxiliary shank C. An adjusting screw D is adapted to engage a thread formed partly in the main shank A and in the auxiliary shank C. This screw is provided with a head at its inner end, which is seated in a groove in the shank C. In use, when it is desired to move the jaw of sleeve B quickly toward the fixed jaw, the shank C is swung downward, as shown in Fig. 1, so as to disengage the screw D from the segmental thread in the shank A. After the jaws have been moved to approximately the position desired, the shank C is swung up toward the shank A and held in engagement therewith by means of a hook, which is passed around the body of the screw D. Thereupon, by turning this screw the jaws may be drawn tightly into engagement with the work. The jaw A is provided with a serrated surface adapting it for use as a pipe wrench. In order to convert the wrench into one of ordinary form a plate E is provided, which is fitted into the jaw A. A tongue formed on this plate projects into a recess in the jaw, and a transverse adjusting screw which passes through the tongue serves to hold the plate firmly in place. Mr. C. M. C. Kirk, of Nahcotta, Wash., is the inventor of this improved wrench.

PORTABLE SAW-OPERATING MECHANISM.

A patent has recently been secured by Mr. W. K. Gor-

don, of Thurber, Tex., on a mechanism for operating cross-cut saws whereby logs, timbers, trees, or the like may be cut into blocks or lengths while the wood is flat upon the ground. The mechanism is supported on a wheeled-carriage, the wheels turning in planes at right angles to that of the saw so that the carriage may be moved along the log to bring the saw to a new place for cutting. The saw is operated by a gasoline or electric motor, mounted on a carriage.




PORTABLE SAW-OPERATING MECHANISM.

The power is transmitted by means of belts and pulleys to a crank shaft on which a disk is secured. A pitman engages a crank pin on this disk and its opposite end is pivoted to a curved or segmental bar. An arm is adjustably pivoted to the bar at one end, while the other end is mounted on the crank shaft. The lower end of the segmental bar carries the saw which is pivoted thereto. A cable attached to the arm passes over a pulley and to a winding drum. This provides means for lifting the saw when it is desired to move the mechanism about, and a stop pin in the bar projects under the saw and prevents it from swinging down to the ground. In operation the machine is placed to bring the saw in position for cutting the log. The ratchet mechanism on the winding drum is then released, permitting the saw to drop down on the log. At the outer end of the saw is a shoe formed with a curved under face. Now, when the motor is operated the pitman will cause the segmental bar to oscillate on the outer end of the arm as a fulcrum, and thus move the saw back and forth. As the cutting proceeds the saw will move downward on the crank shaft as a fulcrum. The shoe on the end of the saw serves first to weight the saw and assist it in its downward movement, and then, by engaging with the ground, to prevent the saw teeth from touching the ground and being injured.


A NEW FORM OF MUSHROOM BULLET.

The small-bore, high-power rifle that is in general use to-day was originally designed as a military rifle, the object of which is to wound or maim at extreme range; and owing to its high velocity, the trajectory is so flat that the raising or changing of sights under ordinary circumstances is unnecessary. Sportsmen, seeing the advantage gained by great velocity, were quick to adopt this type of rifle. It was found that by inverting the jacket of the full metal-patched bullet



A NEW MUSHROOM BULLET AND THE WOUNDS IT MAKES.

so as to leave the soft nose exposed, this bullet when striking hard substances such as bone, will very often mushroom or expand, causing a severe wound. Improvements in powder have from time to time increased the velocity of these bullets until they now have a muzzle velocity of 2,700 feet per second. With this velocity even the soft nosed bullet will pass through the animal without expanding in the least until some hard substance is struck, when it is apt to fly to pieces. The great heat caused by friction in the air causes the bullet to cauterize the veins and ar-




AN IMPROVED NETTING FOR AIRSHIPS.

teries, causing little bleeding and thus making it impossible for the hunter to track his game by the blood. It is stated on reliable authority that this year in Nova Scotia over forty per cent of the game hit or wounded escaped, some to die a lingering death in great agony.

To overcome these objections to the ordinary bullet, Mr. G. H. Hoxie, 4440 Michigan Avenue, Chicago, Ill., has invented the form of bullet illustrated in section in the accompanying drawing. The bullet consists of a jacket with a filling of lead in which a steel ball is seated. In another construction a steel wedge is used in place of the ball. Behind the ball is a chamber formed in the filling. When the bullet strikes an object the ball is forced into the chamber, expanding it and tearing it open. One of the illustrations shows the character of wounds produced by this bullet as compared with other wounds. The arrows 1, 2, and 3 point to wounds produced by the ordinary soft-nosed bullet. The wounds made by the improved bullet are four or five times larger, and need no designating arrows.

PORTABLE COAL BIN.

The common coal scuttle is a very primitive device, which in nowise meets the requirements of the ordinary household. It is impossible to scoop a shovelful of coal out of it without tipping the scuttle, unless the scuttle be filled to the top, and in the latter case there is danger of spilling the coal over the floor. Furthermore, the scuttle is of entirely too small a capacity to supply the needs of the ordinary kitchen range. This deficiency is particularly felt in flats and apartments; and in order to meet these special needs, Mr. August H. Koch, of 230 West 142d Street, New York, has invented a portable coal bin of sufficient size to receive a sackful of coal, and so arranged that the coal may be shoveled out of it with equal facility, whether the bin is full or nearly empty. The accompanying engraving clearly illustrates the device. It consists of a metal box with a hinged lid at the top, covering the opening through which the coal may be poured into the bin. At the lower end of the bin is an inclined chute or slide, which directs the coal toward the rear. A door opens into the bin at the bottom, and when this is open the coal may be scooped out with perfect ease. The door is formed with side walls which prevent the coal from spilling when it is shoveled out. At the side of the bin is a rack adapted to hold a shovel, poker, etc. It will be noticed that the lid at



PORTABLE COAL BIN.

the top and the door at the bottom render the bin entirely dustproof. Not only is the bin of advantage as a place for storing coal, but it provides a convenient receptacle for trash and sweepings which may be thrown in, and later, as they work their way down through the chute, taken out with the coal and burned.

IMPROVED NETTING FOR AIRSHIPS.

One of the difficulties encountered in the dirigible balloon or airship is the tendency of the gas bag to sag in the middle, the gas going toward both ends, thus changing the form of the bag and rendering the airship uncontrollable. To obviate this it has been customary to use a second internal bag or "ballonette." This requires a continuously-operating air pump to keep up the pressure in the internal bag. Capt. Thomas S. Baldwin (Box 78, Madison P. O., New York city), has recently received a patent on a means for preventing this collapse of the gas bag without employing a ballonette. This result he attains by inclosing the bag

in a netting, having a square or other form of mesh, which enables the lines of the netting bearing the weight of the frame, to extend truly vertically and to be of equal length. This places an equal strain on the gas bag, practically throughout its entire length, and it retains the bag in its correct form. At its extremities the bag is inclosed in netting caps, which may be of the usual diamond or diagonal mesh and which are connected to the main portion of the netting. The frame of the airship is constructed in triangular cross sectional form and is suspended from the netting by means of hanger lines which reach down to the bottom of the frame. The frame is prevented from undue rolling and is held in the correct position by means of guy lines which pass from the sides of the netting to the upper part of the frame. As shown in the illustration the frame consists of three longitudinal stringers connected at intervals by braces of equal length so that its cross section is that of an equilateral triangle. The peculiar manner of supporting the frame allows a certain swaying thereof, but within well-defined limits.

Patents, Trade Marks, and Copyrights in the Panama Canal Zone.


On the secession of Panama from the Republic of Colombia, there was a great deal of uncertainty for a time concerning the status of patent and trade-mark rights and the laws for their protection in Panama, and this uncertainty was made even more annoying for inventors and merchants by the further complications which existed in the Canal Zone by the formal lease of that important strip of land to the United States, with authority on the part of the lessee to govern the leased territory. The Republic of Panama many months ago made provision for the protection of inventions and trade marks, but these enactments did not extend protection to the Canal Zone, which is not under the administration of the Republic of Panama, but is governed from Washington. The Administration, in whose hands the governing of the Canal Zone has been intrusted by Congress, was requested many times to make some ruling which would enable interested parties to protect their inventions and trade marks, but no action was taken until, on March 12, 1907, the Hon. William H. Taft, Secretary of War, issued an executive order extending the United States patent, trade-mark, and copyright laws to the Canal Zone, which has the effect of protecting in that territory, in the names of the legal owners of record, all United States patents, trade-marks, and copyrights issued or registered in the United States. The issue of this order is one more step for the protection of the rights of classes of people who have ever been foremost in the development of trade and the technical and the fine arts.

Tantalum has been hammered into sheets, which are extremely hard. Sir William Crookes, F.R.S., states that "a hole had to be bored through a plate of this metal, and a diamond drill was used, revolving at the rate of 5,000 revolutions per minute. This whirling force was continued ceaselessly for three days and nights, when it was found that only a small depression 0.25 millimeter deep had been drilled; and it was a moot point which had suffered the more damage—the diamond or the tantalum."

ATTACHMENT FOR SEWING MACHINES

The seamstress while seated at the sewing machine finds it often necessary to use pins or a needle and thimble for basting certain parts together, and for this reason Mr. Andrew B. Rosenthal, 872 Clinton Street, Milwaukee, Wis., has devised a simple pincushion attachment which can be readily applied to

the ordinary sewing machine. The attachment consists of a plate bent over at the upper end and formed with an aperture, which may be fitted over the usual stud or spool holder. This plate hangs down against the side of the machine frame and carries, at its lower end, the cushion in which needles and pins



ATTACHMENT FOR SEWING MACHINES.

may be inserted. At one side the plate is formed with an upwardly-projecting horn on which a thimble may be seated. Above the pincushion is a piece of sandpaper or emery paper, which may be used in sharpening the points of the needles or in removing any rust therefrom. The cushion is sewed to the plate by passing the thread through slits cut into the plate, and the emery paper is held between a pair of nibs formed on the plate. The device can thus be very simply made, as the principal part is the plate, which may be stamped out of sheet metal. In order that the attachment may fit any size of spool holder, the aperture in the plate is fitted with a rubber washer, on which tongues are formed which fit snugly against the stud.

ROLLER APPLIANCE FOR ROCKING CHAIRS.

A very simple attachment, whereby a rocking chair of the ordinary construction can readily be converted into a wheeled invalid chair, has recently been invented by Mr. E. W. Raymond, of 452½ South Broadway, Los Angeles, Cal. The accompanying engraving clearly shows the construction of the attachment and its method of application. It consists of an axle A, on which a pair of rubber-tired wheels or rollers are mounted, and a yoke frame B carried by the axle. The yoke frame comprises a long carrying bar parallel with the axle, and having offset ends formed with eyes which are journaled on the axle. In use this simple truck is slipped under the rocking chair, the rockers passing between the carrying bar and the axle. The chair is rocked forward to permit the axle A to bear against the rear posts of the chair, while the carrying bar bears against the treads in advance of the axle. In this position the appliance is held by means of a diagonally-disposed tie-rod C, which is hooked over the carrying bar and is fastened at its upper end to the seat of a chair. Now, when the chair is tipped back it will be lifted on the rollers. The offset ends of the carrying bar B are made longer than the width of the ordinary rockers, and the appliance is thus made to fit different sizes of rockers. When the truck is detached from the chair, the tie rod C is folded up against the bottom of the chair seat and is held in place by a hook D. The device should prove of especial value for use in cases of temporary illness, when it would not pay to purchase an invalid chair.



ROLLER APPLIANCE FOR ROCKING CHAIRS.

RECENTLY PATENTED INVENTIONS. Pertaining to Apparel.

GARMENT.—A. BERMAN, New York, N. Y. The object of the invention, which is an improved garment having a special reference to dresses and shirt-waists for children or other like garments, is to so construct the dress or waist that it may be readily and conveniently slipped on and off, especially avoiding the use of buttons or the like attaching devices for holding the garment on the body.

Electrical Devices.

COMBINED LIGHTNING-ARRESTER, FUSE-BOX AND INSULATOR.—R. R. BURRIN and T. F. GAEBLER, Rockville, Ind. This invention relates to electric construction, and its object is to provide a convenient device which will constitute a fuse-box, a lightning arrester and an insulator. By enclosing the fuses and the arrester within a porcelain box, there is no danger from fire in case the fuses burn out or a lightning bolt passes through the device.

PARTY-LINE TELEPHONE SYSTEM.—F. VOLLMER, Winsted, Minn. This improvement relates to telephone systems of the general type represented in that described in Mr. Vollmer's former patent and used for selective signaling between stations. Further, it relates to providing such a system with an automatic time-controlled cut-out, whereby the system after use will return automatically to its normal condition within a predetermined length of time.

KICK-BOARD.—W. H. NICOLAY, New York, N. Y. This board is designed to be applied to a base board adjacent to the floor, and the object of the inventor is to provide means adapted to inclose and protect insulating tubes which extend through the floor boards for the purpose of receiving electric wires passing through the floor, thereby protecting the wood-work from the wires.

SPARK-ARRESTER.—C. S. CHALFANT, El Paso, Texas. The design in this case is to provide a device which will enforce the economical consumption of fuel, eliminate danger and discomfort caused by escaping sparks and cinders, and increase the efficiency of the locomotive by dispensing with the usual obstructing screens, nettings, etc., detrimental to good steaming qualities. The invention provides an arrester which will not choke the draught in the smoke box and thereby cause the blowing of smoke and fire out through the fire-box door into the cab.

ELECTRIC SIGNAL.—E. LIONAIS and W. T. SUTTON, Montreal, Quebec, Canada. In this patent the invention has reference to electric signals, and more particularly to a system for ringing one or more electric bells from a distance. It further relates to a system in which a relay is employed for controlling a bell and in which a single battery is used for energizing the relay and for operating the bell.

KEYBOARD TELEGRAPH-TRANSMITTER.—G. M. GODDARD, Rutland, Vt. The invention consists in the construction and arrangement of the train of mechanism which by the operation of the keys causes the proper opening and closing of the circuit to produce dots and dashes representing the particular key struck. The mechanism may be applied to a type-writer, whereby at the same time a Morse signal-message may be sent and a duplicate of it in type-printed letters may be made at one operation, means permitting the transmitter to be used without printing on the typewriter or the latter used without the transmitter, or both used together.

Of Interest to Farmers.

COTTON CHOPPER AND CULTIVATOR.—J. B. FARRAR, Wilmington, N. C. The invention is an improvement in the class of cotton-choppers in which a disk, or wheel, provided with knives is rotated for cutting out and thus spacing the planted cotton. The inventor has devised improvements in the chopper proper and in attachments for breaking or pulverizing the earth about the roots of the plants.

Of General Interest.

COMBINED SETTEE AND BERTH.—G. S. SHERMAN, Nyack, N. Y. This combination is particularly adapted for use on yachts or other water craft, or, it may be used under other conditions, the object being to provide a device that will take up no more room than the usual settee or bed, the construction being such that the apparatus may be easily and quickly converted from one use to the other.

RECORD-CALENDAR.—F. H. RICE, Oakland, Cal. The purpose of the inventor is to provide a calendar adapted to serve as a reminder of transactions to be attended to in the future, and which takes the place of the customary daily journal, the advantage being that in entering any subject requiring attention at a certain time of the month, one entry will carry for all time, whereas in a daily journal twelve entries are required each year for monthly matters.

PILE STRUCTURE.—J. T. PYLE, Amarillo, Texas. The invention pertains to improvements in structure formed of sheet piling driven into sand or soft earth and having the inclosed material removed, whereby the pile may be filled with concrete to serve as a foundation for bridges, buildings, and the like. The walls of the structure are made up of a large number of sections which are driven into the

sand or soft earth one at a time and each succeeding one upon being driven becomes locked to the last one inserted.

BALE-TIE.—A. K. KLINGENDER and DEW. M. COINER, Statesville, N. C. The invention is especially designed for use in securing small packages of papers, such as a series of checks, together. It is also applicable as an improved tie binder for cotton and other heavy materials in bales, the buckle being made of sufficient weight to supply the necessary strength for such service.

FENCE OR DIKE.—J. W. HUMPHREY, St. Johns, Ore. This invention has reference to fences and dikes, and the object in view is to construct a fence or dike in a simple manner, so that it may be readily erected, and to arrange the parts so as to allow for contractions and expansions due to temperature changes and other causes.

APPARATUS FOR PROCESSING SUGAR-CORN.—L. S. FLECKENSTEIN, Easton, Md. In the present patent the invention is an apparatus designed and adapted for processing canned sugar-corn, or like products, by a continuous method whereby the result is effected much more quickly and economically than by the apparatus and methods ordinarily employed. By the use of this apparatus, sugar-corn and like products may be processed without the aid of hand labor.

EGG-LIFTER.—C. F. SWANSON, Eagle Bend, Minn. The invention pertains to improvements in devices for lifting eggs from a crate for the purpose of transferring the eggs to a tester, and returning the same to the crate after testing, the object being to provide a device by means of which all of the eggs in a layer in the crate may be simultaneously picked up.

CHAIN-LINK SHACKLE.—G. A. H. DRESLER, 25 Karlstrasse, Kiel, Germany. The object in this invention is to so construct the parts of the connecting shackle that the means for fastening the closing part to the link will be subjected to but little strain, speedy release and opening is possible, and shocks exerted upon the closing member from outside are kept from the stud ends of the links.

RECEPTACLE FOR POWDER.—F. H. ABOTT, Crystal Falls, Mich. The purpose of this invention is to provide an efficient and inexpensive device which will securely retain the powder or like substance when not in use, and at the same time permit the contents to be readily dispensed therefrom in small quantities. It is especially useful in connection with cans for tooth powder.

MOLD FOR CONCRETE POSTS.—J. P. DONOVAN, Georgetown, Ky. The object in this improvement is to provide a mold for making concrete posts, such as are more especially used in the construction of fences, the mold being arranged to permit the production of posts in an economical manner, the posts combining strength with lightness, and not likely to warp or crack.

MOISTENING ATTACHMENT FOR DENTAL ENGINES.—G. BARTLETT, Lenapeh, Ind. Ter. The invention relates to improvements in dental engines, and more particularly to means for moistening the disks, burrs, or drills while they are being used. By slightly opening a valve, water is delivered to the tool and the ground material washed away from the tooth operated upon, and the tool may be prevented from becoming heated to an uncomfortable temperature.

VAGINAL DOUCHE.—E. J. LAMPORT, Cape Town, Cape Colony. This douche can be inserted in the canal in a collapsed state and then inflated so as to straighten out and render the folds of the parts smooth, whereby the liquid introduced through the instrument and flowing under pressure between the inflated wall of the instrument and opposing wall of the organ will thoroughly wash and disinfect all of the membranes.

BOTTLE-STOPPER.—H. MORGAN, Cripple Creek, Col. This invention has reference to a closure for beer-bottles, mineral-water bottles, etc., and has for its object the provision of an inexpensive device easy to apply to the bottle and easy to remove, but in which there is no liability of its being accidentally displaced by internal pressure or rough handling.

TEMPORARY HOLDER FOR SAFETY-RAZOR BLADES.—D. A. MACBETH, New York, N. Y. One purpose of this invention is to so construct the device that the holder proper will be practically in one piece, the only other factor employed being a clamp mounted upon the jaw-section of the holder, and, further, to so construct the section that the blade can be quickly and conveniently introduced between the jaws in such manner that the blade will remain in set position while the clamp is being applied.

ADJUSTING CLOCKS AND WATCHES TO CHANGES IN TEMPERATURE.—S. KAHAN, New York, N. Y. The object in this instance is to provide means for varying the length of the suspension-feather of a pendulum, or the hair-spring of a watch, or the oscillating member of any other form of timepiece, so as to offset the variation in length caused by changes in temperature.

FENCE-POST.—E. D. MINER, Rathdrum, Idaho. Among the objects of this inventor is the provision of a device both strong and durable, on which fence-wires are to be strung and which can be easily and readily set in position and the wires assembled therewith or disassembled, and the post dismounted when

the fence is to be removed or shifted to a different position.

MAKING CONCRETE WALLS.—F. M. JACKSON, Akron, N. Y. The inventor provides improvements in making concrete walls for buildings, whereby the wall can be quickly and cheaply constructed and when finished is provided with an airspace at the back, and the front face of the wall has an ornamental appearance, thus rendering the wall very desirable for use in the construction of chimneys, fireplaces, and the like.

METHOD OF TREATING GLASS.—W. E. HEAL, Coffeyville, Kan. In the present patent the improvement has reference to a system for treating glass, Mr. Heal's more particular object being to draw the glass into flat sheets suitable for commercial use, and to enable the sheets to be made cheaply, and yet to be comparatively free from imperfections.

CIRCULAR-DISTRIBUTER.—R. G. FRASER, Philadelphia, Pa. The principal objects here are to provide for effectively pressing circulars and the like into such a position that they can be readily abstracted from the distributor by the public without necessitating any complicated manipulation of the parts, and especially to provide means whereby only one circular can be removed at a time. For this purpose a special form of envelope has been designed for containing the circulars, which can be used with the remainder of the device with advantage.

VALVE.—A. L. DOW, Lyons, Col. This invention pertains to improvements in valves, and especially in hydrant-valves, whereby the valve and valve-seat may be removed from the casing without disconnecting the latter, should it become necessary to repair or replace any working parts. This is of particular value around hydrant-valves, which are usually so located that it is very difficult to get at the valve to repair it.

COUNTER-STOOL.—W. G. WINANS, Spokane, Wash. The inventor seeks to avoid some of the objections incident to stools in common use—such, for instance, which are permanently fastened to the floor, where they cannot be readily removed, and others fastened to the front of the counters, where the weight of persons sitting on them exerts a certain strain on the counter sufficient sometimes to tilt the counter. He provides a revolving stool which can be adjusted as to height, easily removed, adjusted to position for use or up against the counter out of the way.

GATE.—W. M. WATSON, Brantford, Ontario, Canada. The gate may be operated in a vehicle without dismounting and similarly closed after the person has driven through. It may be raised to swing over stones or obstructions, but when closed may rest close to prevent small animals from crawling under. It may open in either direction, but be automatically prevented from swinging past the closed portion when being shut.

Hardware.

BELT-TOOL.—E. E. BARNETT, Kremlin, Oklahoma Ter. The improvement is a belt tool having means for punching and cutting holes in the ends of a belt such as are generally provided to receive the lacing; also embodying in its construction a device for drawing the lacing through these holes in the belt, and lacing the ends thereof together.

PUNCHING IMPLEMENT.—J. W. SPENA, Wakeeney, Kan. The object of this invention among others, is the provision of a strong, powerful, hand-operated punch for punching holes in sheet metal and other materials. The punching or cutting tool is mounted in the implement in a manner to at all times remain normal to the work during the punching operation.

PLIERS.—G. G. WORSTALL, Toms River, N. J. The object of the improvement is the provision of a pair of pliers, more especially designed for the use of jewelers, and arranged to permit convenient and quick drawing out and shaping of the claws on new or old settings of the Tiffany, skeleton, or other type.

Heating and Lighting.

GAS AND AIR BURNER.—D. COOLEY, Galena, Kan. This burner is designed for use in heaters, furnaces, and the like arranged to cause a thorough mixing of the gas and air previous to ignition of the mixture with a view to insure a complete combustion of the mixture, the arrangement also permitting independent regulation of the supply of gas and air according to the richness of the gas.

Household Utilities.

WASHBOARD.—S. B. COOK, Laurel, Miss. Mr. Cook's invention is in that class of boards whose scrubbing surface is formed of a series of rectangular bars arranged transversely and held detachably in the side bars of the frame. One of the washboards of this invention is equivalent to four of the ordinary kind. A new set of bars can be supplied at trifling cost when the four corners of the scrub bars are worn off, rendering the board practically new.

SAD-IRON.—J. E. AUSTIN, Binghamton, N. Y. This iron is heated by burning gas, and the design is to provide an iron which is simple and arranged to insure a uniform heating with a minimum consumption of gas and to produce a complete combustion of the gas, to render the use of the iron very economical and practically odorless.

WASTE FOR BATH-TUBS, BASINS, AND LIKE FIXTURES.—P. F. GUTHRIE and T. HAYES, Nutley, N. J. The invention provides a waste or outlet for bath tubs, basins, etc., arranged to insure a free outflow of the water from the tub, basin or like fixture, and without danger of the outflowing water becoming air-bound, and prevents foul air rising in the waste and passing into the room in which the fixture is located, thus rendering the fixture completely sanitary.

MOP-WRINGER.—J. L. POTTS, Ithaca, Mich. This improvement pertains to washing and scrubbing; and its object is the provision of a new and improved mop-wringer arranged to permit of conveniently and quickly placing the mop in position between the mop-wringing rolls to insure a proper wringing of the mop.

STOVE OR FURNACE ATTACHMENT.—L. D. MOHLER, McPherson, Kan. This inventor provides an unfailing draft from the grate of a stove or furnace upward into and through fuel, effectually preventing smothering of the fire in the use of slack, coal dust, or similar fuel; also conducts air above the fuel to carry away surplus gas, and thus prevent an explosion, and, further, operates to deflect air conducted above the fuel across the top of the fire, with such clearance above the fuel as to employ the air for combustion of gas and smoke in the combustion chamber and hold the heat downward and so spread the products of combustion for the purpose of warming the floor.

BED.—L. H. FLANDERS, Memphis, Tenn. The mattress-frame being in position and each bevel-gear in mesh with respective bevel-gears, rotation of a shaft will move all the slides upward, thus moving the frame in its entirety and with sections in aligned position. To raise the head-section to bring the patient into sitting position with legs extended, the gears actuating the slides connected with two frame sections are moved out of mesh by means of levers, when rotation of the shaft will move the head-section into angular position with respect to other sections.

STEAM-COOKER.—C. S. EPPLEY and M. E. STONESIFER, York, Pa. The cooker comprises a casing divided into an upper steaming compartment and a lower baking compartment. Doors give ready access to the compartments. The bottom of the baking compartment is raised above the casing bottom, affording boiler space beneath it for the heating branch of the boiler and bottom plate of the casing, which forms, with the bottom of the baking compartment, the boiler chamber at the casing bottom in which the heat accumulates surrounding the heating branch of the boiler.

IRON-HOLDER.—MARIE AGNEESSENS, New York, N. Y. In ironing certain materials an objectionable glossy appearance is given. This has been overcome by holding the iron in an inverted position and drawing the material back and forth across its face. The invention provides a simple device for sustaining the iron in an inverted position, leaving the handle easily accessible in placing the iron on the holder or removing it.

Machines and Mechanical Devices.

CASH-REGISTER.—T. H. HARRIS, Fredericksburg, Va. This apparatus is for use in shops, stores, warehouses, etc., for registering sales of goods and the amount paid therefor, and also for receiving and holding the cash or vouchers deposited in payment. It is a simple and effective substitute for the expensive cash registers which are in general use, and has marked advantages over them in respect to furnishing a complete record of sales or other transactions.

MACHINE-ROLLS.—C. F. STEIBER, New York, N. Y. This invention relates to machine rolls, and the object is to produce a machine which is especially adapted for rolling the parts of metal stair cases. In this connection, the invention is most useful in forming stringers, risers, and similar parts having flanges which project in opposite directions.

CONCRETE-MEASURING MACHINE.—A. F. NIMS, Philadelphia, Pa. One purpose of the inventor is to provide a machine for measuring concrete or concrete mixtures, or the like, and for delivering the measured material to any desired receiver; which machine is portable and low, enabling material to be easily shoveled into it or dumped therein from wheel-barrows with the assistance of low platforms.

CONCRETE-MIXING MACHINE.—A. F. NIMS, Philadelphia, Pa. Of the several purposes of this improvement, one is to provide a machine which will thoroughly mix material in a very short time and one in which the material may be permitted to remain in the machine for any desired length of time, or be released at intervals, or at any proper time.

WAVE-MOTOR.—J. W. NEAL, Kalia, Ter. of Hawaii. This invention relates to wave motors particularly adapted for use in deep seas, the object being to provide a deep sea motor so constructed as to respond readily to the movements of the water, such as waves and swells coming from every possible direction, and by means of which air is compressed and conducted to machinery on shore as a motive agent.

MECHANISM FOR PROPELING VEHICLES OVER LAND AND WATER.—J. A. HILDEBRAND, Olympia, Wash. The invention

pertains to certain improvements in mechanism adapted to be applied to boats, vehicles, and the like, whereby they may be propelled with equal facility over the surface of land or water. The intervention of streams or lakes would in no way impede the progress of a traveler were his vehicle equipped with this device.

CONTRACTIBLE MOLD.—G. GEORGENSON and J. E. HENNEN, Fond du Lac, Wis. This flexible mold is for use in the construction of arches, culverts, sewers, or the like in which a temporary support is required for the cement, brick, or stone employed in the construction. In carrying out the invention what may be termed a "cylinder" is employed, the same being formed of sheet metal and provided interiorly with means for expanding and contracting it.

AIR-SHIP.—J. SHUKWECH, New York, N. Y. The ship has a main deck mounted on a supporting means for sustaining the weight of the ship when on the ground and maintaining it in an upright position when in flight. Wings are pivoted at each side of the ship, connected with suitable means for oscillating them, and propellers are journaled at each side of the bow of the ship and act to direct a current of air under each of the wings in driving the ship forward, which currents tend to force the wings upwardly.

LAWN-CLEANER.—C. H. MOSHER, Salisbury Mills, N. Y. The object of this invention is to produce a machine which is of simple construction and which can be readily moved across a lawn in the manner of a lawnmower, operating at the same time to pick up any articles which may pass under it and which may be operated by horse or motor power.

FABRIC-TESTER.—R. C. HARRIS, Roselle, N. J. The invention relates to improvements in devices particularly designed for testing the strength of paper, the object being to provide an instrument of this character that will be of comparatively small and compact form, so that it may be carried in a person's pocket and operated by hand pressure.

Prime Movers and Their Accessories.

VALVE.—A. SIMPSON, New York, N. Y. In this instance the invention relates to valves such as used in pipe systems. The valve is intended to be used for water, steam, gas or other fluids. The object is to produce a valve of simple construction which will be well adapted to maintain heavy pressures and which will reduce tendency to leakage.

AUTOMATIC STEAM-TRAP.—W. AUSTIN, Scranton, Pa. The aim of this inventor is to produce a device which may constitute an accessory for a steam pipe system, and which will operate to collect the water of condensation, and expel the same automatically and periodically without allowing any escape of steam.

Railways and Their Accessories.

CAR-WHEEL.—R. P. WILLIAMS, Santa Barbara, Cal. The invention consists of a cast metal wheel having the flange thereof so formed that in case it becomes broken the broken part will not become dislodged but will present a ragged edge extending outward at an angle to the normal plane of the wheel, whereby an air valve of the brake system may be operated. The valve is so constructed that should the car wheel become broken the brakes will operate to immediately stop the train.

AIR-BRAKE ATTACHMENT.—R. P. WILLIAMS, Santa Barbara, Cal. This invention relates to improvements in air brakes for railway cars, and more particularly to means for automatically operating the brake in case that the truck of any one of the cars becomes derailed. The object is to provide means whereby any variation in the plane of the car track in respect to the car body will automatically open a valve of the air brake system and cause the instant application of the air brakes throughout the train.

RAILWAY-SWITCH MECHANISM.—O. A. KRUG, Cincinnati, Ohio. In this patent the invention has reference to improvements in railway switch mechanism, the object being the provision of a simple means whereby an open switch may be automatically closed by an approaching train in either direction, thus preventing possible accident.

RAILWAY-TIE AND RAIL-FASTENING.—A. NEWELL, Guadalajara, Mexico. The improvements are in ties for railways and rail fastenings, and the object of the inventor is to provide a metal tie that will be comparatively light, yet strong and serviceable, and further to provide a fastener that may be readily adjusted to the rail and normally hold the same from any lateral movement with relation to the tie.

STANDARD FOR LOGGING-CARS.—C. H. ALLEN, Aycock, Fla. The design in this case is to provide a standard which is to be arranged on the ends of the transverse bolsters of the car to prevent the logs from rolling off when in transit, but which is capable of adjustment to permit the easy loading or unloading of the log.

BLOCK-SIGNAL SYSTEM.—J. VAN ZANDWEGHE and L. VIBERTI, Rosario De Sante Fc, Argentina. In this patent the invention refers to block signal systems, the more particular objects being to provide efficient means for

stopping trains automatically when they approach each other within certain limits, and also for stopping them if desired when they approach a station.

Pertaining to Recreation.

GAME APPARATUS.—L. J. CASTONGUAY, Thompsonville, Conn. The object in view is to provide in this invention a game apparatus, more especially designed for playing parlor base ball, and arranged to require considerable skill on the part of the players to successfully play the game, and to afford amusement for the players as well as the onlookers.

Pertaining to Vehicles.

WHEEL-HUB.—F. F. UNCKRICH, Galion, Ohio. In the present patent the invention has reference to an improvement in wheel hubs, and it has for its object the provision of a metallic shell and the means for securing the shell in a fixed position upon the hub in a most efficient manner.

VEHICLE RUNNING-GEAR.—P. RICHARDSON, Kennebago Lake, Maine. Withstanding the shock of very rough roads and avoiding its transmission to the occupants, in this case, is accomplished by providing for the yielding in all directions of an upper frame on which the body of the vehicle is mounted, as by a system of springs comprising upright springs for yieldingly maintaining the weight of the body and the occupants and diagonally-extending longitudinal and transverse springs for admitting of a yielding end and side movement of the body, respectively.

TRACTION-ENGINE STEERING-GEAR.—R. RICHARDSON, Yates Center, Kan. The gear is designed particularly for use in connection with traction engines, but applicable in other ways. It may be applied to automobiles and all motor vehicles with equal ease, the shaft being either the crankshaft of the engine or some continuously rotating shaft driven from the engine.

DUST-COLLECTOR FOR WHEELED VEHICLES.—J. M. WEAVER, New Oxford, Pa. The invention relates particularly to improvements in attachments for automobiles or similar vehicles for receiving dust rising from the vehicle wheels and discharging the same in a wet or condensed condition, thus obviating the annoyance from the spread of dust incident to such vehicles as ordinarily equipped.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.



HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication. References to former articles or answers should give date of paper and page or number of question. Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and though we endeavor to reply to all either by letter or in this department, each must take his turn. Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same. Special Written Information on matters of personal rather than general interest cannot be expected without remuneration. Scientific American Supplements referred to may be had at the office. Price 10 cents each. Books referred to promptly supplied on receipt of price. Minerals sent for examination should be distinctly marked or labeled.

(10521) O. J. S. says: 1. Which telephone lines do you consider to give the best service in rural districts—ground or metallic? Can you advise me a good book on practical ground line telephony? A. A metallic circuit is best for all telephone lines, but the cost is so much greater that the grounded circuit is usually employed upon rural circuits. Long-distance lines are always metallic. The best book upon the telephone is Miller's "American Telephone Practice," which we send for \$4. 2. How do you find the distance between the earth and the sun? Give me a simple formula for calculating that distance. A. It is a long story to tell how the distance of the sun from the earth is found. Consult any college astronomy in the University library. The distance is computed from the parallax of the sun. 3. If the radius of a certain pulley is 4 inches and of another is 12 inches, and the distance between their centers is 6 feet, how would you calculate the length of a belt running around these two pulleys? A. The length of the belt you desire will be given with sufficient exactness by adding to 12 feet one-half the circumference of each of the pulleys. 4. Where, for good ventilation, should a ventilator be situated—near the top or the bottom of a wall? Is it better to have two ventilators one in one corner and another diagonally across? A. There are all sorts of opinions upon the location of ventilators. The usual practice is to place them both at the top and bottom of the room, so that either register may be opened. We do not think one ventilator in one corner and another in a diagonally opposite

corner should be preferred. 5. How do you find the horse-power of a common steam engine? A. To find horse-power of a steam engine, multiply the mean effective pressure in pounds per square inch by the length of stroke in feet and by the area of the piston in square inches, and by the number of single strokes per minute. If the piston passes through one end of the cylinder head, subtract one-half of the area of the piston rod from the area of the piston; but if it goes through both ends of the cylinder head, subtract the whole area of the rod from the area of the piston. Divide the product of these numbers by 33,000.

(10522) E. B. S. says: To render theaters safe from fire, a policeman should be on the stage near the curtain, having in his hands or close by one hose containing water under pressure and another hose with carbonic-acid gas under pressure. Either one can be instantly used if necessary. A scientific book says one quart of water resolved into its elements gives 1,200 quarts of hydrogen and 600 quarts of oxygen. Is it correct? If not, how much gas will result of each kind? A. With reference to the suggestion you make that a policeman should be in a theater to guard against fire, we would say that in all New York theaters firemen are on duty all the time when an audience is in the building, ready to turn on the water and use the appliances for extinguishing a fire. A fireproof curtain would be dropped in an instant, and a rope cut, which would open large scuttles above the stage, so that any smoke upon the stage would be drawn up as by a chimney into the open air, and no fire or smoke would or could be drawn out into the house where the audience is seated. The statement is correct that two quarts of water contain 1,200 quarts of hydrogen and 600 quarts of oxygen, when the barometer is at 30 inches and the thermometer is at the freezing point, or 32 deg. Fahr. Unless the pressure and temperature are stated, any statement of quantity of the gases is meaningless.

(10523) L. A. C. asks: Why does not a submarine boat sink all the way to the bottom of the ocean? I understand the method used in plunging submarines is to admit water into tanks, so as to give the boat more weight, weight enough to cause the boat to sink only 50 or 60 feet. It sinks at the surface. Why does it not sink to the bottom? Would a hollow steel ball weighing 65 pounds and having a displacement of one cubic foot (when under a pressure of 4,600 pounds per square inch) sink to the bottom of the ocean, where a cubic foot of water weighs 66.56 pounds (27.366 feet below surface)? I should say that such a ball would sink to a depth of approximately 10,300 feet and there remain suspended. Am I right or wrong? What is the principle involved in the toy known to schoolboys as "the devil in the bottle"? This toy is a bottle filled with water, in which is contained a small hollow image, which image can be made to sink or float in the water, or even to remain suspended half way between the surface of the liquid and the bottom, by manipulating a diaphragm closing over the neck of the bottle. A recent controversy leads me to these questions. A. The submarine and the "devil in a bottle" are instances of the application of Archimedes's principle. The little imp in the bottle is known in science by the name "Cartesian diver." Archimedes stated the principle that a body immersed in a liquid loses as much weight as the weight of the liquid it displaces. If the liquid displaced weighs less than the body, the body sinks; if it weighs more than the body, the body rises and floats partly out of the liquid; if it weighs the same as the body, the body neither sinks nor rises, but remains just where the weight of the displaced liquid is exactly equal to the weight of the body. The Cartesian diver has a little opening into the lower part of its body. When pressure is put upon the air in the top of the bottle, that pressure is transmitted through the water in the bottle to the air in the imp, and compresses the air so that water flows into the imp and makes it heavier. It then sinks. By relaxing the pressure, the imp may be stopped at some point and kept there. If the pressure is however maintained as at first, the imp sinks to the bottom without stopping, since the water has the same density in all parts of the bottle. The submarine is intended to act upon exactly the same principle in the same manner. They usually do so, but once in a while one continues to the bottom, with disastrous results to all on board. The steel ball, which you suppose, would do exactly the same as you state, if it could retain its volume unchanged, and displace a cubic foot of water at a depth such that its weight were exactly the same as that cubic foot of water. But this is not possible. Under the pressure of the water as it sinks the steel will be compressed more than the water, as we showed, even if it were solid, and when it reached the theoretical depth its volume would be less than a cubic foot and it would sink still farther, and be compressed still more till it reached the bottom. There is no place such as you suppose. There is still another impossibility. A steel ball whose volume is one cubic foot and whose weight is 65 pounds must be made of steel plate about a third of an inch thick. This would be in worse shape than the proverbial "cocked hat" long before it reached a depth of 10,000 feet, by the pressure of the water.

NEW BOOKS, ETC.

THE STONE IMPLEMENTS OF SOUTH AFRICA. By J. P. JOHNSON. 258 illustrations. New York: Longmans, Green & Co. 8vo.; cloth. Price, \$2.50.

There is much work to be done in investigating the prehistoric races of South Africa, and in fixing them in their proper places as regards their advancement. Mr. Johnson has collected some interesting material, but it is to be hoped that he will find opportunity to investigate more thoroughly the ground that he has broken. However, his reasoning is quite in accordance with the facts, and places his finds beyond doubt in the periods to which they belong.

A POCKET-BOOK OF MECHANICAL ENGINEERING. Tables, Data, Formulas, Theory, and Examples for Engineers and Students. By Charles M. SAMES. Revised and enlarged. Published by the author at 542 Bramhall Avenue, Jersey City, N. J. 195 pages, 41 figures; flexible leather. Price, \$2.

The author has increased the scope of his first edition, adding much valuable matter, without adding materially to the bulk of the book. As a pocket reference book it cannot be too highly recommended. The field covered is extensive and closely covered, yet there are no unnecessary facts to hinder the practical worker.

THE COAST MANUAL OF LETTERING AND DESIGNS. Los Angeles, Cal.: The Coast Manual Publishing Company. Quarto; cloth; 106 pages. Price, \$5.

Now that advertising is accepted without hesitation as a vital part of commercial routine, a book of letterings and designs, selected especially for their value to the "display artist," will find the readiest appreciation. The handbook published by Fred Knopf and J. M. Mahaffey is full of successful combinations that will be found most serviceable in their promptings to the experienced designer as well as to the novice.

MODERN AMERICAN MACHINE TOOLS. By C. H. BENJAMIN. New York: E. P. Dutton & Co. 8vo.; cloth; 134 illustrations, 320 pages. Price, \$5.

The object of this treatise is to show to the buyer and user the prominent characteristics of modern machine tools as now manufactured in the United States, the various points in which they differ, and some recent data as to their capacity and performance.

To the buyer in Great Britain or on the Continent, this work should be a help, as it brings together in one volume facts from a variety of sources and furnishes information which might otherwise need to be sought at much expenditure of time and trouble.

While the present work is in no sense an advertising medium, it illustrates as large a variety of machines and of makes as the space allows, giving the reader as comprehensive a view as possible, and in all cases allowing an uninfluenced opinion to be formed.

ALTERNATING CURRENTS. A Text-Book for Students of Engineering. By C. G. LAMB. New York: Longmans, Green & Co. London: Edward Arnold. 8vo.; cloth; 325 pages, illustrated. Price, \$3.

Many treatises on this subject have been written, but Mr. Lamb's work fills the need for a text-book for beginners that without being too cumbersome covers the subject of alternating currents in all its aspects.

The treatment of the question is based largely on the use of vectors, supplemented by simple analytical methods when it is desired to obtain numerical results. The symbolic treatment does not appeal to students, and has for that reason not been used. Also no attempt has been made to distinguish in the formulæ whether absolute or practical units are employed, since the unwieldy results are perplexing to beginners.

SPACE AND GEOMETRY IN THE LIGHT OF PHYSIOLOGICAL, PSYCHOLOGICAL, AND PHYSICAL INQUIRY. By DR. ERNST MACH. From the German by Thomas J. McCormack. Chicago: The Open Court Publishing Co. London: Kegan Paul, Trench, Trübner & Co., Ltd. 12mo.; cloth; 148 pages. Price, \$1.

The three essays which form the present volume were written for the Monist some four years ago. Last year they were in great part incorporated in their original German in Prof. Mach's latest published work, "Erkenntnis und Irrthum; Skizzen zur Psychologie der Forschung." In them Prof. Mach discusses the questions of the nature, origin, and development of our concepts of space from the three points of view of the physiology and psychology of the senses, of history, and of physics, in all of which departments his profound researches have gained for him a most exalted position.

SMALL ELECTRICAL MEASURING INSTRUMENTS. How to Make and Use Them. By Percival Marshall. New York: Spon & Chamberlain. 12mo.; paper covers, 90 pages, illustrated. Price, 25 cents.

A clearly-written and freely-illustrated handbook for the experimenter and investigator. By its use many instruments of equal efficiency to those sold by the regular makers can be made at very low cost.

MODERN PLUMBING ILLUSTRATED. By R. M. Starbuck. Fully illustrated by fifty full-page plates made expressly by the author of this work. New York: Munn & Co. One large 8vo. volume; cloth; pp. 392. Price, \$4.

The purpose of this work is to demonstrate in the most practical manner the best modern practice in plumbing and water supply. There is an abundance of useful information in reference to the kinds of plumbing materials and fixtures and the installation of these for the modern cottage, or the more pretentious house, apartment house, hotel and office building. The purpose of this work is to demonstrate by liberal scale drawings, which cover almost every imaginable condition likely to come before the plumber, architect, and sanitary engineer. The book will be found valuable to the plumber in his actual work, giving special details as to size and weight of pipes required under different conditions. To the architect it will be found suggestive and will aid in preparing plans and directing and superintending work; to the owner in aiding him to secure the best and simplest systems for his building; to the plumber inspector the many practical features it presents will remind him of the methods to be pursued to secure safe and healthful sanitary conditions, and to the plumbers, practical methods of executing the work. The book presents, in a word, the latest and best modern practice, and should be in the hands of every architect, sanitary engineer and plumber who wishes to keep himself up to date in this important feature of construction.

A TEXT-BOOK OF SANITARY AND APPLIED CHEMISTRY, OR THE CHEMISTRY OF WATER, AIR, AND FOOD. By E. H. S. Bailey. New York: The Macmillan Company. 12mo.; cloth; 345 pages. Price, \$1.40.

Although some knowledge of chemistry is necessary for a thorough assimilation of the present work from the theoretical standpoint, the layman will find it unusually instructive. Chapter I. treats of the "Atmosphere," its composition and the impurities affecting it. Chapter II. deals with "Fuels," and Chapter III. deals with "Heating and Ventilation." Chapter V. on "Water," and Chapter VI. on "Purification of Water Supplies" are highly important. The rest of the book is devoted to foods, etc. As a whole, the work is concise, well written, and not too technical to be of universal value.

GLUE HANDLING. Part I. Twelve Chapters of General Information. By F. H. Kahrs. East Haddam, Conn. Price, \$1.

A handbook of value to all glue users, being the result of the author's observations during his eighteen years of experience as a glue expert. It is too bad, however, that such an excellent work should have its attractiveness, if not its usefulness, lessened by the introduction into the text of matter of a purely advertising nature.

SOME CITIES AND SAN FRANCISCO AND RE-SURGAM. By Hubert Howe Bancroft. New York: The Bancroft Company.

An interesting comparison of San Francisco and the late disaster with other cities and the calamities that have befallen them. Every line is full of the local pride and confidence that go so far to make up the body of American patriotism.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Issued

for the Week Ending

April 30, 1907.

AND EACH BEARING THAT DATE


(See note at end of list about copies of these patents.)

Acid cooling and generating chamber, I. P. Libme	852,390
Advertising device, H. F. Eckersberg	852,170
Aerial vessel, T. Orgren	852,292
Aeroplane, navigable, B. F. Mickle	851,683
Agitator, F. W. Cowan	852,114
Agricultural implement, P. Petersen	851,959
Air brake apparatus, R. J. Wilson	852,007
Air brake system, D. M. Daley	852,108
Air brake system and engine's valve, G. Macloskie	851,818
Air purifying apparatus, J. H. Kinealy	852,122
Air ship, J. C. Reckweg	852,239
Alarm mechanism, automatic, C. Breiland	851,915
Alloys, producing low-carbon ferro, E. F. Price	852,347
Amusement apparatus, N. G. Warth	852,149
Amusement device, W. T. Watson	852,248
Anchor, sea, F. Rose	852,009
Animal trap, O. H. & F. H. Voelkerding	851,716
Animal trap, J. W. F. Rose	852,009
Ankle supporter, R. F. Le Mat	851,950
Anti-skidding device, J. M. M. Blanchard	851,857
Apparel, C. R. De Boisse	852,262
Automatic brake, J. J. Muller	851,766
Automatic switch, J. Hency	851,935
Automobile controlling means, H. Lemp	851,762
Axle stub, Detar & Schoonover	852,169
Bag holder, M. E. Eagleton	851,873
Baking pan, B. Morrow	851,826
Bale of fibrous materials, H. J. Duncan	852,015
Baling press, W. F. Truelsen	851,714
Baling press, L. P. Agnew	852,252
Banded stave pipe, J. S. F. Marks	852,336
Barrel trussing and hoop driving machine, J. B. Stanhope	852,040
Battery. See Dry battery.	
Bearing, centrifugal separator, C. H. Shaw	852,203
Bearings, ball holding ring for ball, S. Schneider	851,697
Bed, N. S. Stein	852,041

Wood-working Machinery

For ripping, cross-cutting, mitering, grooving, boring, scroll-sawing edge molding, mortising, for working wood in any manner. Send for catalogue A.

The Seneca Falls Mfg Co., 185 Water St., Seneca Falls, N. Y.



Engine and Foot Lathes

MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FREE

SEBASTIAN LATHE CO., 120 Culvert St., Cincinnati, O.

FRICITION DISK DRILL

FOR LIGHT WORK.


Has These Great Advantages: The speed can be instantly changed from 0 to 1600 without stopping or shifting belts. Power applied can be graduated to drive, with equal safety, the smallest or largest drills within its range—a wonderful economy in time and great saving in drill breakage.

W. F. & JNO. BARNES CO., Established 1872.

1999 Ruby Street, Rockford, Ill.

ELECTRICAL APPARATUS REPRE- sented by Conventional Diagrams in Drawings.—Fifty diagrams showing the usual method of illustrating electrical apparatus in drawings. A labor saving paper. Contained in SUPPLEMENT 1106. Price 10 cents. For sale by Munn & Co. and all newsdealers.

Andrew Carnegie, Thomas A. Edison and many other successful men began their careers at Telegraph Operating. Why don't you learn? For \$1.75 we will send you a complete N. D. outfit with book of instructions, by express (not pre-paid). Send for catalogue of electric apparatus, supplies and novelties.



J. H. BUNNELL & Co., Inc., 20 Park Place, New York



Asbestos and Magnesia Products

STEAM PIPE AND BOILER COVERINGS. ASBESTOS PACKING (For all purposes). ASBESTOS FIRE-RESISTING CEMENTS. ASBESTOS BUILDING MATERIALS.

H. W. JOHNS-MANVILLE CO.

New York, Milwaukee, Chicago, Boston, Philadelphia, St. Louis, Pittsburg, Cleveland, New Orleans, Kansas City, Minneapolis, San Francisco, Los Angeles, Seattle, London.

The Varnish that lasts longest

Made by Murphy Varnish Company.

DuBrie Marine Motors

4 REASONS why DuBrie engines are speedier, operate at lowest fuel cost, run easier, quieter, and last longer than any other. (1) Correct design, form and shape of pistons and size and location of ports, producing perfect scavenging. (2) Original generator valve, with float-feed and throttle—better than any carburetor. (3) Perfect Cooling System—direct-acting non-binding vertical plunger pump, and we take water from top of cylinder where hottest. (4) Elevated Gearless Commutator—positive, noiseless, safe. Other reasons, convincing and vital to you, in catalog, free on request.

DuBrie Motor Co., 421 Guoin St., Detroit, Mich.

2 1/2 h.p. \$60
4 h.p. \$75
6 h.p. \$95
Prices for Complete Engine.

Wizard Repeating LIQUID PISTOL

Will stop the most vicious dog (or man) without permanent injury. Perfectly safe to carry without danger of leakage. Fires and recharges by pulling the trigger. Loads from any liquid. No cartridges required. Over 6 shots in one loading. All dealers, or by mail, 50c. Rubber-covered holster, 5c. extra.

Parker, Stearns & Co., 226 South St., Dept. G, New York

FUEL GAS

SEND FOR—FROM NAPHTHA FOR—FREE CATALOG.

GANNERS, LAUNDRIES, SHOPS, LABORATORIES, ALL MANUFACTURING.

SPRINGFIELD FUEL GAS MACHINES.

GILBERT & BARKER MFG CO. 82-4th Av. N.Y. CITY

STEAM TURBINES. — THEIR CON- struction, Operation and Commercial Application. SCIENTIFIC AMERICAN SUPPLEMENTS 1306, 1307, 1308, 1422, 1400, 1447, 1370, 1372. The articles have all been prepared by experts in steam engineering. Price 10 cents each, by mail. Munn & Co., 361 Broadway, New York City, and all newsdealers.


Whipple The Motor-Cycle Man

(Pioneer Motor-Cyclist of Chicago) Can and will save you money on new or second-hand motor-cycle. General agent and distributor seven leading makes—also **Ferro Motor Boat Engines**—with satisfied patrons the world over. If you have the "motor-cycle fever" let me prescribe for you.

WHIPPLE "The Motor-Cycle Man" 262 West Jackson Boulevard, CHICAGO

Make Your Own Fertilizer

at Small Cost with WILSON'S PHOSPHATE MILLS From 1 to 40 H. P. Also Bone Cutters, hand and power, for the poultrymen; grit and shell mills, farm feed mills, family grist mills, scrap cake mills. Send for our catalog.



Wilson Bros., Sole Mfrs., Easton, Pa.

Wooden Tanks

Any Size or Shape

Steel Towers

Any Height

The Baltimore Cooperage Co.

MANUFACTURERS

BALTIMORE CITY, MD.

CATALOGUE GRATIS

The Major Reversible Marine Engine for 1907

1 1/2 H. P. \$33.15 (engine only) New features, better engine, stronger, more horse power. MAJOR engine can be used for stationary work. We built and sold 5,000 engines last year. We are building 10,000 engines this year. from 1 1/2 to 20 H. P. Write at once for catalog and special inducement to one agent in each locality.

DETROIT GAS ENGINE AND MACHINERY CO. 58 E. Congress Street, Detroit, Mich.

WELL DRILLING Machines

Over 70 sizes and styles, for drilling either deep or shallow wells in any kind of soil or rock. Mounted on wheels or on skids. With engines or horse powers. Strong, simple and durable. Any mechanic can operate them easily. Send for catalog.

WILLIAMS BROS., Ithaca, N. Y.

Asbestos and Magnesia Products

STEAM PIPE AND BOILER COVERINGS. ASBESTOS PACKING (For all purposes). ASBESTOS FIRE-RESISTING CEMENTS. ASBESTOS BUILDING MATERIALS.

H. W. JOHNS-MANVILLE CO.

New York, Milwaukee, Chicago, Boston, Philadelphia, St. Louis, Pittsburg, Cleveland, New Orleans, Kansas City, Minneapolis, San Francisco, Los Angeles, Seattle, London.

Bed bottom, G. Bezanger..... 852,255

Bed, folding, J. M. Wilder..... 851,910

Bed, spring, W. F. Ade..... 851,911

Bedclothes fastener, A. M. Hoffman..... 852,180

Bedstead, folding, F. Wood..... 851,724

Beehive, C. P. Harrison..... 851,882

Beer coolers, locking device for, M. D. Sadler..... 852,140

Belt, abdominal, Knight & Davis..... 851,889

Belt cutter, R. T. More..... 852,340

Belt, life, A. & E. Gareis..... 851,740

Belt thrower and guide, J. L. Coutts..... 851,652

Binder, loose leaf, W. M. Raynor..... 851,693

Binder, loose leaf, J. Strang..... 852,084

Binder, loose leaf, P. Revere..... 852,139

Block signal system, automatic, Patenall & Dryden..... 851,692

Boat, G. A. Farini..... 852,380

Boats, device for locating and raising sunken, Slattery & Sambur..... 851,698

Bobbin clamping device for spindles, C. A. Hawes..... 851,884

Bobbin holder, F. Pope..... 851,774

Body bolster, C. F. Huntton..... 851,753

Boiler cleaner, steam, F. G. Rogers..... 851,694

Boiler water purifying device, steam, W. P. Weimann..... 852,005

Bolster, A. Lipschutz..... 852,391

Bolt cutter, stay, E. T. Strong..... 852,302

Boot calk, C. Pfeiffer, reissue..... 12,644

Bottle holder, J. T. H. Paul..... 852,345

Bottle, non-refillable, M. P. Niendam..... 851,896

Bottle, non-refillable, G. V. Doherty..... 851,925

Bottle, non-refillable, A. B. Court..... 852,260

Bottle, non-refillable, H. O. McClurg..... 852,408

Bottle stopper, E. C. Leach..... 851,901

Bottle stopper, A. E. Redlich..... 852,242

Bottle, syrup, W. R. Warner..... 852,360

Bottle washing machine, C. H. Loew..... 852,127

Bottles, capping, H. L. Fulewider, et al..... 852,323

Box ending machine, automatic, P. L. Smith..... 852,083

Bracket, J. Hilbert..... 852,179

Brake, W. H. Lewis..... 851,892

Brick kiln, E. Weiss..... 852,404

Broom, R. Rosenbaum..... 852,244

Broom machine, C. Clemens..... 851,916

Brush holder, R. E. Barker..... 851,793

Bucket scraper, orange peel, L. A. Desy..... 851,733

Bucket scraping attachment, J. T. Boyd..... 851,824

Bureau, P. Ramming..... 852,214

Burglar alarm relay drop, D. D. Friedman..... 852,226

Burial case, J. F. Russell..... 852,080

Bushing, self-oiling, Perkins & Jenney..... 851,958

Button, hose supporter, E. Cleary..... 851,980

Cable chain connecting means, A. Frankenheim..... 852,264

Cable clamp, A. H. Meech..... 851,822

Cake machine, G. S. Ward..... 852,208

Cane loader, J. B. Gaussiran..... 852,267

Car brake, automatic, C. Fero, Jr..... 851,874

Car construction, W. G. Thummel..... 852,042

Car fender, J. P. Rohn..... 851,900

Car signal, F. D. Malloy..... 852,167

Car stake, F. Carman..... 852,167

Car vestibule, J. Krebbel..... 851,945

Car wheel fender, J. F. Sargent, Jr..... 851,965

Cars, pneumatic appliance for, G. H. Hollingsworth..... 852,117

Cars, steam-heating system for railway, E. E. Gold..... 852,019

Carburetor, A. Kunkel..... 851,759

Carding machine, M. A. Kehoe..... 852,330

Carpet beater, O. O'Halloran..... 852,195

Carpets and the like, apparatus for making, Clark & Poole..... 852,104

Carriers. See Target trap carrier..... 851,698

Cash register attachment, P. L. Shier..... 852,352

Casket lowering device, A. W. Brown, et al..... 851,861

Cellulose, manufacture of artificial thread from solutions of, R. Linkmeyer..... 852,126

Cement kiln, T. M. Morgan..... 851,765

Center swiveling hook, G. F. Murray..... 852,285

Chart for garment patterns, W. P. Abnelt..... 852,151

Check and like value or amount indicating document, form of, A. Collier..... 852,257

Check controlled apparatus, Beaumont & Garmon..... 851,641

Chimney flue protector, C. Leak..... 851,949

Chimney top, T. Kernchen..... 851,942

Chopper and cultivator, E. T. Odom..... 852,194

Chuck, tool, T. Dicks..... 852,320

Churn, R. Koch..... 852,067

Cigar cutter and pipe cleaner, combined, G. Nelson..... 851,769

Cigar machine, W. S. Luckett..... 851,681

Circuit connector, C. F. Patterson..... 852,395

Circuit protection, secondary, S. Ferguson..... 851,739

Circuits, means for nullifying inductive interference between parallel, E. Blakeney..... 851,856

Clamp, Hewlett & Van Brunt..... 851,661

Clamping device, E. Franke..... 851,875

Cleansing machine, W. H. Dunn..... 851,736

Closet bowl, W. H. Lloyd..... 851,679

Clutch, W. J. Hands..... 851,986

Clutch, A. Vivinus..... 852,045

Clutch for automobiles and other purposes, friction, M. F. McMahon..... 851,956

Clutch for countershafts, I. M. Foster..... 852,057

Clutch mechanism, T. L. Carbone..... 851,797

Coal piling apparatus, C. Piez..... 852,238

Cock box for water and gas pipes, street stop, Walcott & Fischer..... 852,359

Cock clamp, basin, T. L. Cecil..... 852,220

Cock lock, stop, C. H. Thompson..... 852,303

Coffee mill grinder, W. J. Bussinger..... 852,164

Coil, reactance, C. L. Fortescue..... 851,658

Coin collector circuit, J. G. Roberts..... 851,838

Coin mechanisms, fraud preventive device for, J. Fritsche..... 852,111

Cold storage box, Emmerich & Heidland..... 852,225

Collar stuffing machine, horse, L. J. Powers..... 852,137

Columns, means of connecting channel irons in the construction of, G. Aus..... 851,973

Concrete arch, reinforced, H. M. Russell, Jr..... 852,202

Concrete mixer, Muir & Herod..... 851,686

Control system, R. P. Jackson..... 851,694

Converter system, rotary, W. S. Rugg..... 851,695

Conveyor, E. H. Spear..... 851,701

GENTLEMEN
WHO DRESS FOR STYLE
NEATNESS, AND COMFORT
WEAR THE IMPROVED

BOSTON GARTER

THE RECOGNIZED STANDARD
The Name is stamped on every loop—

The *Velvet Grip*
CUSHION BUTTON CLASP

LIES FLAT TO THE LEG—NEVER SLIPS, TEARS NOR UNFASTENS

Sample pair, Silk 50c., Cotton 25c.
Mailed on receipt of price.

GEO. FROST CO., Makers
Boston, Mass., U. S. A.

ALWAYS EASY.

BUILD A BOAT

By the WEATHERWAX METHOD.

We are the only boat builders who sell boat patterns. Knock-down frames easily put together. The best is the cheapest. Send for our 100-page Catalog J of 1907 models.

BAY CITY BOAT MFG. CO., Bay City, Mich., U. S. A.

Convert Your Bicycle Into a Motorcycle

at small cost by attaching the self-starting **Eric 2 H. P. Power Outfit**. This includes all parts. Anyone can easily make a powerful motorcycle. Speed 20-30 miles an hour. 2-3 H. P. Motorcycles. Send stamp for either catalog. "The Motorcycle." It tells about the mechanism, care, operation, how to get more power, etc.

MOTORCYCLE EQUIPMENT CO., 5 Lake, Hammondport, N. Y.

"Success" Automobile, \$250

Practical, durable, economical and absolutely safe. A light, strong, steel-tired Auto. Suitable for city or country use. Speed from 4 to 20 miles an hour. Our 1907 Model has an extra powerful engine, patent ball-bearing wheels; price, \$275. Also 10 h. p. \$400. Write for descriptive literature.

"Success" Auto-Buggy Mfg. Co., St. Louis, Mo.

Everything for the AUTOMOBILE and AUTOMOBILIST

Our 1907 Catalogue No. 32B, 150 pages, 1000 illustrations, 5000 prices with descriptions, yours for the asking.

NEUSTADT AUTOMOBILE AND SUPPLY CO.
Largest Parts and Supply House in America
3932 Olive Street ST. LOUIS, MO.

A Motor-Cycle or Launch

At Small Cost by using one of Our Attachable Outfits. We have Finished Motors or Rough Castings from 1 1/2 to 10 horse power for Auto, Marine or Stationary. Send stamp for catalogue.

STEFFEY MFG. CO., 2941 W. Girard Ave., Phila., Pa.

ELECTRIC LAUNCH MOTOR. THE

design in this paper is for a motor of unusual simplicity of construction, which can easily be built by an amateur at small cost. It is intended for a boat of about 24 feet over all and 4 feet 6 inches beam, drawing 18 inches, and is capable of propelling such craft at a speed of 7 miles per hour. Illustrated with 21 cuts. See SCIENTIFIC AMERICAN SUPPLEMENT, No. 1202. Price 10 cents by mail, from this office, and from all newsdealers.

Keystone Well Drills

for Artesian and Ordinary Water Wells, Mineral Prospecting and Packer Drilling for Oil and Gas. Contractor's Blast Hole Drilling, River and Harbor Exploration, etc. Our five catalogs are text-books in these lines.

KEYSTONE WELL WORKS
Beaver Falls, Pa.

Marine Engines

For power boats, pleasure launches, and towing craft. Perfect in every mechanical detail. Designed and built by oldest marine engine builders in the West. Greater speed, more power, less vibration per H. P. than any marine engine built. Two speeds, 1 to 500 H. P. Single, double, 4, 8 and 12 cylinders. Don't place your order until you get our latest pamphlet and prices on engines and marine fittings.

2616 DeKalb St., St. Louis, U. S. A.

ST. LOUIS GAS & GASOLINE ENGINE COMPANY

Kerosene Oil Engines

Marine, Stationary, Portable

NO DANGER. Maximum Power. Lightest Weight. Simple, Reliable, Economical. No Batteries. Self Ignition by Compression. Fully guaranteed. Write for Catalogue S. A. P. No charge for packing.

INTERNATIONAL OIL ENGINE CO.
38 Murray St., New York, U. S. A.

Door check and closer, Bardsley & Rosen-treter	851,640
Door closer and check, combined, W. M. Armsbury	851,972
Door, grab, G. W. Kellogg	851,331
Door opener, electric, J. Koch	852,279
Door spring and stop, A. C. Wyman	852,091
Doubletree attachment, J. F. Butterfield	851,648
Draft apparatus, G. M. Sommer	851,903
Draft appliance, R. Leitz	851,814
Draft equalizer, A. Kurlde	851,676
Drag, G. E. Ketchum	851,943
Drapery supporting device, C. Levy	851,678
Drawer stop, Tuell & Borgerding	852,247
Drawers, apparel, H. P. Wheeler	852,364
Drawing instrument, H. Mettler	852,132
Dressing device, rotary, V. Spietschka	851,702
Drier. See Hair drier.	
Dry battery, C. D. Manville	852,188
Dry pan crusher, J. W. Boltz	852,160
Drill, D. B. Edwards	852,109
Drilling machine, E. Westberg	852,046
Dust deflector, Replogle & Thackray	852,035
Dye of the quinophthalone series and making same, yellow sulfon, A. Bertschmann	852,158
Elastic comb, M. Hess	852,273
Electric cables, drying, W. B. Hale	851,747
Electric circuit controller, hand-operated, R. P. Jackson	852,386
Electric circuit switch, automatic, C. H. Hill	851,808
Electric conductor supporting device, B. J. Jones	851,671
Electric elevator, H. F. Gurney	851,934
Electric furnace, H. N. Potter	851,961
Electric motor and other apparatus in which there is magnetic flux, R. D. Mershon	852,028
Electric motor controller, C. A. Dresser	851,804
Electric motor controlling apparatus, R. P. Jackson	851,662
Electrical systems from lightning and other static disturbances, protection of, R. D. Mershon	852,026
Electrically controlled elevator, W. D. Lutz	851,682
Electrically controlled elevator, C. & F. C. Naujoks	851,829
Electromagnet, R. P. Jackson	851,663
Electromagnetic separator, W. Blackmore	851,979
Electrotherapeutic instrument, J. W. Molire	852,133
Elevator control device, automatic, S. S. Teague	852,357
Elevator controller, electric, H. F. Gurney	851,933
Elevator safety means, M. T. Weston	852,048
Elevator safety stop, J. N. Mitchell	852,072
Engine, D. A. Seyler, Jr.	852,351
Engine cylinder, explosive, Bigsby & Barhoff	851,977
Engines, fair lead for donkey, H. Holmes	852,002
Excavating machine bucket, C. C. Jacobs	851,888
Excavator, W. R. Martin	852,131
Exercising apparatus, electric, A. B. McMillan	852,193
Expanding bit, A. E. Swanson	851,783
Explosive, F. Sparre	852,142
Explosive engine, C. Schultz	851,779
Extension table, M. J. Bowman	851,759
Fan attachment for sewing machines and the like, J. P. Coleman	851,651
Fan attachment motor, B. Fesenfaier, Jr.	852,055
Fan, rotary, J. W. Harding	851,660
Faucet, self-closing, W. M. Bashlin	852,155
Feed box for poultry, F. G. Allen	852,211
Feed strainer for locomotives, A. C. Bottger	851,914
Feeder, automatic boiler, J. H. Murray	852,286
Fence clip, wire, M. Howard	851,937
Fence machine, wire, I. N. Morford	851,955
Fence post and fastening device therefor, metallic, R. Mattice	852,235
Fence tie, wire, C. Hendershott	851,807
Fender. See Car fender.	
File, letter, J. J. Dettwyler-Bruderlin	851,870
File, paper, C. F. McBe	852,288
Fire box and grate, adjustable, E. A. Probst	852,294
Fire escape, F. J. Bryant	851,862
Fire extinguisher, C. E. Buell	851,893
Fire extinguisher, H. Mikorey	852,393
Firearm sight, G. H. Conrad	852,106
Firearm sight, G. E. Albee	852,152
Fireproof building construction, C. Collins	851,919
Fishing reel, W. E. Marhoff	852,070
Flax treating apparatus, F. H. Richards	852,399
Flexible wheel, E. Wigglesworth	852,006
Floor construction, J. Kahn	852,207
Floor waxing machine, C. B. Wattles	852,087
Flooring, J. McIntyre	851,768
Flue joint structure, A. Leggett	852,278
Flue support, W. L. Williamson	851,720
Fluid pressure controlling device, G. H. Gilman	851,878
Flux, C. Ellis	852,017
Flying machine, M. Nial	851,895
Flying machine, B. Connolly	852,221
Folding machine delivery mechanism, S. Wheeler	852,089
Foot power machines, device for promoting the impetus of, A. J. Pierce	852,034
Fruit gatherer, A. A. Smith	852,082
Fruit jar, G. F. Wellhouse	851,788
Furnace, J. F. Monnot	851,992
Furnace rail, M. Sklovsky	852,000
Fuse holder, J. C. Ralls	851,997
Fuse terminal, safety, J. Sachs	852,037
Game apparatus, W. J. Thomas	852,085
Game appliance, Charity & Critchley	851,864
Garment supporter, F. L. De Graff	851,923
Gas cut off, automatic, R. C. Stevens	852,355
Gas generator, acetylene, L. Pederson	851,772
Gas generator, acetylene, J. T. Kittredge	852,066
Gas igniter, electric, F. C. Nickel et al.	852,342
Gas producer, C. L. Huston	852,228
Gas producing and heat generating process, A. E. Johnson	851,756
Gas regulating apparatus, G. Marconnet	851,954
Gas regulator, D. P. Skellenger	851,968
Gate, A. Hendrich	852,336
Gear, changeable drive, H. Wichmann	852,310
Gearing, alternating, M. L. Moses	852,394
Girth, J. W. Gardner	852,050
Glass and show cases, fastening for plate, C. M. Conley	851,920
Glass articles, shaping, W. E. Bock	852,098
Glass delivering apparatus, molten, R. S. Pease	852,196
Glass, drawing, R. S. Pease	852,197
Glass, forming apertures in, G. A. Macbeth	852,129
Glass making apparatus, R. S. Pease	852,396
Glass, making wire, R. A. B. Walsh	851,787
Glass shaping machine, W. E. Bock	852,097
Glass shaping machines, mold for, W. E. Bock	852,099
Gluing machine, J. Alger	851,852
Go cart body, W. A. Marqua	851,820
Goods handler, E. E. Welch	852,300
Governing means for internal combustion engines, R. Hennig	852,272
Grab hook, A. W. Robinson	852,348
Grain binder, M. Molitor	851,825
Grain separators, distributor for, M. L. Barbeau	852,050
Gravel spreader and road leveler, D. M. Traube	851,712
Grinding and polishing machine, F. L. Wadsworth	852,403
Grinding apparatus, Grosvenor & Coolidge	852,021
Guide, J. R. Mitchell	852,073
Gun, semi-automatic, Benet & Mercie	852,253
Guns, cartridge deflector for top ejection, W. Bennett	851,643
Guns, cartridge deflector for top ejection, T. C. Johnson	851,669
Guns, telescope attachment for, T. C. Johnson	852,119
Hair drier, C. S. Mason	852,164
Hammer, drop, Lamb & Griggs	851,764
Hammer or the like handle, L. F. Tarbell	851,707
Harrow, J. C. Ferguson	851,657
Harrow riding attachment, G. Huismann	852,118
Harvester attachment, A. G. Bestgen	852,053
Harvester cutting apparatus, corn, W. H. Tilson	851,785
Hat dipping apparatus, A. W. Hilsinger	851,809
Hat fastener, H. V. Levison	852,125
Hat pin, M. Lowy	852,128
Hay and stock rack, D. L. Ryder	851,777
Hay carrier tracks, hinged extension for, J. A. Cross	851,869
Hay loader, E. A. Johnston	851,670

Instructive Volumes

Scientific American Reference Book


12mo. 516 Pages. Illustrated. 6 Colored Plates. Price \$1.50, postpaid



The result of the queries of three generations of readers and correspondents is crystallized in this book, which has been in course of preparation for months. It is indispensable to every family and business man. It deals with matters of interest to everybody. The book contains 60,000 facts and is much more complete and more exhaustive than anything of the kind which has ever been attempted. The "Scientific American Reference Book" has been compiled after gauging the known wants of thousands. It has been revised by eminent statisticians. Information has been drawn from over one ton of Government reports alone. It is a book of everyday reference—more useful than an encyclopedia, because you will find what you want in an instant in a more condensed form. Sixty years of experience alone have made it possible for the publishers of the SCIENTIFIC AMERICAN to present to the purchasers of this book a remarkable aggregation of information.

Home Mechanics for Amateurs

This book has achieved an unparalleled success in one week, and a Special Edition of 4,000 copies has been ordered. It is by far the largest and best book on the subject ever offered at such a low price. It tells how to make things the right way—the "only" way—at small expense. It will prove of value to you much more than you realize. Do things with your hands. Send for a circular giving contents—the circulars cost only a cent—the book \$1.50 postpaid. If the book could meet you face to face you would be the first to purchase. The first large edition is almost gone, order to-day.




370 Pages 326 Engravings Price \$1.50

TWENTY-THIRD EDITION Experimental Science

By GEORGE N. HOPKINS
Revised and Greatly Enlarged. 2 Octavo Volumes. 1,100 Pages. 900 Illustrations. Cloth Bound, Postpaid, \$5.00. Half Morocco, Postpaid, \$7.00.

EXPERIMENTAL SCIENCE is so well known to many of our readers that it is hardly necessary now to give a description of this work. Mr. Hopkins decided some months ago that it would be necessary to prepare a new edition of this work in order that the many wonderful discoveries of modern times might be fully described in its pages. Since the last edition was published, wonderful developments in wireless telegraphy, for example, have been made. It was necessary, therefore, that a good deal of new matter should be added to the work in order to make it thoroughly up-to-date, and with this object in view some 200 pages have been added. On account of the increased size of the work, it has been necessary to divide it into two volumes, handsomely bound in buckram.



A Complete Electrical Library

By Prof. T. O'CONOR SLOANE

An inexpensive library of the best books on Electricity. Put up in a neat folding box, as shown in cut. For the student, the amateur, the workshop, the electrical engineer, schools and colleges. Comprising five books, as follows:

- Arithmetic of Electricity 188 pages, \$1.00
- Electric Toy Making 140 pages, \$1.00
- How to Become a Successful Electrician 189 pages, \$1.00
- Standard Electrical Dictionary 682 pages, \$3.00
- Electricity Simplified 158 pages, \$1.00

A valuable and indispensable addition to every library. OUR GREAT SPECIAL OFFER.—We will send prepaid the above five volumes, handsomely bound in blue cloth with silver lettering, and inclosed in a neat folding box, as shown in the illustration, at the special Reduced Price of \$5.00 for the complete set. The regular price of the five volumes is \$7.00.

The New Agriculture

By T. BYARD COLLINS
12mo. 374 Pages, 160 Illustrations
Cloth, price, \$2.00

This new and valuable work sets forth the changes which have taken place in American agricultural methods which are transforming farm life, formerly so hard, into the most independent, peaceful, and agreeable existence. Farm life to-day offers more inducements than at any previous period in the world's history, and it is calling millions from the desk. The present work is one of the most practical treatises on the subject which has ever been issued.

The latest and best book on the subject. Contents: I. The New Call to the Farm.—II. The New Soil.—III. The New Fertilization.—IV. The New Transportation.—V. New Interests.—VI. New Conditions.—VII. New Varieties.—VIII. New Practice.—IX. New Machinery.—X. The New Inspiration.

Special circular of contents of these volumes sent free

MUNN & CO., 361 Broadway, New York

Hay loading machine, F. E. Fox	852,322
Hay raking and cocking machine, H. A. Grant	852,269
Head rest, B. K. Ackley	851,851
Headlight, M. E. Fuld	852,265
Heater. See Oil heater.	
Heating furnace, L. A. Fisk	852,056
Heating system, J. D. Jones	852,064
Heel, detachable, Greenstein & Lednitzky	852,178
Hoe and rake handle, O. Stewart	852,245
Horn, electric, H. Casanyi	851,655
Horseshoe calk, W. B. Cole	852,317
Horseshoe nail making machine, S. M. Cutter	852,376
Hose clamp, H. E. Crandall	851,653
Hose clamp, Palmer & Taylor	851,996
Hose pipes to pipe ends, fastening of, C. Nielsen	852,102
Hose supporter, C. J. Ljunggren	852,063
Hot air register attachment, A. O. Jones	852,063
Impact motor, rotary, J. T. Pritchard	852,293
Incandescent light attachment, W. V. D. Kelley	852,121
Index head, J. Parker	851,831
Insulator, H. Stotz	851,707
Invalid handling device, W. N. Mason	852,280
Ironing board, D. Block	852,373
Jar wrench, Macy & Wilbur	852,234
Joint plate, L. W. Kershaw	852,276
Journal box, J. Pearson	852,032
Journal box lid, Williams & Harrison	851,850
Key action, M. Miller	851,905
Knockdown box, T. West	852,248
Label pasteur, Byl & Koehler	852,210
Lacing terminal fastener, F. H. Steiniger	851,733
Lacings, machine for manufacturing shoe or similar, W. H. Church	852,102
Lactose from glucose, making, J. A. Just	851,673
Ladder, folding, N. Schaefer	851,696
Lamp burner, J. A. Mosher	851,827
Lamp support, incandescent, E. Beaudette	851,975
Last, W. E. Trufant	851,968
Latch, gate, B. S. Rector	852,240
Lawn trimmer, S. O. Sawyer	851,840
Lead oxid, making, C. A. Hall	852,325
Leather, coloring, W. M. Norris	851,905
Leather skiving machine, P. J. Lapham	852,277
Letter case, W. A. Tilley	852,304
Level and inclinometer, gravity plumb, C. B. Watts	851,717
Leveling device, H. Brown	852,013
Life lines, means for projecting and anchoring, Meyer & Rogers	851,824
Lifting apparatus, L. O. Beaudette	851,912
Lighting, vacuum tube, D. M. Moore	851,685
Line locking mechanism, A. Schneeloch	852,400
Liquid, means for delivering measured quantities of, R. Park	852,343
Liquid purifying apparatus, C. Schmidt	851,778
Load binder, A. L. Cox	851,866
Loading device, J. W. Pim	851,867
Lock, C. E. Scribner	851,900
Locking device for containing cases, E. B. Craft	851,868
Locomotive, gathering, J. M. Roan	851,837
Log turner, D. A. Kennedy	852,231
Logotypes, producing, P. T. Dodge	852,224
Loom shuttle, H. W. Brackett	851,647
Loom shuttle, C. Aillery	851,853
Loom with sliding front plate for the shuttle box, automatic shuttle changing, E. S. Stimpson	851,905
Lubricator, C. F. Schroyer	852,099
Lubricator, A. Byington	852,165
Mail box, I. W. Sample	852,298
Mail box attachment, H. M. Cole	851,730
Mail receiving box, A. Haentze	851,745
Manure spreader, F. M. Goodhue	851,928
Marker, C. Beckmann	852,214
Marker, land, A. E. Le Blanc	852,049
Massage implement, L. B. Buchanan	852,163
Match making machine, Weaver & Laux	851,848
Measuring attachment for bottle stoppers, A. Morrison	852,074
Measuring instrument, electrical, A. O. Bencke	851,976
Metal bodies, making compound, J. F. Monnot	851,684
Metal coating apparatus, J. F. Monnot	851,993
Metal converting apparatus, R. L. Lloyd	851,817
Metals, converting, R. L. Lloyd	851,816
Metallic structure, E. Molloy	851,991
Milk and cream pasteurizer and cooler, combined, J. L. Ahlers	851,971
Milking machine operating device, B. & F. Ljungstrom	851,951
Milling machine, W. P. Porteous	852,346
Mixer. See Concrete mixer.	
Mixing machine, Blake & Longshore	852,406
Molds, forming, J. F. Willey	851,849
Molding or briquetting, apparatus for preparing pulverulent materials for, G. J. Mashek	852,024
Molding or briquetting, preparing pulverulent materials for, G. J. Mashek	852,025
Molding or forming mechanism, P. Hunt	851,939
Mop wringer, W. W. Todd	852,043
Motion, mechanism for imparting and reversing, Mashek & Price	851,821
Motor, R. Philippe	852,082
Motor control system, W. L. Merrill	851,822
Motor starter, automatic, C. D. Knight	851,811
Motors, electrically braking alternating current, W. A. Layman	851,891
Motors, starting alternating current, W. A. Layman	851,890
Mower, J. H. Sherrard	851,901
Mower, lawn, R. A. Dickson	852,321
Music sheet feed device, perforated, H. K. Sandell	852,299
Musical compositions, reproducing, H. P. Ball	852,312
Musical instrument player, pneumatic, G. P. Brand	852,161
Musical instruments, mechanism for making master sheets of, H. N. Cross	852,261
Net, trawl, R. R. Obee	852,135
Nut lock, M. Rosenkranz	852,194
Nut lock, axle, A. J. Garrison	852,176
Oil burning apparatus, E. J. Foster	852,382
Oil burning system, Macerate & Toomey	851,953
Oil heater, A. K. Johns	851,755
Oilier, snap lever, J. H. Deare	852,319
Oiling device for feed grinders, L. B. McCargar	851,767
Ore mill, J. Johnson	851,757
Ores for metallurgical purposes, forming blocks of, A. Ronay, reissue	12 643
Oven, S. Torg	851,711
Package, fabric shipping, W. L. Penney	852,397
Packing, metallic, C. C. Hageman	851,747
Padlock, permutation, M. J. O'Leary	852,291
Pan lid, W. C. Vernon	851,969
Pan support, R. P. Cook	852,223

BUILD YOUR OWN BOAT


By the Brooks System of full size patterns and illustrated instructions.

Patterns of all Rowboats and Canoes, \$1.50 to \$2. Launches and Sailboats, 20 feet and under, \$4 to \$5. From 21 to 30 feet inclusive, \$5 to \$10.

We sell frames with patterns to finish for less than it costs others to manufacture.

\$15—price of 16-ft. launch frame (No. 5) complete with patterns and instructions to finish. \$20—price of 22-ft. speed launch frame (No. 15) complete with patterns and instructions to finish. 21,311 inexperienced people built boats last year. Why not you?

Free Illustrated Catalogue quotes prices on other patterns, knock-down frames with patterns to finish, and complete knock-down boats—launches—sailboats—rowboats and canoes. Satisfaction guaranteed or money refunded.



BROOKS BOAT MFG. CO. (BROOKS SYSTEM)
415 SHIP ST. SAGINAW, MICH. U.S.A.

Wachusett Shirts

There is a great difference between a Wachusett Coat Shirt and the average pull-over your head kind; as great as between a stem winding watch and the old fashioned key winder.

You purchase the best watch available, why not apply this rule in the selection of your shirts?

WACHUSETT COAT SHIRTS promote ease and dispatch in dressing. Save time, temper, torment. Stylish and durable—cheapest because best.

Ask for "Wachusett" make. Booklet free.
WACHUSETT SHIRT COMPANY
Dept. 2, Leominster, Mass.
Manufacturers of White, Fancy, Neat and Coat Shirts, Night Robes and Pajamas.

16 Ft. Steel Launch with 2HP Engine

18-21-25 foot launches at proportionate prices. All launches fitted with two cycle reversing engines with speed controlling lever, simplest engine made; starts without cranking, has only 3 moving parts. Steel rowboats, \$20.00. All boats fitted with water-tight compartments; cannot sink, need no boat house. We are the largest manufacturers of pleasure boats in the world. Orders filled day they are received. We sell direct to user, cutting out all middlemen's profits. Free catalog.

MICHIGAN STEEL BOAT CO.
1332 Jefferson Ave.
Detroit, Michigan

Important to Subscribers for Scientific American in Canada

Owing to recent changes in the Postal Laws, copies of SCIENTIFIC AMERICAN mailed to addresses in Canada will have to be prepaid by stamps affixed at the rate of one cent for each four ounces or fraction thereof.

Commencing May 1, 1907, the rates for subscriptions for our periodicals mailed to Canada, postage prepaid, will be as follows:

	PER YEAR
Scientific American	\$3.75
Supplement	5.50
American Homes and Gardens	3.50
Scientific American and Supplement (to one address)	8.25
Scientific American and American Homes and Gardens (to one address)	6.25

MUNN & COMPANY, Publishers
SCIENTIFIC AMERICAN OFFICE
361 BROADWAY, NEW YORK

Planter marker, corn, N. G. Christiansen	851,798
Planter, seed, J. S. Gardner	851,741
Planter, seed, J. B. Reed	852,398
Plastic material mold, H. B. Copeland	852,259
Pliers, construction of, E. Strassburger	851,906
Plow, S. B. Carter	851,729
Plow, W. D. Dozier	851,872
Plow, C. C. Addington	852,251
Plow attachment, W. B. Tunnell	852,086
Plow hopple or regulator, W. N. Thornton	852,710
Plow jointer, R. C. Smith	851,902
Pneumatic tube apparatus, carrier separator for, C. S. Jennings	851,754
Pocket, safety, E. Shaw	851,966
Poke, animal, A. Williman	852,250
Pole seat, safety, C. H. Coar	851,650
Polishing wheel, J. B. Fontaine	851,984
Post, See Fence post.	
Post and molding machine, J. G. Ash	852,049
Potash from feldspathic or other potash bearing rock, extracting, A. S. Cushman	851,922
Potential regulator, W. H. Thompson	851,709
Poultry fountain, C. F. Gill	852,177
Powered or mastic material, machine for packing, V. G. Apple	851,791
Power transmission device, W. T. Sears	851,842
Power transmission mechanism, fluid pressure, J. W. Hall	852,384
Press bar locking device, P. R. Wirt	852,369
Pressure equalizer, P. E. Whitney	852,150
Printing blocks and plates, manufacturing, L. Collardou	851,918
Printing press front or feed guide, G. P. Fenner	852,263
Printing presses, bed motion for cylinder, E. F. Leilich	852,124
Printing presses, perforating or scoring device for, C. E. Burch	852,315
Progressive brake and clutch, C. A. Arbey	852,311
Pulley, J. A. Kaplan	851,940
Pulley attachment, C. E. Curtiss	851,802
Pulverizer, G. J. Belstner	852,096
Pulverizing or grinding mill, J. W. Fuller, Jr.	852,173
Pump elevator, T. N. & J. A. London	851,763
Pump regulator, condenser, R. Wikander	851,719
Pump, rotary, R. P. Christensen	852,201
Pumping, deep oil well, R. J. Hoffman	852,061
Punch, S. Boisseau	852,215
Punch, pliers, etc., W. A. Bernard	851,794
Radiator box base, M. E. Danforth	852,318
Rail joint, L. Boudreaux	851,645
Rail joint, V. C. Young	852,210
Rail joint chair, G. W. Strother	852,206
Rail splice, G. W. Holford	852,181
Railway constructing machine, R. F. Downey	851,982
Railway gate, W. L. Smyth	852,354
Railway, pleasure, R. Hunt	852,184
Railway semaphore signal, H. M. Abernethy	852,093
Railway signal, A. W. Harvey	852,227
Railway signaling apparatus, E. R. Wolcott	852,405
Railway switch, O. A. Bird	851,913
Railway switch lock, F. McGuire	852,075
Railway tie, J. Campbell	852,166
Railway vehicles, means for signaling and stopping, W. M. Beck	852,156
Railways and the like, fog signaling apparatus for, Humphrey & Mawbey	851,989
Range finder, depression, A. Swasey	851,706
Razor strop, G. Tryon	851,715
Reel, W. A. Nichols	851,770
Refrigerator distributor, W. Wolf	851,722
Relay, E. F. Bliss	851,705
Reproducing device, E. Rollandet	852,036
Resistance terminal, H. D. James	851,667
Rifle, magazine, E. E. Redfield	852,241
Road working machine, D. M. Trabue	851,713
Rotary engine, J. F. Brice	851,860
Rotary engine, Wallot & Kruger	851,908
Rotary engine, J. A. Kray	851,944
Rotary engine, F. R. Bussard	852,218
Rotary engine, internal combustion, L. P. Prossen	851,962
Rotary explosive engine, R. E. Krause	851,675
Rotary motor, J. W. Staun	852,144
Rubber articles, making, F. A. Magowan	852,130
Runway or guide, L. J. Harris	852,115
Sack holder, H. F. Henke	851,749
Sad iron stand, E. Nickum	851,897
Saddle for harness, cart, G. J. Theobald	851,784
Safe, A. F. Gustafson	851,744
Safe, G. J. H. Goehler	851,880
Safety burner, automatic, N. Wise	852,370
Safety device, D. M. Watkins	851,909
Saw guide, miter box, E. A. Schade	851,841
Scaffolding, R. M. Sebree	852,141
Scale, J. H. Milburn	852,281
Score tablet for games, J. C. Patterson	852,031
Screen, See Window screen.	
Screw machine, W. H. Gates	851,742
Screws, automatic feeding mechanism for temper, R. C. Jones	852,120
Seal lock, A. Boal	851,644
Sealing and stamping machine, letter, J. N. Stacy	852,003
Sectional mold, T. C. Steimer	851,904
Self-adjusting wrench, G. A. Meyers, Jr.	852,071
Semaphore signal, electrically controlled, H. M. Abernethy	852,092
Service entrance box, E. E. A. Magowan	851,726
Sewing machine take up, J. Diehl	851,734
Shade support, window, Dixon & Howard	851,924
Shears, G. P. Taylor	851,708
Shears, O. Witt	851,721
Sheet metal vessel joint, L. Libbman	851,815
Shingle package, J. C. Alexander	851,789
Shipping case, C. O. Wright	852,010
Shock absorber, R. H. Smith	852,001
Shock compressor, E. M. Smithburg	852,205
Shoe turning machine, A. Eppler, Jr.	851,737
Side frame construction, O. S. Pulliam	852,079
Sieve for sinks and the like, W. B. Vander Minder	852,044
Sight, B. B. Westlake	852,047
Signal system, supervisory, C. F. Patterson	852,344
Silo, W. Clement	852,105
Sink strainer, N. Lyke	852,233
Siphon, H. B. Peacock	851,898
Siphoning device, J. T. McKinnon	851,688
Skirt and garment marking device, J. M. Beere	851,642
Skirt supporter and waist stay, C. D. Fletcher	851,805
Sleigh, spring, D. C. Markham	851,819
Smoking device, G. A. Pfortner	851,773
Soap switch, four-way, N. W. Crandall	851,654
Soap cutting and pressing machine, H. W. McEwen	852,190
Soap holder, E. F. Wach	852,305
Soldering flux, neutral, O. J. Lanigan	851,813
Spark indicator, jump, O. C. Hoffmann	851,751
Speed regulation, N. W. Storer	851,704
Spindle drive, W. J. Bayrer	851,728
Spinning and twisting machine, C. E. Lombard	851,952
Spinning or twisting apparatus, ring, G. W. Knight	851,812
Splice caller, M. B. Moloney	852,283
Splice or angle bar, E. C. Seward	852,038
Splints, apparatus for applying composition to, F. C. Dinny	852,379
Spraying device, E. F. Kaufman	851,758
Spring motor, L. J. Ring	851,836
Square, degree, L. Lalone	851,947
Square, T. E. R. E. Nilsson	852,077
Stair, metallic, S. Crossman	851,932
Stair stringers, table for punching, M. Grossman	851,931
Stairway, F. B. Dickason	851,871
Steering gear, H. M. Love	851,680
Stock loader, W. S. Bourne	852,314
Stocking, R. W. Scott	852,235
Stone pulley, A. Deschambault	851,732
Stone saw hanger, pendulum, F. A. Daley	851,731
Stove, E. P. Watson, Sr.	852,209
Stove, cooking, C. W. Curtis	851,801
Stove cover or mat, L. J. Herrick	852,116
Stove, electric, A. L. Marsh	852,338
Stove, heating, E. Elofson	852,054
Stove lids and plates, closure for lifter openings for, H. L. Sheldon	851,967
Strainer, milk, N. Entringer	851,983
Stripped instruments, device for securing charts to, U. G. Galbraith	852,407
Surgical instrument, J. E. Kennedy	851,941
Suspenders, H. C. Hine	851,885
Suspenders, J. T. McNeely	852,076

Amatite ROOFING

WATERPROOF AND REPAIRPROOF

As a practicable, durable, economical and labor-saving roof, Amatite tops them all.

Let us look into the subject more fully.

With any other roof there is the necessary preparation before you can begin the work.

With shingles—the slow, laborious work of nailing each shingle separately, matching and chalk-lining each row.

With Tin—matching, soldering, painting—then the everlasting keeping it painted, year after year, so it won't leak.

With ordinary ready roofings—paint! paint! paint!

With Amatite—you can nail it down yourself, over your new roof or your old shingled or tin roof, and there you are.

No worry, no fuss, no expense.

Could you possibly find any other roofing to so completely meet every requirement?

And your expense ceases after you have purchased enough Amatite for the job. There need be no saving to repair the barn roof next spring. You will not need it.

Amatite doesn't need to be repaired every year or so; it requires no painting or coating of any kind to make it last from one season to another. Amatite is waterproof, weatherproof and repairproof.

Free Samples

Write for a free sample and examine it. That will tell its own story.

Barrett Manufacturing Co.

New York Chicago Cleveland Allegheny Kansas City
St. Louis Boston Minneapolis Philadelphia
New Orleans Cincinnati London, Eng.

Jars and Vibrations

Every watch is daily subjected to severe jars and vibrations—in going up and down stairs, in riding, and in various other ways. Unless properly adjusted, such jars will seriously affect the time-keeping accuracy of any watch. When you buy a Howard Watch, you have a watch that is absolutely perfect in adjustment—that keeps accurate time under all conditions. The makers of the

HOWARD WATCH

have found by experience that the only possible way to achieve such delicate and accurate adjustments is to perfect them finally after the movement has been placed in its own case. Therefore, when you buy a "Howard," you buy a watch the adjustments of which have never been disturbed, for after the final test by the expert adjuster, it is enclosed in the velvet-lined mahogany cabinet in which you buy it, and is accompanied by Certificates of Guarantee completely identifying watch, case and movement, also stating the fixed price at which the watch must be sold—no matter where or from whom you buy it.


Howard Watches are made in men's sizes only. Prices range from \$35 to \$150, the difference being not in the grade of materials or workmanship, but in quality of case, number of jewels, and the adjustments.

"Watch Wisdom" FREE

We want you to have a FREE copy of "Watch Wisdom"—a mighty interesting book which tells more about time than you ever knew before. It's written by Elbert Hubbard. WRITE TO-DAY.

E. HOWARD WATCH COMPANY,
South St., Waltham, Mass., U. S. A.

THE AUTOMATIC COLD PROCESS GAS MACHINE



Runs with Air or Water.
Makes Gas Automatically.
Perfect City convenience for the Country Home.
Light, Heat and Fuel Combined.
Use Regular Gas Fixtures.
Absolutely No Danger, Smoke or Odor.
Cheaper than City Gas.
Machinery shipped ready to set up.
Send for Description and Price List.

AUTOMATIC GAS LIGHT COMPANY
44 E. Chicago Avenue, Chicago

WRITE FOR SAMPLES AND PRICES ON ROOFING

FROM 50 CENTS TO \$4.25 PER SQUARE.

Ready for immediate shipment. TAR, RUBBER, STEEL, flat, corrugated, ceiling and siding. Send for free catalogue on pipe, plumbing and building material. Address:

ST. LOUIS WRECKING & SUPPLY CO., 3865 MANCHESTER AVE., ST. LOUIS

Classified Advertisements

Advertising in this column is 50 cents a line. No less than four nor more than ten lines accepted. Count seven words to the line. All orders must be accompanied by a remittance. Further information sent on request.

BUSINESS OPPORTUNITIES.

"ASK OUR REPRESENTATIVES"—any one of the many—about the assistance and the co-operation that our system extends to them and why they are so successful in placing securities with the investing public. We desire a representative in every community. Request information at Old South Building, Seventh Floor, Boston, Mass., The Hammett Investment Corporation.

FOR A FINANCIER.—I WANT A MAN WITH \$50,000 to finance a newly patented absolutely burglar proof lock, the only one in existence; it is endorsed by the principal burglary insurance company of New York, and will be adopted by them when put on the market; positively a fortune in it. For further information and full particulars, address E. A. Whitney 200 East 116th St., N. Y. Phone, 5317—Harlem.

PATTERN LETTERS AND FIGURES (White Metal and Brass) for use on patterns for castings. Large variety, prompt shipments. Send for catalog. H. W. Knight & Son, Seneca Falls, N. Y.

INVENTORS WITH BRITISH RIGHTS FOR DISPOSAL, are requested to correspond with London party. For full information, address Bates, P. O. Box 206, Madison Square, New York.

METAL NOVELTY WORKS CO., Manufacturers of all kinds of light metal goods, Patented Articles and Hardware Specialties on contract. Metal Stamping Dies and Stamping our specialty. 43-47 Canal St., Chicago.

I MADE \$50,000 in five years in the mail order business. Began small. Any one can do it at home in spare time. Send for free booklet. Tells how to get started. For particulars address Manager, Box 570 A, Lockport, N. Y.

WE WILL MANUFACTURE FOR YOU, on reasonable basis, specialties in Electrical, Hardware or Metal lines. Large quantities or continuous contracts desired. Forest, Box 1736, New York.

PATENTS SOLD ON COMMISSION.—If you wish to buy or sell a patent, write for particulars to E. L. Perkins, 72 Broad Street, Boston. Patent Sales Exclusively.

WANTED.—Used filter press of 500-1000 pounds capacity, modern system. Must be in good working condition. Answer with full particulars P. L. 000, Box 773, New York.

I SELL PATENTS.—To buy or having one to sell, write Chas. A. Scott, Granite Building, Rochester, N. Y.

HELP WANTED.

DRAFTSMEN.—Detailers and Tracers—wanted at once for some of the technical employers we serve. Highest market wages. Excellent chances for advancement. Write us to-day. Hapgood, 305 Broadway, N. Y.

MEN AND BOYS TO LEARN PLUMBING, Brick-laying, Plastering and Electrical Trades. Positions secured. Free catalogue. Coyne Trade Schools, New York, San Francisco and Chicago. Mention SCI. AMER.

WANTED.—A first-class nickel plater. One who understands buffing and polishing, by manufacturing concern who do their own nickel plating. Must thoroughly understand the art. Steady employment guaranteed to right party. Address Nickel Plater Box 773, N. Y.

AGENTS.—Our Wonderful Cork-puller, not a screw, everybody needs, because no hard pulling is necessary; fits all bottles; send for circulars; plated samples, 25c. C. S. Hawley 154 Leonard Street, New York.

WANTED.—First-class Experienced Superintendent. Three malleable furnaces and two gray iron cupolas. Address Secretary, St. Louis Malleable Casting Co., St. Louis, Mo.

MEN AND BOYS, LEARN PRACTICAL ELECTRICITY, the best-paid trade. Our 7-story building has total electrical equipment of \$50,000. Day and evening courses; individual instruction. Positions guaranteed. Call or address N. Y. Electrical Trade Schools, 39 West 17th St., mentioning SCIENTIFIC AMERICAN.

GEO. H. WILSON, the World's Champion, has written a booklet, "Vaudeville, Stage Dancing and Entertaining." It is absolutely free and very interesting. Just address Wilson's Vaudeville School, 233 W. 42d St., N. Y.

MACHINISTS, ELECTRICIANS, PRINTERS, IRON-Workers, Plumbers, Engineers, Motormen, Chauffeurs order Kleenall for clean hands. Removes machine grease, grime, paint, printers' ink and dyes. Good garage side line. Continental Supply Co., 53 W. 24th St., N. Y.

TYPEWRITERS.

INVENTORS, AVOID MISTAKES.—Use a typewriting machine for your contracts and correspondence. Reliable typewriters from \$10.00 upwards. Ask for price list. Atlantic Typewriter Exchange, 246 Broadway, New York. Telephone 6235 Cortlandt.

MULTICOPYING.—The Bensinger "Rapid" Duplicator, quick, inexpensive, benefits business and professional men. Exact copies, forms, letters, diagrams, music, or anything in pen, pencil, typewriter. C. N. Bensinger Co., 34 Stone St., New York.

TYPEWRITERS.—Sold, rented, and repaired. Expert repairing on all makes. High grade machines at lowest prices. All makes rented. Henry Typewriter Exchange, 54 W. 125th Street, New York. Telephone 4652.

TYPEWRITER "Bargain List" free. Deal direct, save agents' commissions. Underwoods, Remingtons, Oliverts, \$28 others \$15, \$25, shipped on trial. Old Reliable, Consolidated Typewriter Ex., 243 Broadway, N. Y.

PHOTOGRAPHY.

PHOTOGRAPHERS, we want to get you in the habit of reading the American Photographer and Camera and Dark Room, the biggest and best photographic monthly. The yearly subscription price is \$15.00, 15 cents monthly at news dealers. We will send you four numbers as a trial subscription for 25 cents in stamps or coin. American Photographic Pub. Co., 361 Broadway, New York.

BARGAIN TIME IS HERE. Splendid opportunity in high grade lenses and cameras. If you want to buy, sell or exchange, write us for lists. National Specialty Co., 49 W. 28th St., New York City.

FILMS, FILMS, FILMS.—Lumiere Celebrated Films, made in Lyons, France, can now be purchased from all anti-trust dealers or from 11 West 27th Street, New York City.

PATENTS FOR SALE.

FOR SALE.—OUTRIGHT OR ON ROYALTY BASIS United States and Canadian Patent on Hand Power Propeller for small boats. Something new. Manufacturers only. No agents. For full information, address N. Johnson 233 N. Curtis Street, Chicago, Ill.

FOR SALE CHEAP.—PATENT 620156 CHAIN ADJUSTING device for bicycles. For full information and further particulars, address H. W. Lloyd, 360 King St., Charleston S. C.

A MONEY MAKING PATENT FOR SALE.—Would consider propositions to manufacture on royalty. See SCIENTIFIC AMERICAN, March 30, page 276, for cut and description of invention. For further particulars address Karlson & Grau, 134 Oak Street, Chicago, Ill.

SEPARABLE SQUARE.—A TOOL WANTED BY all mechanics. Will sell outright or lease on royalty demand will be enormous. For particulars, address L. V. Shepherd, 3034 Pasadena Ave., Los Angeles, Cal.

PATENTS can be sold outright or royalty agreements made to much greater advantage if protected by us. Permission given Contract Holders to use our Electro-type on stationery and otherwise patents protected by Patent Title and Guarantee Co., 25 Pine St., N. Y.

WATER FILTER.

THE DUPLEX FILTER is positively hygienic, because it is self-cleaning. Leased by 257 physicians, 6 hospitals, thousands of private families. Rent, 2 cents per day. Duplex Filter Co., 1140 Broadway, New York.

FACTORY AND MILL SUPPLIES.

STOP PAYING WATER RENT at your mill or factory. Erect a Caldwell Tank on a Caldwell Tower or your building. Plenty of pressure for every purpose. Fire protection besides. First cost only cost. Dozens of references right around you. John T. Stearns & Co., Silk Manufacturers, of Elmira, N. Y., say: "Don't see how a factory could do without it." Send for Illustrated Catalogue and Price List. W. E. Caldwell Co., Station D D, Louisville, Ky.

SITUATIONS WANTED.

SUPERINTENDENT.—YOUNG MAN FOR PAST two years manager of factory making a rubber and metal novelty and who is thoroughly familiar with mechanical rubber work, including horseshoe pads and tires is open for position. Take charge of established factory or equipping of new one. For further information and particulars address Thos. Fredwick, 53 North 14th Street, East Orange, N. J.

MOTION PICTURES.

MOTION PICTURE MACHINES. Films, Slides and Supplies from the largest store of its kind in this city. Sole agent Powers' Cameragraph the real fireproof machine. Catalogs. Lewis M. Swaab, 336 Spruce St., Phila.

THE MOVING PICTURE WORLD, weekly, 10 cents per copy, yearly subscription, \$2. The only paper devoted to the moving picture, illustrated song and lantern lecture field. Moving Picture World, Box 450, N. Y.

EXPERIMENTAL ELECTRICS.

STUDY ELECTRICITY AT HOME. Complete course, 30-pg. detail-book, 220-pg. text-book, 200 experiments, over 100 pieces of apparatus. Only \$5.40. Bulletin "A S" explains. Thomas M. St. John, 845 Ninth Ave., N. Y.

EYE-GLASS SPECIALTIES.

REMARKABLE MAGNETIC SPECTACLE AND EYE GLASS OFFER. Send stamp, no postals, for Free Pair, coupon and testimonials. S. A. Fredrick Optical Co., Toledo, Ohio.

MACHINERY FOR SALE.

FOR SALE.—24-INCH FREEMAN HAND-POWER Searfer, also 20-inch Belt Stripper. Both in good condition. Will sell cheap. For further particulars, address F. Renville Co., Grand Rapids, Mich.

SEASICKNESS.

SEASICKNESS and Car Nausea prevented. Brush's Remedy (Elixir prophylactic). Guaranteed perfectly Harmless. The only preparation that has never failed. Free booklet proving these statements sent by Brush Chemical Co., 299 Broadway, N. Y. All druggists \$1 per bottle.

NOVELTIES.

WANTED NOVELTY OR PATENTED ARTICLE suitable for agents and mail order business. Useful articles and novelties of merit only considered. Swift Disposal Co., General Delivery, East Orange, N. J.

SOUVENIR POST CARDS.

25 BEAUTIFUL POST CARDS mailed to any address for 12c. Agree variety of subjects. Sold by some stores at 2 for 5c and others at 10c each. Deduance Studio, 65 West Broadway, New York. Price list free.

Suspenders, etc., spring attachment for, P. E. Wirt	852,367
Switch, W. J. McKewen	852,192
Switch mechanism, T. Rundorf	851,839
Switch mechanism, electric, F. C. Newell	851,690
Switch structure, V. Angerer	851,691
Switch throwing device, G. J. Thomas	852,212
Syringe, B. F. Keller	852,401
Syringe, M. Bariffi	852,065
Syringe, vaginal, D. O. Fosgate	852,154
Table, See Extension table	852,110
Table lock, extension, J. L. Arnold	852,011
Tank heater, T. J. Ingold	851,887
Tanks, electric attachment for, H. E. Reeve	851,775
Target trap carrier, J. P. Leggett	852,123
Teeth, artificial, E. D. R. Garden	852,266
Telegraph receiving system, wireless, L. De Forest	852,381
Telephone exchange system, J. A. Aven	851,792
Telephone holder, T. J. Skelley	852,081
Telephone switch, T. S. Mount	851,994
Telephone switch hook, A. Larsson	851,761
Telephone switch system, automatic, Wicks & McKay	852,004
Telephone system, Lattig & Goodrum	851,948
Telephone trunking system, W. W. Dean	851,803
Telescope, A. J. Schoenborn	852,300
Tent and hammock support, J. M. Fyfe	851,927
Textile machine spindle, H. Cruse	851,921
Thill coupling, A. Bauer	851,883
The plate, L. H. Hart	852,051
Tie plate, A. Morrison	852,284
Tie machine, C. L. Baldwin	852,095
Tie machine, L. O. Burnham	852,101
Tie, roofing, A. Voigt	852,402
Tire for wheels, elastic, W. R. Smith	852,002
Tire repair and protective device, C. D. Gilman	852,113
Tire repairing apparatus, pneumatic, F. L. Harley	852,326
Tire valves and the like, manufacture of dust caps for, Schweinert & Kraft	851,781
Tire, vehicle, D. R. & O. D. Salisbury	851,899
Tires and other pneumatic articles, lining for pneumatic, F. Petnecky	852,198
Tires, manufacturing elastic fillings for, F. Pfeumer	851,960
Tongs, crucible, W. H. Hewitt	851,987
Tool, adjustable, R. T. Johnston	852,274
Tool heating furnace, W. S. Conant	851,865
Tool holder, S. S. Fuller	851,877
Tool holder, A. Munch	852,134
Tool, motor driven hand, Collins & Hearn	852,258
Tool post, adjustable, J. W. Swift	852,246
Toy, J. Soss	851,782
Toy, F. Wheeler	852,383
Toy, W. T. Keefer	852,388
Toy figure, A. R. Reihing	852,297
Toy or advertising novelty, A. Appel	852,153
Toy railway vehicles, means for stopping and releasing, E. Sollmann	851,843
Trace holder, T. B. Smith	852,353
Traction system, electric, A. Churchward	851,799
Traction wheel, power generating, M. C. Sharpneck	852,301
Train blocking system, automatic, C. E. Roehl	851,776
Train stop, automatic, F. B. Corey	851,800
Transformer controlling switch, M. O. Troy	851,786
Transformer, variable voltage, E. F. Gehrens	851,743
Transporting device, automatic, W. C. Carr	851,649
Trolley pole catcher, J. H. Walker	852,307
Trousers support, D. Greenberger	851,930
Truck, Brust & Du Bose	852,217
Truck for agricultural implements, steering, M. Goodfellow	852,020
Truck for annealing furnaces, charging, J. G. Blum	852,012
Truck, railway car, E. Kaylor	852,387
Truck, tobacco, W. Bechtold	852,052
Trunk and dresser, combined, W. Rinke	852,245
Turbine, W. N. Hoover	851,886
Turbine, elastic fluid, W. A. Nussbaumer	852,030

Turpentine and other products from wood, extracting, M. McKenzie	851,687
Turpentine and other substances from wood, apparatus for extracting, M. McKenzie	852,236
Twisting and spinning machines, construction of carrier bar mechanisms for, F. R. Jones	851,672
Type casting machine, automatic, L. B. Benton	851,855
Type, spaces, and quads, mold for casting, F. H. Brown, et al.	852,162
Typewriter feeding attachment, F. D. Bulard	852,100
Typewriter tabulator, B. Gereben	852,324
Typewriters, eraser for, E. C. McFadden	852,191
Typewriting and adding machine, combined, A. H. Ellis	852,014
Typewriting machine, C. W. Walker	851,847
Typewriting machine, C. W. Howell	851,988
Typewriting machine, L. P. Diss	852,014
Typewriting machine, R. Rein	852,200
Typewriting machine, E. E. Barney	852,313
Typewriting machine, A. T. Brown	852,374
Undergarment, C. M. Walker	852,306
Undergarment, combination, A. M. Brasington	851,796
Universal joint, A. Vanderbeek	851,845
Unwinding, measuring, and rewinding rolls of sheet material, machine for, R. W. Hull	851,938
Valve, W. R. Park	851,830
Valve, automatic shut off, G. A. Fullipp	852,174
Valve, by-pass, W. L. Wilson	852,008
Valve, check, R. W. Lewis	852,334
Valve for air brakes, safety, T. Behan	852,157
Valve for compressors and the like, W. Wolf	851,722
Valve for radiators, air, F. W. Leuthesser	852,333
Valve gear, H. Lentz	852,389
Valve jack, E. Stevens	852,145
Valve mechanism for internal combustion engines, C. Sintz	851,998
Valve, pressure reducing, J. Cloos	851,981
Valve, straightway, P. Fraser	851,876
Vehicle, V. G. Glibreath	852,112
Vehicle, motor, A. L. McMurtry	851,689
Vehicle top, O. Sutton	852,146
Vehicle wheel, L. D. Bergh	852,254
Vending machine, W. M. McCarty	852,289
Vending machine, W. L. Coley	851,917
Vending machine, R. Weittlich	852,088
Vending machine, H. B. Conover	852,222
Ventilating and moistening of workshops, apparatus for the combined, C. G. & A. G. Lambert	852,068
Voltage adjustment means, R. P. Jackson	851,665
Voltage regulator, R. P. Jackson	861,666
Wagon, dump, D. S. Watson	852,361
Wagon, dumping, W. T. Garrison	852,060
Wagon gear, W. A. Murray	852,287
Wall structure for sliding doors, semi-metallic, D. Schuyler	851,780
Washing machine, W. M. Kincaid	851,674
Watchmaker's tool, W. Arthur	851,854
Watchmaker's tool, G. V. Neal	852,290
Water heater, A. Goldfein	851,985
Water purifying apparatus, E. D. Packard	851,957
Water tower, F. A. Balin	852,213
Water tube marine boiler, E. Botticher	851,858
Wave motor, E. Kohler	852,232
Weighing scoop, F. C. Howe	852,182
Well plunger, tubular, E. R. Lockwood	852,185
Wheel, See Flexible wheel	851,974
Wheel brace, vehicle, C. H. Badger	852,175
Windmill, Keener & Munson	852,275
Windmill regulator, J. B. Vail	851,846
Window, casement, I. Wroblewski	851,725
Window screen, Tidd & Cook	852,147
Window supporting attachment, O. A. Eschholz, et al.	852,172
Wire connector, J. S. Tucker	852,148
Wire splicer, E. Bowman	852,216
Wood, extracting products from, F. Pope	852,078
Wrapping machine, J. J. Sullivan	851,907
Wrench, D. C. Groves	851,881
Wrench, J. R. Eddy	852,177
Wrench, F. Haight	852,270
Yarn and making same, party colored, W. M. Stevenson	852,356
Zinc retorts, filling, J. D. James	851,668
Zinc sulfate directly from the ore, producing, G. O. Angell	851,639

DESIGNS.

Badge, S. Y. Bell	38,541
Hammock, H. L. Hohlfield	38,542
Lace, levers, C. W. Birkin	38,543
Lace, levers, C. W. Birkin	38,544
Light reflector, artificial, O. A. Mygatt	38,545
Stove, B. B. Cohen	38,544

TRADE MARKS.

Almond meal, Peroxidant Manufacturing Co.	62,285
Automobiles and parts thereof, G. Dumond	62,281
Baking powder, Pure Food Baking Powder Co.	62,299
Beer, ale, brown stout, and malt extract, Fred Feil Brewing Co.	62,348
Belting, hose, and machinery packings, Revere Rubber Co.	62,362
Beverage and syrup for making the same, non-alcoholic carbonated, Moxie Nerve Food Company of New England	62,295
Brandy, apricot, Page & Sandeman	62,334
Brandy, apricot, Societe Anonyme de la Grande Distillerie E. Cusenier Fils Aine et Compagnie	62,336
Buckles, Alma Manufacturing Company of Baltimore	62,276
Candies, H. Heide	62,246
Candy and chewing gum, Manufacturing Co. of America	62,269
Candies, Will & Baumer Co.	62,256
Canned fruits and vegetables, C. Callahan Co.	62,264
Canned fruits and vegetables, F. M. Ketchum	62,332
Canned fruits and vegetables, jelly, and jam, Abraham & Straus	62,240
Canvas or duck cleaning and whitening preparation, Raven Gloss Mfg. Co.	62,335
Cards, playing, Kalamazoo Playing Card Co.	62,247
Chimneys and globes for lights, Postoria Glass Specialty Co.	62,346
Chocolate and chocolate candies, S. F. Whitman & Son	62,339
Cigars, Wertheimer Bros.	62,254
Cigars and cigarettes, G. H. G. Wing	62,258
Coats, capes, pants, etc., waterproof, E. A. Armstrong Mfg. Co.	62,379
Coats, vests, pants, and overcoats, Rosenzweig Bros. & Co.	62,367
Collars, cuffs, and shirts, Hargadine-McKittick Dry Goods Co.	62,351
Cordials, Imperial Distilling & Cordial Co.	62,353
Cordials, Societe Anonyme de la Grande Distillerie E. Cusenier Fils Aine et Compagnie	62,370
Corn and spavin cure and court plaster, F. Atwell	62,375
Cotton and linen duck articles, preparation for cleaning and bleaching white, I. Nachmann	62,248
Cotton piece goods, Rice, Stix Dry Goods Co.	62,382
Cotton piece goods and blankets, Indian Head Mills of Alabama	62,331
Cotton piece goods and blankets, Jackson Company	62,355
Cough drops, Fredericks & Tammen	62,328
Cravats, Bernstein, Kaufman & Co.	62,376
Cream and condensed milk, sterilized, Abraham & Straus	62,239
Cream, face, W. C. Schley	62,246
Cream or paste, shaving, Armour & Co.	62,304
Dress shields, Ono Manufacturing Co.	62,297
Duck pins, J. Dittmar & Sons	62,265
Embalming fluids and disinfectants, Egyptian Chemical Co.	62,305
Emery cloth and sandpaper, American Glue Co.	62,260
Enameled metal household utensils, H. M. Schnarr	62,287
Engine and dynamo electric machine, combined steam, A. L. Ide & Sons	62,321

SKIDOO!

MARINE ENGINE

The 2-Cycle-Engine-Sensation of the Year Entirely new and improved design introducing many exclusive features. Runs on Gasoline, Distillate, Kerosene or Alcohol.

2 H. P. Engine

COMPLETE ENGINE with Fresh Water Boat Fittings \$39.90; With Salt Water Boat Fittings, \$43.90.

Swiftest, most powerful, efficient and reliable engine of its size on earth. Drives Canoe, Rowboat or 14 to 20 ft. Launch with load, 6 to 10 miles per hour. Reversible, easy to install and operate. Unfailing endurance powers, economical and safe, cannot back-fire. Sold under Five Year Guarantee.

Catalog FREE

Belle Isle Motor Co., Dept. 18, Detroit, Mich.

The Dayton Sprayer and Whitewasher

Covers 10,000 sq. feet of surface per day with whitewash, cold water paints or disinfectants. Used by farmers, tobacco growers, horticulturists, for watering, destroying insect pests or plant diseases.

Easily operated, developing high pressure for extinguishing fires, washing vehicles, etc. will last a lifetime. Write for catalog of other kinds and prices.

The "Progress" 12 gal.—\$21.00
20 gal.—\$30.00
including hose, etc.

Dayton Supply Co., Dept. R, Dayton, Ohio.

The "Climax" On legs \$10.50
On Bbl. \$12.95
including hose, etc.

Cash Profits Pile Quickly Get Started Now

Let me tell you the name of this man and many others who are making from \$5 to \$10 a day, and more, making these Miracle Concrete Sewer Pipe on my Miracle Bell End Sewer Pipe Molds. Write me today. I'll answer you personally and make you a special proposition if you START NOW where you live. No experience necessary. It won't cost you a cent to investigate. My Free Book Explains.

Miracle Concrete Bell End Sewer Pipe

and how easily you, as an individual or contractor, can make money faster with my Miracle Molds than any other made. My Miracle Molds quickly pay for themselves. I make you the lowest price and best terms. The first 68 feet of pipe you make pays for your outfit. Sells at \$1.35 per foot or more. Don't miss this



THE National Runabouts, Touring Cars and Limousines

The NATIONAL is always popular because it gives perfect satisfaction in the HANDS OF THE OWNER. National Engines have Ball-Bearing Crank-Shafts and Cam-Shafts. Hence, their wonderful power.

Model F, 4 cyl., 40 H.P. Model H, 4 cyl., 50 H.P.
Model L, 6 cyl., 75 H.P.

NATIONAL MOTOR VEHICLE CO.
1019 E. 22d Street, Indianapolis, Ind.
Members American Motor Car Mfrs. Assn., N. Y.

EMBLEMS FOR EVERY FRATERNAL ORDER

I save you dealers' profits. I send an assortment of Emblems on approval to any Fraternal man in good standing in the United States, from which to make a selection. Write for an assortment, naming emblem desired and approximate price you wish to pay.

W. L. DODDS, 911 Ellicott Square, Buffalo, N. Y.

Every reader of the SCIENTIFIC AMERICAN should also be a reader of

Technical Literature

A Monthly Review of Current Technical Publications

a large 64-page illustrated journal giving its readers, in more or less condensed form, the BEST literary material of general interest appearing in the current technical publications of America and Europe, as well as much valuable information found in daily papers, trade pamphlets, society proceedings, speeches and lectures, etc. The

"Index to Articles in Current Technical Periodicals" gives a classified descriptive listing of all the articles of importance appearing in the current technical press, brought down to the first of the month of issue.


"An indispensable publication for engineers and other technical men, and one of the most instructive ever published for general readers who wish to keep in touch with modern industrial progress."

SUBSCRIPTION RATES
\$2.00 a Year. Single Copies, - - 20 Cents

Special Offers to Readers of the Scientific American.—As a trial subscription we will send you TECHNICAL LITERATURE for two months for 25 CENTS with a low rate in combination with a special Premium Book Offer for the continuance of the subscription.

Send your quarter to-day and get the current numbers.


TECHNICAL LITERATURE, 19 S, 220 Broadway, New York



COMING AND GOING

ALWAYS USE

"The Only Way"



60 YEARS' EXPERIENCE

PATENTS

TRADE MARKS
DESIGNS
COPYRIGHTS & C.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. HANDBOOK on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the

Scientific American.
A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.

MUNN & Co., 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.

Engines, steam, A. L. Ide & Sons..	62,322	62,323
Face enamel, liquid, R. E. Martin	62,315	
Fence wire, Interlocking Fence Co.....	62,312	
Fence, wire, Keystone Fence Company.....	62,313	
Food, stock, Farmers Friend Stock Food Co.....	62,380	
Foods, certain sea, Reiss & Brady.....	62,252	
Fuses, Coast Manufacturing & Supply Co.....	62,242 to 62,244	
Game, certain, J. W. Spear & Sohne.....	62,274	
Gin, Wm. Bergenthal Co.....	62,374	
Gloves, knitted, netted, and lace, Rice, Stix Dry Goods Co.	62,363	
Handkerchiefs, International M'fg. Co.....	62,354	
Hats and caps, straw, Townsend Grace Co. of Baltimore City	62,373	
Hats, men's and boys' fur, Gauss-Langen-berg Hat Co.....	62,306	
Hematogenic or blood forming iron com-pounds, A. Gude & Co.....	62,309	
Hosiery, O. Osborne	62,359	
Hosiery, J. Silver & Co.....	62,369	
Hosiery and knitted underwear, Brown Dur-rell Co.....	62,341	
Illuminating glassware, Welsbach Co.....	62,338	
Ink reducers and driers, printing, J. P. Conner	62,343	
Isinglass, Cape Ann Isinglass Co.....	62,241	
Jewelry, H. N. Pervier Co.....	62,298	
Kerosene, Polanco, Torres & Co.....	62,251	
Knitted underwear, H. Frank & Sons.....	62,347	
Lamp chimneys, W. R. Noe	62,358	
Lead, white, R. Shoemaker & Co.....	62,271	
Leather, patent side, Seton Leather Co.....	62,368	
Liquor, apricot, J. & A. Freiberg.....	62,329	
Machinery, certain, Newton Machine Tool Works	62,316	
Mast arms for the support of lamps, George Cutter Co.....	62,292	
Medicated stock foods, Dr. Hess & Clark	62,311	
Medicine, certain, Society of Chemical Indus-try in Basle	60,300	
Medicine, proprietary, E. L. Bauer	62,277	
Medicines, certain, E. S. Wells	62,289	
Medicines, certain, F. A. Steck	62,383	
Metal manufactures, certain, S. Sternau & Co.....	62,318	
Newspaper, W. Bullock	62,320	
Oil, castor, J. N. Stearns	62,288	
Oils, cotton seed, Southern Cotton Oil Co.....	62,273	
Optical apparatus appliances, etc., F.irm of C. Zeiss	62,340	
Paints, ready mixed, R. Shoemaker & Co.....	62,272	
Paper, writing, bond, and ledger, Union Card & Paper Co.....	62,253	
Papers, surface coated engraving, Dill & Collins Co.....	62,344	
Periodical, National Baker Publishing Co.....	62,326	
Periodicals, Jewelers' Circular Publishing Co.....	62,324	
Pie fillings, preserves, and jellies, M. Ams, Pills and headache tablets, J. L. Ward	62,262	
Medicine Co.....	62,301	
Pipe threading and cutting machines, Curtis & Curtis Co.....	62,279	
Publication, monthly, R. M. Van Arsdale.....	62,337	
Punch, arraks, C. A. Lindgren & Cis., Vin-handels Aktiebolag	62,377	
Railway equipment, certain, Fried, Krupp Aktiengesellschaft	62,283	
Refrigerators and ice boxes, Illinois Re-frigerator Co.....	62,352	
Remedy for diseases of the blood, J. M. Myers	62,296	
Remedy for malaria and grippe, A. Fischer.....	62,282	
Remedy, rheumatic, A. Giesecke	62,293	
Rubber roofing, H. A. Whiteman & Co.....	62,255	
Sausages, hams, lard, etc., Jones Dairy Farm	62,268	
Sewing machine needles, White Sewing Ma-chine Co.....	62,302	
Sewing machines, L. C. King & Co.....	62,294	
Shirts, Bronne-Mayer Co.....	62,342	
Silver plated jewelry, toilet, hollow, and flat ware, E. & J. Bass	62,319	
Soap, N. K. Fairbank Co.....	62,357	
Soap, liquid, A. V. Hassman	62,350	
Soap, perfumed, A. & F. Pears, Lind.....	62,259	
Soaps, W. Berry	62,263	
Starch or size, certain, Greene & Company.....	62,245	
Storage and conveying apparatus, Dodge Coal Storage Co.....	62,280	
Stoves, gasolene or vapor stoves, and vapor burners and ovens, gas, American Stove Co.....	62,261	
Sugars, refined, Henry Tate & Sons	62,267	
Suppositories, salves, and teas, G. Kerschen-meyer	62,284	
Syrup, Welch Bros. Maple Co.....	62,275	
Syrup, corn, O. W. Peirce Co.....	62,249	
Talking machines, Geo. Borgfeldt & Co.....	62,349	
Tea and coffee, C. E. Moody & Co.....	62,270	
Thread, certain, Oneida Community Lim-ited	62,250	
Tires, rubber, Goodyear Tire and Rubber Co.....	62,266	
Tools, certain hand, Collins Co.....	62,290	
Tools, certain hand, Societe Anonyme Des Anciens Etablissements Panhard & Levasor	62,317	
Washing compounds, Laundry Blue Co.....	62,333	
Watchsprings, Hammel, Riglander & Co.....	62,310	
Watches, watchcases, and watch movements, Langendorf Watch Co.....	62,314	
Water, mineral, Wild Pigeon Mineral Springs Co.....	62,303	
Water, mineral, J. A. Morgart	62,356	
Water, table, Great Bear Spring Co.....	62,308	
Whisky, Frankfort Distillery	62,327	
Whisky, A. Fischer	62,345	
Whisky, Goodhart-Hartman Co.....	62,350	
Whisky, Records & Goldsborough.....	62,361	
Whisky, J. P. Straub	62,372	
Whisky, A. Fischer	62,381	
Whisky, Maryland rye, Clotti, Vincenti & Co.....	62,378	
Wines, Carmel Wine Co.....	62,278	
Wines, port and sherry, Geo. G. Sandeman Sons & Co.....	62,307	

LABELS.

"California's Club Water," for mineral water, T. P. Converse	13,507
"Cottage Bread," for bread, Leonard Bak-ing Co.....	13,516
"El Barlo," for cigars, L. W. Keyer.....	13,505
"Hee-Haw," for chewing tobacco, Victor Tobacco Co.....	13,503
"K. B. C. Bohemian," for beer, Kittanning Brewing Co.....	13,509
"Night Cap Whisky," for whisky, J. Reusch	13,508
"Old Colony," for cigars, L. W. Keyer.....	13,504
"Old Pfister's Life Elixir," for a medicine, Hansen & Angard	13,515
"Pet's Nutro Bread," for bread, A. Peter	13,517
"Pur-It-Is Toilet Water," for toilet water, Pur-It-Is Mfg. Co.....	13,510
"Romanza Heliotope," for soap, Armour & Co.....	13,513
"Romanza Lilac," for soap, Armour & Co.....	13,511
"Romanza Rose," for soap, Armour & Co.....	13,514
"Romanza Violet," for soap, Armour & Co.....	13,512
"Schiller," for cigars, L. Mueller	13,506
"The Sign of the Kettle," for candles, E. B. Jones	13,519
"Unkle Sam's Cones," for ice cream cones, S. Kart	13,520
"Vezino's Digestive Health Food Choco-lates," for health food chocolates, V. de Vezino	13,518

PRINTS.

"Men's and Boys' Apparel," for men's and boys' apparel, H. C. Lytton	1,974
--	-------

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

WINCHESTER



.32 Special Caliber Rifles for Smokeless or Black Powder

Sportsmen who want to confine themselves to one gun and still be able to use either high or medium power ammunition as occasion demands, will find the Winchester Model 1894 .32 Special just the rifle they have been looking for. It shoots a smokeless powder cartridge more powerful than the .30 Winchester or a black powder cartridge of the .32-40 class equally well. These rifles are made in styles and weights to meet all tastes.

Winchester Guns and Winchester Ammunition are Made for Each Other

WINCHESTER REPEATING ARMS CO., NEW HAVEN, CONN.

As A Present

Why not one of these
NEW YORK STANDARD

"Chronographs?"



They combine a 1-5 second hand with an accurate movement and will ever be a reminder of the donor.

**All Jewelers Sell Them
They Are Fully Guaranteed**

New York Standard Watch Co., 401 Communipaw Ave., Jersey City, N. J.

Astronomy Without a Telescope!


Barritt-Serviss Star and Planet Finder



Every Stellar body accurately placed for any date for the next twenty years, in the Northern Hemisphere. Endorsed by leading scientists. Requires no technical knowledge to use it. Complete mastery of the heavenly bodies in a few hours.

Most graphic way of interesting all in the wonderful planetary system of the Universe. Chart is 15 in. square, with revolving disk map showing all stars. Made of heavy card-board. Sent anywhere in U.S. carriage paid, securely packed, \$5

LEON BARRITT, 150 Nassau Street, New York, U. S. A.



Mullins Steel Boats

Motor Boats, Row Boats, Hunting and Fishing Boats
built of steel with air chambers in each end like a life boat. They can't sink. Faster, more buoyant, practically indestructible, don't leak, dry out and are absolutely safe. No calking, no bailing, no trouble. Every boat is guaranteed. Highly endorsed by sportsmen. The Ideal boat for pleasure, summer resorts, parks, etc.

THE W. H. MULLINS CO.,
118 Franklin Street,
Salem, Ohio.

Write for Catalogue

NOTICE TO CONTRACTORS.

SEALED PROPOSALS, suitably endorsed on envelope, for Rearrangement of Heating System, North and South Wings at Hudson River State Hospital, Poughkeepsie, N. Y. will be received up to 3 o'clock P. M. on Wednesday, the 5th day of May, 1907, by the State Commission in Lunacy at the Capitol, Albany, N. Y., when bids will be opened and read publicly. Drawings and specifications may be consulted and blank forms of proposals obtained at the Hudson River State Hospital, Poughkeepsie, N. Y., or by application to G. L. Heins, State Architect, Capitol, Albany, N. Y. Contracts will be awarded to the lowest responsible and reliable bidder unless the bids exceed the amount of funds available therefor, in which case the right to reject all bids is reserved.

T. E. MCGARR,
Sec'y, State Commission in Lunacy.

Dated Albany, N. Y., April 22, 1907.

LET US BE YOUR FACTORY

WRITE FOR ESTIMATE ON ANY ARTICLE YOU WANT MANUFACTURED
STAMPINGS, MODELS, EXPER. WORK
WRITE FOR FREE BOOKLET
THE GLOBE MACHINE & STAMPING CO.,
970 Hamilton St., Cleveland, O.

ICE MACHINES

Corliss Engines, Brewers and Bottlers' Machinery. THE VILIER MFG. CO., 899 Clinton St., Milwaukee, Wis.

MODELS & EXPERIMENTAL WORK.

Inventions developed. Special Machinery.
E. V. BAILLARD, 24 Frankfort Street, New York.

RUBBER

Expert Manufacturers
Fine Jobbing Work
PARKER, STEARNS & CO., 228-229 South Street, New York

MODELS & EXPERIMENTAL MACHINERY.

Gears, Dies, Tools, Novelty manufac-tured. Fine, Accurate Work a Specialty. M. P. Schell, 1759 Union Street, San Francisco.

WANTED.—A SUPERINTENDENT.

Syracuse Chilled Plow Co.,
Syracuse, N. Y.



Are your bearings running hot? Reduce friction "mentally" and mechanically by sending to us for full particulars about Frictionless. We have the remedy. No bearing can run hot with it.

Frictionless Metal Co., Chestnut St., Chattanooga, Tenn.

MODELS & INVENTIONS PERFECTED

UNION MODEL WORKS
193 So. CLARK ST. CHICAGO.

CEMENT BOOKS.

How to Use Portland Cement
30c., Cement Sidewalk Con-struction, 50c., Reinforced Concrete Construction, \$2.50, Hol-low Concrete Block Building Construction, 50c. Sent postpaid.

CEMENT AND ENGINEERING NEWS, Chicago, Ill.


How to Construct An Independent Interrupter

In SCIENTIFIC AMERICAN SUPPLEMENT, 1615, A. Frederick Collins describes fully and clearly with the help of good drawings how an independent multiple interrupter may be constructed for a large induction coil.

This article should be read in connection with Mr. Collins' article in SCIENTIFIC AMERICAN SUPPLEMENT, 1605, "How to Construct a 100-Mile Wireless Telegraph Outfit."

Each Supplement costs 10 cents; 20 cents for the two. Order from your newsdealer or from

MUNN & CO., 361 Broadway, New York




Rubber Pump Valves

For Cold and Hot Water, Oils, Acids, High Pressure Mine Service and for every pumping requirement. * * *

Mechanical Rubber Goods of every description of unsurpassed qualities, including BELTING, HOSE PACKINGS, Gaskets, Mats and Matting, Tubings, Springs, Interlocking Tilting, Emery Wheels and MOULDED and CUT SPECIALTIES for any mechanical and commercial device. * * *

NEW YORK BELTING & PACKING COMPANY, Ltd.
91 & 93 Chambers Street, New York



CHARTER

Stationaries, Portables, Hoisters, Pumps, Sawing and Boat Outfits, Combined with Dynamos.


Gasoline, Gas, Kerosene.
Send for Catalogue.

State Power Needs.

CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.

Scales

All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Saws, Sewing Machines, Bicycles, Tools, etc. save Money. Lists Free CHICAGO SCALE CO., Chicago, Ill.



LEARN TO BE A WATCHMAKER

Bradley Polytechnic Institute
Horological Department
Peoria, Illinois
Formerly Parsons Horological Inst.
Largest and Best Watch School in America

We teach Watch Work, Jewelry, Engraving, Clock Work, Optics. Tuition reasonable. Board and rooms near school at moderate rates. Send for Catalog of Information.


FORMOZONE "ODORLESS" GARBAGE CAN

Made of heavy galvanized iron, air and water tight, two steel shields steel bound top and bottom, tight fitting cover, rivetted and soldered throughout. Odorless. Practical. Sanitary. Costs very little more than the ordinary garbage can. Used in connection with Formozone, averts nauseating odors, dispels the germ-carrying fly.

The Only Antiseptic Garbage Can Made.

We also manufacture the Formozone "Odorless" Garbage Pail.


Send for full details and Price List.



Patent Pending

FORMOZONE HYGIENIC MFG. CO.
East Madison St., CHICAGO

I. H. C.



Gasoline Engines

are the outcome of a thorough study and application of the principles which underlie this class of powers. They are built to make certain response with abundant power to every call upon them, and at least operating expense.

USE GAS, GASOLINE or ALCOHOL.

I. H. C. engines are built Vertical in 2 and 3-H. P., and Horizontal (Stationary and Portable) in 4, 6, 8, 10, 12, 15, and 20-H. P.

A demonstration and catalog with particulars can be had by calling on I. H. C. local agents. Or address the home office.

The International Harvester Company of America
(INCORPORATED)
7 C Monroe Street, Chicago, Ill., U. S. A.



LUFKIN TAPES AND RULES


ARE THE BEST.

For sale everywhere. Send for Catalog No. 18.

LUFKIN RULE CO.

Saginaw, Mich., U. S. A.

New York and London.



Franco-Auto Portable TURNTABLE

No. 2 Ball Bearing Caster, made in one piece, light and durable. Cars can be run off or on at either end. Protects Tires when car not in use. One man can handle the largest car with ease. Indispensable for handling cars in garage, factory or private barns. Requires no jack to place in position. Write for full description and price list.

FRANCO-AMERICAN AUTO & SUPPLY COMPANY
1402 Michigan Avenue, CHICAGO

The KITCHEN and PANTRIES

are the busiest places of the home. Within their walls more work is done—upon their floors more steps are taken than in all the other rooms combined. Where food is prepared there is necessarily a large quantity of waste produced.

If cleanliness is necessary in other parts of the residence, it is vital in the kitchen and pantries. Cleanly conditions cannot be maintained with wood floors or coverings of semi-permanent character. The peculiar advantages of

PENNSYLVANIA INTERLOCKING RUBBER TILING

for spaces especially requiring sanitary floors have brought about its use in many of the handsomest homes of America.

This incomparable flooring material is absolutely waterproof and sanitary. No other surface is nearly so restful to stand and walk upon. It makes a floor that is more durable than marble. It is not possible to slip upon it, and it is silent to the tread. It is adaptable to a greater variety of designs and is far more elegant than any other material.

Send us the dimensions of your kitchen, pantries, bathroom, vestibule, or any other area you may wish to be laid with Pennsylvania Rubber Tiling, and receive figures of cost with full information.

Our Book-of-Designs-in-Color will be mailed on request.

PENNSYLVANIA RUBBER CO.
JEANNETTE, PA.

NEW YORK—1741 Broadway.
CHICAGO—1211 Michigan Avenue.
PHILADELPHIA—615 N. Broad Street.
ATLANTA, GA.—102 N. Prior Street.
BOSTON—20 Park Square.
BUFFALO—717 Main Street.
DETROIT—237 Jefferson Avenue.
CLEVELAND—2124-5 East Ninth St.
SAN FRANCISCO—512-14 Mission St.
LONDON—26 City Road.

OPAQUE PROJECTOR

for showing Photos, Postal Cards, Book Illustrations and opaque objects on the screen in natural colors. Wireless Telegraph Outfits for the classroom and experimental work. New Direct Vision Spectroscopes for titling negatives. Send for Lists.

WILLIAMS, BROWN & EARLE, 918 Chestnut Street, Dept. 6, Philadelphia, Pa.

BUILD WITH PRACTICAL KNOWLEDGE



If you are a House-Owner or planning to build, this set of books will save you many times its cost. For the young man no better chance to learn a paying trade or profession could be offered. If you are a Carpenter, Contractor, Builder, Architect, Draftsman or Mechanic it offers you an exceptional chance to advance in your present occupation. The true test of your present efficiency is the amount of money earned by you from week to week. Unless you are advancing and earning more and more money as you grow older, there must come a time when younger and more ambitious men will crowd you out. Learn now to turn your spare time into money.

Cyclopedia of Architecture, Carpentry and Building

Compiled from representative instruction papers of American School of Correspondence. This offer is made to advertise the School. WE EMPLOY NO AGENTS as we believe this great work will easily demonstrate the superiority of our method of instruction. If you mention this Magazine, a 200-page handbook describing the School's 60 regular courses will be sent FREE.

SPECIAL ADVANCE SALE

LESS THAN 1-3 REGULAR PRICE

TEN MASSIVE VOLUMES, each nearly one foot high. Bound in red half morocco. Over 4 000 pages; 3 000 illustrations, full page plates, plans, sections, etc. Printed on highest grade paper; entirely new type—DE LUXE books in every particular.

Special \$19.80 Price

Regular Price \$60


Sent by prepaid express. Send \$2 within five days, and \$2 a month if satisfactory; otherwise notify us to send for them. In any case you lose nothing.

Absolutely no orders accepted at this price if postmarked later than June 30th, 1907.

Among the Chapters: Reinforced Concrete Construction—Carpentry—The Steel Square—Fireproofing—Star Building—Superintendence—Estimating—Contracts—Specifications—Strength of Materials—Architectural Drawing—Masonry—Electric Wiring—Plumbing—Steam Fitting—Heating—Ventilating—Cornice Work—Skylight Work—Roofing—Steel Construction.

AMERICAN SCHOOL of CORRESPONDENCE, CHICAGO

COLD GALVANIZING. AMERICAN PROCESS. NO ROYALTIES. SAMPLES AND INFORMATION ON APPLICATION.



NICKEL

AND

Electro-Plating

Apparatus and Material.

THE

Hanson & Van Winkle

Co.,


Newark, N. J.

28 & 30 S. Canal St.

Chicago.

THE LAMBERT

"Friction-Drive."



The Famous "Friction-Drive" Car

Models and styles to suit the purchaser
PLEASURE CARS, RUNABOUTS and TOURING CARS

Commercial Trucks for all purposes.

The LAMBERT patented FRICTION-DRIVE TRANSMISSION has proven by years of tests to be the SAFEST, SUREST, MOST EASILY CONTROLLED and entirely satisfactory transmission made.

LAMBERT CARS ARE IN A SUPERIOR CLASS BY THEMSELVES. INVESTIGATE.

WRITE FOR OUR ART CATALOGUE "S."

THE BUCKEYE MANUFACTURING CO., Anderson, Ind., U.S.A.

Members American Motor Car Mfrs. Association.